

5/14/99

**CLEARING AND GRUBBING
EROSION CONTROL FOR
CONSTRUCTION SHEET 44**

NOTE:
PLACE TEMPORARY ROCK SEDIMENT DAMS TYPE - B
AND TEMPORARY ROCK SILT CHECKS TYPE - A AT
DRAINAGE OUTLETS.

NOTE:
PERIMETER EROSION CONTROL MEASURES SHALL BE
INSTALLED DURING CLEARING AND GRUBBING PHASE.

NOTE:
CONTRACTOR SHALL PROVIDE GROUND COVER ON
EXPOSED SLOPES IN ACCORDANCE WITH THE "SOIL
STABILIZATION TIMEFRAMES", SEE EC-3.

NOTE:
PRIOR TO INSTALLATION OF EROSION CONTROL DEVICES,
CONTRACTOR SHALL VERIFY BOUNDARIES OF JURISDICTIONAL
AREAS AND DELINEATE WITH SAFETY FENCE OR FLAGGING.

NOTE:
ALL EROSION CONTROL DEVICES SHOWN ARE LOCATED
WITHIN EXISTING RW OR EASEMENT.

PROJECT REFERENCE NO. 1-5987B SHEET NO. EC-45/CONST.44
RW SHEET NO.

ROADSIDE ENVIRONMENTAL PROJECT ENGINEER

LEVEL III CERTIFIED BY:
MATTHEW HARVEY, PE
CERTIFICATION NUMBER: 3487
ISSUED: MARCH 15, 2022

Prepared in the Office of:

M M
MOTT
MACDONALD

PO Box 700
Fuquay-Varina, NC 27526
www.mottmac.com/americas

**ETHERILL
ENGINEERING**

1223 Jones Franklin Rd.
Raleigh, N.C. 27606
License No. 14377
Bus: 919.951.8077
Fax: 919.951.9107



MATCHLINE -Y6- STA. 26 + 00.00 SEE SHEET NO. 25

-Y6-

PI Sta 20+25.89	PI Sta 26+92.85
$\Delta = 4' 58' 32.9''$ (LT)	$\Delta = 1' 54' 45.5''$ (RT)
$D = 0' 30' 58.2''$	$D = 0' 30' 58.2''$
$L = 963.97'$	$L = 370.54'$
$T = 482.29'$	$T = 185.29'$
$R = 11,100.00'$	$R = 11,100.00'$
SE = NC	SE = NC

3/14/2022
Erosion_Control\15987b_EC_PSH_44_CG.dgn
Mott MacDonald