

- 1 INSTALL 3-WIRE COPPER SERVICE ENTRANCE CONDUCTORS
- 2 INSTALL 4-WIRE COPPER FEEDER CONDUCTORS
- 3 INSTALL 3-WIRE COPPER FEEDER CONDUCTORS
- 4 INSTALL SMFO CABLE
- 5 INSTALL CAT 5e CCTV CABLE
- 6 INSTALL FIBER OPTIC DROP CABLE
- 7 INSTALL TRACER WIRE
- 8 TRENCH
- 9 INSTALL PVC CONDUIT
- 10 INSTALL RIGID, GALVANIZED STEEL CONDUIT
- 11 INSTALL RIGID, GALVANIZED STEEL RISER WITH WEATHERHEAD
- 12 INSTALL RIGID, GALVANIZED STEEL RISER WITH HEAT SHRINK TUBING
- 13 INSTALL HEAT SHRINK TUBING RETROFIT KIT
- 14 INSTALL POLYETHYLENE CONDUIT
- 15 DIRECTIONAL DRILL CONDUIT
- 16 BORE AND JACK CONDUIT
- 17 INSTALL CABLE(S) IN EXISTING CONDUIT
- 18 INSTALL CABLE(S) IN NEW CONDUIT
- 19 INSTALL CABLE(S) IN EXISTING RISER
- 20 INSTALL CABLE(S) IN NEW RISER
- 21 INSTALL CABLE(S) IN EXISTING CONDUIT ENTRANCE
- 22 INSTALL NEW CONDUIT INTO NEW CABINET BASE (USE EXISTING CONDUIT STUBOUTS WHEN AVAILABLE)
- 23 INSTALL NEW RISER INTO EXISTING CABINET BASE (USE EXISTING CONDUIT STUBOUTS WHEN AVAILABLE)
- 24 INSTALL NEW CONDUIT INTO POLE MOUNTED CABINET
- 25 INSTALL NEW RISER INTO POLE MOUNTED CABINET

- 26 TERMINATE FIBER-OPTIC CABLE ON INTERCONNECT CENTER IN CCTV EQUIPMENT CABINET
- 27 INSTALL NEW ETHERNET EDGE SWITCH IN CABINET
- 28 INSTALL INTERCONNECT CENTER, PATCH PANEL, JUMPERS, AND FUSION SPLICE CABLE IN CABINET
- 29 INSTALL UNDERGROUND SPLICE ENCLOSURE
- 30 INSTALL AERIAL SPLICE ENCLOSURE
- 31 INSTALL SPLICE CABINET
- 32 MODIFY EXISTING SPLICE ENCLOSURE OR INTERCONNECT CENTER
- 33 REMOVE EXISTING SPLICE CABINET
- 34 INSTALL CABINET FOUNDATION
- 35 REMOVE EXISTING CABINET FOUNDATION
- 36 INSTALL CCTV CAMERA ASSEMBLY
- 37 ITS EQUIPMENT REMOVAL (DMS)
- 38 INSTALL CCTV CAMERA METAL POLE AND FOUNDATION
- 39 INSTALL STANDARD (ELECTRICAL) JUNCTION BOX
- 40 INSTALL OVERSIZED JUNCTION BOX
- 41 INSTALL SPECIAL OVERSIZED JUNCTION BOX
- 42 INSTALL NCDOT SUPPLIED CELL MODEM
- 43 REMOVE EXISTING METAL POLE AND FOUNDATION
- 44 INSTALL AERIAL GUY ASSEMBLY
- 45 INSTALL STANDARD GUY ASSEMBLY
- 46 INSTALL SIDEWALK GUY ASSEMBLY
- 47 INSTALL MESSENGER CABLE
- 48 REMOVE EXISTING COMMUNICATIONS CABLE
- 49 EXISTING SIGNAL CABINET (HUB CONNECTION)
- 50 CONDUITS INSTALLED IN BRIDGE STRUCTURE (SEE ROADWAY PLANS)

- 51 INSTALL CABLE STORAGE RACKS (SNOW SHOES) AND STORE 100 FEET OF CABLE
- 52 INSTALL DELINEATOR MARKERS
- 53 STORE 30 FEET OF COMMUNICATIONS CABLE (EACH CABLE), EXCEPT AS NOTED ON PLANS
- 54 REMOVE EXISTING CABINET
- 55 LASH CABLE(S) TO EXISTING SIGNAL/COMMUNICATIONS CABLE
- 56 LASH CABLES TO NEW MESSENGER CABLE
- 57 MODIFY EXISTING ELECTRICAL SERVICE
- 58 INSTALL NEW ELECTRICAL SERVICE
- 59 BOND TRACER WIRE TO EQUIPMENT GROUND BUS ON ONE END
- 60 BOND MESSENGER TO POLE GROUND
- 61 BOND RISER TO POLE GROUND
- 62 INSTALL DMS, PEDESTAL STRUCTURE, ACCESS LADDER AND DMS FOUNDATION
- 63 INSTALL CCTV FIELD EQUIPMENT CABINET
- 64 INSTALL NEW EQUIPMENT CABINET DISCONNECT
- 65 INSTALL GROUND MOUNTED SHELL CABINET
- 66 INTERCEPT EXISTING JUNCTION BOX
- 67 INSTALL CCTV CAMERA EXTENSION POLE
- 68 INSTALL SOLAR PANEL ASSEMBLY
- 69 REMOVE WOOD POLE
- 70 INSTALL CCTV WOOD POLE
- 71 ITS EQUIPMENT REMOVAL (CCTV)
- 72 INSTALL STEP-UP /STEP-DOWN TRANSFORMER
- 73 INSTALL WOOD POLE

3/11/2022 8:36:05 AM R:\ITS\665\gmp\plan_sheets\I-5987B_ITS_psh_03.dgn

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED



Prepared for the Offices of:		Construction Notes		SEAL	
		Division 6 Robeson County Lumberton		SEAL	
PLAN DATE: March 2022	REVIEWED BY: S.G. Haynie	REVISIONS		INIT.	DATE
PREPARED BY: O. Drobny	REVIEWED BY: J. S. Cole				
DocuSign		Steven G. Haynie		18/2022	
CADD Filename:					