DocuSign Envelope ID: CFAF2891-8AF5-4EC3-B06A-DDC5C37BE5A7

PROJECT REFERENCE NO.	SHEET NO.
I-5987B	ITS-4

LEGEND

- EXISTING COMMUNICATIONS CABLE
- EXISTING COMMUNICATIONS CABLE TO BE REMOVED
- NEW CONDUIT
- EXISTING CONDUIT
- NEW DIRECTIONAL DRILLED CONDUIT
- EXISTING GUARDRAIL
- NEW GUARDRAIL
- NEW CHAIN LINK FENCE
- EXISTING RIGHT OF WAY
- NEW CCTV CAMERA ASSEMBLY
- EXISTING CCTV CAMERA ASSEMBLY
- NEW STANDARD GUY ASSEMBLY
- EXISTING STANDARD GUY ASSEMBLY
- NEW SIGNAL CABINET
- EXISTING SIGNAL CABINET
- NEW ITS EQUIPMENT CABINET
- EXISTING ITS EQUIPMENT CABINET
- NEW SOLAR PANEL ASSEMBLY
- NEW ELECTRICAL SERVICE
- EXISTING ELECTRICAL SERVICE
- SIGNAL POLE
- EXISTING ANTENNA
- CCTV /DMS NUMBER
- SIGNAL INVENTORY NUMBER
- NEW JUNCTION BOX
- EXISTING JUNCTION BOX
- NEW OVERSIZED HEAVY DUTY JUNCTION BOX WITH SPLICE ENCLOSURE
- EXISTING OVERSIZED HEAVY DUTY JUNCTION BOX WITH SPLICE ENCLOSURE
- NEW WOOD POLE
- EXISTING WOOD POLE
- NEW METAL POLE
- EXISTING METAL POLE
- STEP-UP STEP-DOWN TRANSFORMER
- NEW DMS
- EXISTING DMS

CONSTRUCTION NOTE SYMBOLOGY KEY

- NUMBER OF CABLE(S), LOOPS, ETC. — NUMBER OF FIBERS / TWISTED PAIRS PER CABLE, ETC.
- NUMBER OF RISER(S)/CONDUIT(S) — DIAMETER OF RISER(S)/CONDUIT(S) (INCH)
- NUMBER OF DEVICES — NUMBER OF FIBERS
- NUMBER OF CABLES — REMOVE OR MODIFY CABLE

ATTACHMENT POINT

- XXX / YYY — DISTANCE ABOVE INCHES REFERENCE POINT
- YYY / XXX — REFERENCE POINT DISTANCE BELOW INCHES

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

RS&H
NC FIRM LICENSE No: F-0493
8521 SIX FORKS ROAD, SUITE 400
RALEIGH, NC 27615
(919) 926-4100

Prepared for the Offices of:
Transportation Mobility and Safety Division
STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
ITS and Signals Unit
750 N.Greenfield Pkwy,Garner,NC 27529

Construction Note Symbology/ Legend

Division 6 Robeson County Lumberton

PLAN DATE: March 2022	REVIEWED BY: S.G. Haynie
PREPARED BY: O. Drobny	REVIEWED BY: J. S. Cole

REVISIONS	INIT.	DATE

SEAL
NORTH CAROLINA PROFESSIONAL ENGINEER SEAL 029531 STEVEN G. HAYNIE
DocuSigned by: Steven G. Haynie 3/18/2022
DESIGN ENGINEER SIGNATURE DATE
CADD Filename:

3/17/2022
R:\ITS\Design\Plan Sheets\I5987B_ITS_psh_04.dgn
8:36:06 AM