

PROJECT REFERENCE NO.	SHEET NO.
BR-0044	EC-03A
RW SHEET NO.	
<small>Prepared in the Office of:</small> AECOM	
<small>NC FIRM LICENSE No. F-0342 438 Wood Park Boulevard, Suite 200 Raleigh, NC 27607 +1-919-461-0000</small>	

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

SOIL STABILIZATION TIMEFRAMES

<i>SITE DESCRIPTION</i>	<i>STABILIZATION TIME</i>	<i>TIMEFRAME EXCEPTIONS</i>
PERIMETER DIKES, SWALES, DITCHES AND SLOPES	7 DAYS	NONE
HIGH QUALITY WATER (HQW) ZONES	7 DAYS	NONE
SLOPES STEEPER THAN 3:1	7 DAYS	IF SLOPES ARE 10' OR LESS IN LENGTH AND ARE NOT STEEPER THAN 2:1, 14 DAYS ARE ALLOWED.
SLOPES 3:1 OR FLATTER	14 DAYS	7 DAYS FOR SLOPES GREATER THAN 50' IN LENGTH.
ALL OTHER AREAS WITH SLOPES FLATTER THAN 4:1	14 DAYS	NONE, EXCEPT FOR PERIMETERS AND HQW ZONES.

5/14/99

R:\Environment\BR0044\Design\BR0044.REU.EC03A.dgn
3:01:22 PM
REU