PROJ. REFERENCE NO.	SHEET NO.
Y-5500JC	X-1A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR EMBANKMENT

CROSS-SECTION SUMMARY

'NOTE: Appropximate quantities only. Shoulder Borrow, Fine Grading, Clearing and Grubbing, and Removal of Existing Asphalt Pavement will be paid for at the contract Lump Sum price for "Grading".

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
13+25.00	0	0
13+50.00	31	3
14+00.00	32	27
14+50.00	3	96
15+00.00	0	178
15+50.00	0	222
16+00.00	0	249
16+50.00	0	235
17+00.00	5	111
17+50.00	120	9
18+00.00	487	0
18+50.00	960	0
19+00.00	1199	0
19+50.00	1948	0
20+00.00	4303	0
20+50.00	7067	0
21+00.00	8284	0
21+50.00	7981	0
22+00.00	6466	0
22+50.00	4313	0
23+00.00	2263	176
23+50.00	704	956
24+00.00	125	1698
24+50.00	100	1853
25+00.00	147	1491
25+50.00	122	1119
26+00.00	44	819
26+50.00	239	281
27+00.00	454	71
27+50.00	386	127
28+00.00	314	203
28+50.00	200	453
29+00.00	144	509
29+50.00	344	188
30+00.00	440	28
30+50.00	308	185
31+00.00	118	923
31+50.00	0	2322
32+00.00	0	2604
32+50.00	0	1501
33+00.00	0	996
33+50.00	0	2008
34+00.00	0	2960
34+50.00	0	3308
35+00.00	0	4825
35+50.00	0	6102
36+00.00	0	4892
36+50.00	1050	1900
37+00.00	3192	108
37+50.00	5231	0
38+00.00	7136	0
38+50.00	8622	0
39+00.00	8542	0

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
39+50.00	6841	0
40+00.00	4789	0
40+50.00	3064	0
41+00.00	1545	0
41+50.00	420	209
42+00.00	25	848
42+50.00	0	2270
43+00.00	0	3380
43+25.00	0	1748
43+25.00	0	0
43+50.00	0	1256
44+00.00	9	831
44+50.00	252	67
45+00.00	600	0
45+50.00	763	0
46+00.00	744	0
46+50.00	487	0
47+00.00	280	0
47+50.00	224	0
48+00.00	153	0
48+50.00	86	2
49+00.00	44	15
49+50.00	38	42
50+00.00	32	56
50+50.00	11	40
51+00.00	2	17
51+50.00	10	5
52+00.00	24	0
52+50.00	49	0
53+00.00	33	0

Station Y1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+11.05	0	0
10+50.00	62	7
11+00.00	40	12
11+50.00	1	10
12+00.00	3	3
12+50.00	4	0
12+80.00	6	18
13+00.00	3	12
13+50.00	2	1
14+00.00	3	1
14+30.00	4	0
14+50.00	2	1
14+75.00	0	7
15+00.00	1	7
15+50.00	2	4
16+00.00	2	3
16+15.00	1	1
16+50.00	3	1
17+00.00	6	1
17+50.00	6	3
18+00.00	3	69
18+50.00	11	191
18+55.54	2	27

Station Y2	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+11.00	0	0
10+50.00	215	0
11+00.00	213	0
11+40.00	32	1