

8/17/99

REVISIONS



NOTE: PROPOSED PIPE EXTENSIONS AND DROP INLETS ON NORTH SIDE OF MEDIAN SHALL BE SET AT GRADES AND INVERT ELEVATIONS TO ENSURE POSITIVE FLOW TO THE EXISTING DROP INLET. INSTALLATION AT UNIFORM DEPTHS FROM THE EXISTING PAVEMENT SURFACE SHOULD PROVIDE POSITIVE FLOW. PIPE EXTENSION LAYOUT, DROP INLET LOCATIONS, AND PIPE GRADE AND INVERT ELEVATIONS SHALL BE APPROVED BY THE ENGINEER PRIOR TO INSTALLATION.