PROJ. REFERENCE NO.	SHEET NO.
B-5810	X-1A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

Approximate quantities only. Unclassified excavation, borrow excavation, fine grading, clearing and grubbing, and removal of existing pavement will be paid for at the lump sum price for "Grading".

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
16+60.00	0	0
17+00.00	22	6
17+50.00	26	36
18+00.00	27	58
18+50.00	29	41
19+00.00	28	16
19+50.00	25	6
20+00.00	19	6
20+50.00	8	488
20+57.00	0	158

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
25+77.00	0	0
26+00.00	29	107
26+50.00	42	18
26+90.00	13	22
27+00.00	11	3
27+50.00	59	7
28+00.00	24	4
28+25.00	13	0

Station XL	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
13+04.93	0	0
13+50.00	15	27
14+00.00	22	54
14+50.00	28	69
15+00.00	35	59
15+50.00	49	35
16+00.00	34	20
16+50.00	14	10
16+70.60	6	2

Station XL	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
29+54.69	0	0
30+00.00	11	29
30+50.00	14	49
31+00.00	22	44
31+50.00	24	18
31+95.29	18	3