DocuSign Envelope ID: FEC680E6-CB45-4C69-A809-6B6D3CC7F073

PROJECT REFERENCE NO.	SHEET NO.
A-0009CA	EC-3B

ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

SOIL STABILIZATION SUMMARY SHEET

EXCELSIOR DITCHLINE MATTING

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
DITCHLINE EXCELSIOR MATTING					
6	L	27+00	27+50	RT	55
6	DR2	10+42	11+50	LT	55
6	DR2	10+27	11+50	RT	65
7	L	31+50	32+68	RT	125
10	L	68+50	70+50	LT	140
10	L	69+50	71+00	RT	200
10	L	73+50	78+00	RT	590
10	L	81+50	82+00	RT	70
11	L	92+00	94+00	LT	280
11	L	95+50	96+00	RT	85
12	L	96+00	100+50	LT	630
12	L	96+00	99+00	RT	315
12	L	100+00	102+00	RT	280
14	L	131+50	132+00	LT	35
16	L	165+50	166+00	RT	55
18	L	186+00	186+50	RT	35
	EXCELSIOR MATTING SUBTOTAL				3,015
	SLOPE MATTING SUBTOTAL				57,710
	DITCHLINE MATTING SUBTOTAL				3,425
	EXCELSIOR MATTING SUBTOTAL				3,015
MISCELLANEOUS MATTING TO BE INSTALLED AS DIRECTED BY THE ENGINEER					145,000
				TOTAL	209,150
				SAY	209,150

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)