

**This electronic collection of documents is provided
for the convenience of the user
and is Not a Certified Document –**

**The documents contained herein were originally issued
and sealed by the individuals whose names and license
numbers appear on each page, on the dates appearing
with their signature on that page.**

**This file or an individual page
shall not be considered a certified document.**


09, 08, 2019

CONTRACT: C204731 TIP PROJECT: A-0009CA

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS



GRAHAM COUNTY

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	A-0009CA		
STATE PROJ. NO.	F.A. PROJ. NO.	DESCRIPTION	
32572.1.FS10	APD-0074(178)	PE	
32572.2.13	0143012	ROW	
32572.2.16	UNASSIGNED	UTIL.	
32572.3.13	0129007	CONST.	




LOCATION: UPGRADE US 129 FROM SOUTH OF SR 1275 (FIVE POINTS ROAD) TO NC 143 AND UPGRADE NC 143 FROM US 129 TO SR 1223 (BEECH CREEK ROAD)

TYPE OF WORK: GRADING, PAVING, DRAINAGE, CULVERTS, RETAINING WALLS, AND SIGNALS



CULVERTS

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED



DESIGN DATA

ADT 2019 =	6300
ADT 2045 =	8800
K =	11 %
D =	57.5 %
T =	7 % *

50MPH - BEGIN PROJECT TO FIVE POINTS RD
60MPH - FIVE POINTS RD TO END OF PROJECT
* TTST = 2% DUAL = 5%
FUNC CLASS = RURAL ARTERIAL REGIONAL TIER

PROJECT LENGTH

LENGTH ROADWAY TIP PROJECT A-0009CA =	3.720 MILES
LENGTH STRUCTURE TIP PROJECT A-0009CA =	0.007 MILES
TOTAL LENGTH TIP PROJECT A-0009CA =	3.727 MILES


NCDOT CONTACT: WANDA H. AUSTIN, PE

PLANS PREPARED BY: TGS ENGINEERS 201 W. MARION ST SHELBY, NC 28150 PH (704) 476-0003 CORP. LICENSE NO. C-0275	PLANS PREPARED FOR: NORTH CAROLINA DEPARTMENT OF TRANSPORTATION DIVISION 14 252 Webster Rd Sylva, NC 28779
LETTING DATE: AUGUST 16, 2022	MARC CHEEK, PE STRUCTURES DESIGN ENGINEER


2018 STANDARD SPECIFICATIONS

STRUCTURES DESIGN ENGINEER

Marc Cheek, Jr.
7/14/2022 | 10:58 AM EDT



7/14/2022 User:zsm111



INDEX

STR	STATION	DESCRIPTION	SHEET NUMBERS
1	17+34.70 -L-	QUADRUPLE 12 FT.X 12 FT.REINFORCED CONCRETE BOX CULVERT, LEFT & RIGHT HEADWALL/ WING EXTENSIONS	C1-1 THRU C1-5
2	46+41.00 -L-	TRIPLE 12 FT.X 9 FT.REINFORCED CONCRETE BOX CULVERT, LEFT & RIGHT EXTENSIONS	C2-1 THRU C2-14
3	108+27.00 -L-	SINGLE 7 FT.X 8 FT.REINFORCED CONCRETE BOX CULVERT	C3-1 THRU C3-6
4	113+69.00 -L-	TRIPLE 11 FT.X 9.2 FT.REINFORCED CONCRETE BOX CULVERT LEFT EXTENSION	C4-1 THRU C4-8
5	144+74.50 -L-	DOUBLE 66" Ø ALUMINUM PIPE WITH CONCRETE HEADWALLS	C5-1 THRU C5-4
6	195+16.00 -L-	DOUBLE 12 FT.X 8 FT.REINFORCED CONCRETE BOX CULVERT	C6-1 THRU C6-7
7	10+59.00 -DR1A-	SINGLE 16 FT.X 9 FT.REINFORCED CONCRETE BOX CULVERT	C7-1 THRU C7-8
W1,W2	32+55.00 -Y1- TO 34+15.00 -Y1- 11+79.00 -L- TO 12+50.00 -L-	CAST-IN-PLACE GRAVITY RETAINING WALL	W1/W2-1-THRU W1/W2-2
W4	167+75.00 -L- TO 171+75.00 -L-	SHORED MSE RETAINING WALL	W4-1 THRU W4-5
W5	175+35.00 -L- TO 176+65.00 -L-	CAST-IN-PLACE GRAVITY RETAINING WALL	W5-1 THRU W5-2
W6	186+75.00 -L- TO 192+05.00 -L-	SOIL NAIL RETAINING WALL	W6-1 THRU W6-2

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

TGS ENGINEERS
706 HILLSBOROUGH STREET
SUITE 200
RALEIGH, NC 27603
PH (919) 773-8887
CORP. LICENSE NO.: C-0275

PROJECT NO. A-0009CA
GRAHAM COUNTY


STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

INDEX OF SHEETS

DRAWN BY : S.B. WILLIAMS DATE : 2-22
CHECKED BY : MGC DATE : 4-22

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	TOTAL SHEETS
1			3			4
2			4			

BENCH MARK #1: SPIKE NAIL SET IN BASE OF 18" MAPLE; 30 LT. OF STA. 14+27.88 -L-; ELEV. 1993.80



LOCATION SKETCH

FOR UTILITY INFORMATION, SEE UTILITY PLANS AND SPECIAL PROVISIONS.


NOTES:

- FOR OTHER DESIGN DATA AND NOTES, SEE STANDARD NOTES SHEET.
- THE RESIDENT ENGINEER SHALL CHECK THE HEIGHT OF THE HEADWALL AND WING EXTENSIONS BEFORE CONSTRUCTION TO MAKE CERTAIN THAT IT WILL PROPERLY TAKE CARE OF THE FILL.
- DOWELS SHALL BE USED TO CONNECT THE HEADWALL EXTENSION AND THE WING EXTENSIONS TO THE EXISTING CULVERT AS SHOWN. FOR NOTE REGARDING SETTING OF DOWELS, SEE SHEET SN.
- FOR FALSEWORK AND FORMWORK, SEE SPECIAL PROVISIONS.
- FOR SUBMITTAL OF WORKING DRAWINGS, SEE SPECIAL PROVISIONS.
- FOR CRANE SAFETY, SEE SPECIAL PROVISIONS.
- FOR GROUT FOR STRUCTURES, SEE SPECIAL PROVISIONS.
- THE CONTRACTOR SHALL PROVIDE INDEPENDENT ASSURANCE SAMPLES OF REINFORCING STEEL AS FOLLOWS: FOR PROJECTS REQUIRING UP TO 400 TONS OF REINFORCING STEEL, ONE 30 INCH SAMPLE OF EACH SIZE BAR USED, AND FOR PROJECTS REQUIRING OVER 400 TONS OF REINFORCING STEEL, TWO 30 INCH SAMPLES OF EACH SIZE BAR USED. THE SAMPLE BARS SHOULD COME FROM STEEL ACTUALLY USED IN THE PROJECT AND THE SAMPLE BARS SHOULD BE REPLACED BY SPICED BARS AS SPECIFIED IN THE SAMPLE BAR REPLACEMENT CHART. PAYMENT FOR THE SAMPLE BARS AND REPLACEMENT REINFORCING STEEL SHALL BE CONSIDERED INCIDENTAL TO VARIOUS PAY ITEMS.

F.A. PROJECT NO. : APD-0074(178)

TOTAL STRUCTURE QUANTITIES

CLASS A CONCRETE	
INLET HEADWALL & WING EXTENSIONS	8.8 C.Y.
OUTLET HEADWALL & WING EXTENSIONS	4.0 C.Y.
TOTAL	12.8 C.Y.
REINFORCING STEEL	
INLET HEADWALL & WING EXTENSIONS	737 LBS.
OUTLET HEADWALL & WING EXTENSIONS	456 LBS.
TOTAL	1,193 LBS.



CULVERT LAYOUT


HYDRAULIC DATA	
DESIGN DISCHARGE	= 5,080 CFS
FREQUENCY OF DESIGN FLOOD	= 50 YRS
DESIGN HIGH WATER ELEVATION	= 1988.0'
BASE DISCHARGE (Q100)	= 6080 CFS
BASE HIGH WATER ELEVATION	= 1989.4'
OVERTOPPING FLOOD DATA	
OVERTOPPING DISCHARGE	= 8850+ CFS
FREQUENCY OF OVERTOPPING FLOOD	= 500+ YRS
OVERTOPPING FLOOD ELEVATION	= 1994.0'

SAMPLE BAR REPLACEMENT	
SIZE	LENGTH
#3	6'-2"
#4	7'-4"
#5	8'-6"
#6	9'-8"
#7	10'-10"
#8	12'-0"
#9	13'-2"
#10	14'-6"
#11	15'-10"

NOTE:
SAMPLE BAR REPLACEMENT LENGTHS BASED ON 30" (SAMPLE LENGTH) PLUS TWO SPLICE LENGTHS AND f_y = 60ksi.

PROJECT NO. A-0009CA
GRAHAM COUNTY
STATION: 17+34.70 -L-

SHEET 1 OF 5 STRUCTURE NO. 370134



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH


QUADRUPLE 12FT. x 12FT.
CONCRETE BOX CULVERT
110° SKEW

DRAWN BY : ZCS DATE : 1/21
CHECKED BY : MGC DATE : 4/22
DESIGN ENGINEER OF RECORD : ZCS DATE : 4/22


DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

TGS ENGINEERS
804-C N. LAFAYETTE ST
SHELBY, NC 28150
PH (704) 476-0003
CORP. LICENSE NO.: C-0275


REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	C1-1
1			3			TOTAL SHEETS
2			4			5



ELEVATION OF HEADWALL & WING EXTENSIONS - INLET END



SECTION A-A



PLAN OF HEADWALL & WING EXTENSIONS - INLET END

PROJECT NO. A-0009CA
GRAHAM COUNTY
 STATION: 17+34.70 -L-


SHEET 2 OF 5




STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
**VERTICAL EXTENSION
 OF EXISTING
 INLET
 HEADWALL**

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED						REVISIONS			SHEET NO.			
TGS ENGINEERS 804-C N. LAFAYETTE ST SHELBY, NC 28150 PH (704) 476-0003 CORP. LICENSE NO.: C-0275						NO.	BY:	DATE:	NO.	BY:	DATE:	C1-2
						1			3			TOTAL SHEETS
						2			4			5

DRAWN BY : ZCS DATE : 1/21
 CHECKED BY : MGC DATE : 4/22
 DESIGN ENGINEER OF RECORD : ZCS DATE : 4/22




SECTION B-B




BILL OF MATERIAL FOR EXISTING INLET HEADWALL EXTENSION					
BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
H1	12	#4	STR	28'-4"	227
U1	55	#4	1	5'-11"	217
REINFORCING STEEL				444 LBS	
CLASS A CONCRETE HEADWALL EXTENSION				5.7 CY	
TOTAL				5.7 CY	

BILL OF MATERIAL FOR EXISTING WING W1 EXTENSION					
BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
H2	6	#4	STR	21'-5"	86
U2	21	#4	1	5'-8"	79
REINFORCING STEEL				165 LBS	
CLASS A CONCRETE WING EXTENSION				1.8 CY	
TOTAL				1.8 CY	

BILL OF MATERIAL FOR EXISTING WING W2 EXTENSION					
BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
H3	6	#4	STR	16'-8"	67
U2	16	#4	1	5'-8"	61
REINFORCING STEEL				128 LBS	
CLASS A CONCRETE WING EXTENSION				1.3 CY	
TOTAL				1.3 CY	




ELEVATION W1



ELEVATION W2

PROJECT NO. A-0009CA
GRAHAM COUNTY
 STATION: 17+34.70 -L-

SHEET 3 OF 5



STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

INLET END
 WING EXTENSIONS
 WINGS 1 & 2


DRAWN BY : ZCS DATE : 1/21
 CHECKED BY : MGC DATE : 4/22
 DESIGN ENGINEER OF RECORD : ZCS DATE : 4/22

DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED


TGS ENGINEERS
 804-C N. LAFAYETTE ST
 SHELBY, NC 28150
 PH (704) 476-0003
 CORP. LICENSE NO.: C-0275

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			C1-3
2			4			TOTAL SHEETS 5


STR, #1



ELEVATION OF HEADWALL & WING EXTENSIONS - OUTLET END



SECTION C-C



PLAN OF HEADWALL & WING EXTENSIONS - OUTLET END

PROJECT NO. A-0009CA
GRAHAM COUNTY
 STATION: 17+34.70 -L-


SHEET 4 OF 5

6/1/2022


DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED
TGS ENGINEERS
 804-C N. LAFAYETTE ST
 SHELBY, NC 28150
 PH (704) 476-0003
 CORP. LICENSE NO.: C-0275

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH					
VERTICAL EXTENSION OF EXISTING OUTLET HEADWALL					
REVISIONS					SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:
1			3		
2			4		
					C1-4
					TOTAL SHEETS 5

DRAWN BY : ZCS DATE : 1/21
 CHECKED BY : MGC DATE : 4/22
 DESIGN ENGINEER OF RECORD : ZCS DATE : 4/22



SECTION D-D



BILL OF MATERIAL FOR EXISTING OUTLET HEADWALL EXTENSION


BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
H1	8	#4	STR	28'-4"	151
U3	55	#4	1	3'-5"	126
REINFORCING STEEL					277 LBS
CLASS A CONCRETE HEADWALL EXTENSION					2.6 CY
TOTAL					2.6 CY

BILL OF MATERIAL FOR EXISTING WING W3 EXTENSION


BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
H4	4	#4	STR	16'-8"	45
U4	16	#4	1	3'-2"	34
REINFORCING STEEL					79 LBS
CLASS A CONCRETE WING EXTENSION					0.6 CY
TOTAL					0.6 CY

BILL OF MATERIAL FOR EXISTING WING W4 EXTENSION

BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
H5	4	#4	STR	21'-1"	56
U4	21	#4	1	3'-2"	44
REINFORCING STEEL					100 LBS
CLASS A CONCRETE WING EXTENSION					0.8 CY
TOTAL					0.8 CY



ELEVATION W4



ELEVATION W3

PROJECT NO. A-0009CA
GRAHAM COUNTY
 STATION: 17+34.70 -L-

SHEET 5 OF 5

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

OUTLET END WING EXTENSIONS WINGS 3 & 4

6/1/2022


DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

TGS ENGINEERS
 804-C N. LAFAYETTE ST
 SHELBY, NC 28150
 PH (704) 476-0003
 CORP. LICENSE NO.: C-0275

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			C1-5
2			4			TOTAL SHEETS 5

DRAWN BY : ZCS DATE : 1/21
 CHECKED BY : MGC DATE : 4/22
 DESIGN ENGINEER OF RECORD : ZCS DATE : 4/22

BENCH MARK #3: STA. 48+93.40 -L- 56' RT. ELEV. 2016.23'
SPIKE NAIL IN BASE OF 10" POPLAR



LOCATION SKETCH

TOTAL STRUCTURE QUANTITIES	
CLASS A CONCRETE	
LEFT EXTENSION	118.3 C.Y.
RIGHT EXTENSION	202.4 C.Y.
TOTAL	320.7 C.Y.
REINFORCING STEEL	
LEFT EXTENSION	15,495 LBS
RIGHT EXTENSION	27,074 LBS
TOTAL	42,569 LBS
CULVERT EXCAVATION LUMP SUM	
FOUNDATION COND. MAT'L.	
LEFT EXTENSION	59 TONS
RIGHT EXTENSION	130 TONS
TOTAL	189 TONS


SAMPLE BAR REPLACEMENT	
SIZE	LENGTH
#3	6'-2"
#4	7'-4"
#5	8'-6"
#6	9'-8"
#7	10'-10"
#8	12'-0"
#9	13'-2"
#10	14'-6"
#11	15'-10"

NOTE:
SAMPLE BAR REPLACEMENT LENGTHS BASED ON 30" (SAMPLE LENGTH) PLUS TWO SPLICE LENGTHS AND $f_y = 60\text{ksi}$.


ROADWAY DATA	
GRADE POINT ELEV. @ STA. 46+41.00 -L-	= 2017.48'
BED ELEV. @ STA. 46+41.00 -L-	= 1997.17' ±
ROADWAY SLOPES	= 1.5 : 1
HYDROGRAPHIC DATA	
DESIGN DISCHARGE	= 3210 CFS
FREQUENCY OF DESIGN FLOOD	= 50 YRS
DESIGN HIGH WATER ELEVATION	= 2009.5'
DRAINAGE AREA	= 13.7 SQ. MI.
BASE DISCHARGE (Q100)	= 3870 CFS
BASE HIGH WATER ELEVATION	= 2011.2'
OVERTOPPING FLOOD DATA	
OVERTOPPING DISCHARGE	= 5720 CFS
FREQUENCY OF OVERTOPPING FLOOD	= 500 YRS
OVERTOPPING FLOOD ELEVATION	= 2017.44'

NOTES:

- ASSUMED LIVE LOAD ----- HL-93 OR ALTERNATE LOADING.
- DESIGN FILL----- 10.05' MAX.
- FOR OTHER DESIGN DATA AND NOTES, SEE STANDARD NOTES SHEET.
- 3" Ø WEEP HOLES INDICATED TO BE IN ACCORDANCE WITH THE SPECIFICATIONS.
- CONCRETE IN CULVERTS TO BE POURED IN THE FOLLOWING ORDER:
 - PHASE I WING FOOTINGS AND FLOOR SLAB INCLUDING 4" OF ALL VERTICAL WALLS.
 - THE REMAINING PORTIONS OF PHASE I WALLS AND PHASE I WINGS FULL HEIGHT.
 - PHASE II WING FOOTINGS AND FLOOR SLAB INCLUDING 4" OF PHASE II VERTICAL WALLS.
 - THE REMAINING PORTIONS OF PHASE II WALLS AND PHASE II WINGS FULL HEIGHT.
 - ROOF SLAB AND HEADWALLS.
- THE RESIDENT ENGINEER SHALL CHECK THE LENGTH OF CULVERT BEFORE STAKING IT OUT TO MAKE CERTAIN THAT IT WILL PROPERLY TAKE CARE OF THE FILL.
- DIMENSIONS FOR WING LAYOUT AS WELL AS ADDITIONAL REINFORCING STEEL EMBEDDED IN BARREL ARE SHOWN ON WING SHEET.
- AT THE CONTRACTOR'S OPTION, HE MAY SPLICE THE VERTICAL REINFORCING STEEL IN THE INTERIOR FACE OF EXTERIOR WALL ABOVE LOWER WALL CONSTRUCTION JOINT. THE SPLICE LENGTH SHALL BE AS PROVIDED IN THE SPLICE LENGTH CHART SHOWN ON THE PLANS. EXTRA WEIGHT OF STEEL DUE TO THE SPLICES SHALL BE PAID FOR BY THE CONTRACTOR.
- FOR CULVERT DIVERSION DETAILS AND PAY ITEM, SEE EROSION CONTROL PLANS.
- FOR CRANE SAFETY, SEE SPECIAL PROVISIONS.
- FOR SUBMITTAL OF WORKING DRAWINGS, SEE SPECIAL PROVISIONS.
- FOR FALSEWORK AND FORMWORK, SEE SPECIAL PROVISIONS.
- FOR GROUT FOR STRUCTURES, SEE SPECIAL PROVISIONS.
- FOR EROSION CONTROL MEASURES, SEE EROSION CONTROL PLANS.
- IF APPROVED BY THE ENGINEER, THE CONTRACTOR MAY USE THE EXISTING WINGS AS TEMPORARY SHORING FOR THE CONSTRUCTION OF THE CULVERT EXTENSION. IN THIS CASE, THE BOTTOM SLAB OF THE EXTENSION SHALL BE POURED AT LEAST 72 HOURS PRIOR TO CUTTING THE WINGS. THE WINGS MAY BE CUT EARLIER PROVIDED THE SLAB CONCRETE STRENGTH HAS REACHED A MINIMUM COMPRESSIVE STRENGTH OF 1500 PSI.
- AT THE CONTRACTOR'S OPTION HE MAY SUBMIT, TO THE ENGINEER FOR APPROVAL, DESIGN AND DETAIL DRAWINGS FOR A PRECAST REINFORCED CONCRETE BOX CULVERT IN LIEU OF THE CAST-IN-PLACE CULVERT SHOWN ON THE PLANS. THE DESIGN SHALL PROVIDE THE SAME SIZE AND NUMBER OF BARRELS AS USED ON THE CAST-IN-PLACE DESIGN. FOR OPTIONAL PRECAST REINFORCED CONCRETE BOX CULVERT, SEE SPECIAL PROVISIONS.
- THE CONTRACTOR SHALL PROVIDE INDEPENDENT ASSURANCE SAMPLES OF REINFORCING STEEL AS FOLLOWS: FOR PROJECTS REQUIRING UP TO 400 TONS OF REINFORCING STEEL, ONE 30 INCH SAMPLE OF EACH SIZE BAR USED, AND FOR PROJECTS REQUIRING OVER 400 TONS OF REINFORCING STEEL, TWO 30 INCH SAMPLES OF EACH SIZE BAR USED. THE SAMPLE BARS SHOULD COME FROM STEEL ACTUALLY USED IN THE PROJECT AND THE SAMPLE BARS SHOULD BE REPLACED BY SPICED BARS AS SPECIFIED IN THE SAMPLE BAR REPLACEMENT CHART. PAYMENT FOR THE SAMPLE BARS AND REPLACEMENT REINFORCING STEEL SHALL BE CONSIDERED INCIDENTAL TO VARIOUS PAY ITEMS.
- EXCAVATE 1 FOOT BELOW CULVERT AND REPLACE WITH FOUNDATION CONDITIONING MATERIAL IN ACCORDANCE WITH ARTICLE 414-4 OF THE STANDARD SPECIFICATIONS. FOUNDATION CONDITIONING MATERIAL SHOULD CONSIST OF SELECT MATERIAL CLASS V OR VI FOR RCBC.
- IF REQUIRED, UNDERCUT LOOSE SOILS THAT MAY BE ENCOUNTERED BENEATH THE BOTTOM OF THE FOUNDATION CONDITIONING MATERIAL. BACKFILL UNDERCUT AREAS WITH FOUNDATION CONDITIONING MATERIAL.
- DOWELS SHALL BE USED TO CONNECT THE PROPOSED EXTENSIONS TO THE EXISTING CULVERT. FOR NOTE REGARDING SETTING OF DOWELS, SEE SHEET SN.



PROFILE ALONG Q CULVERT




CONSTRUCTION PHASING

(LOOKING DOWNSTREAM)

- PHASE I CONSTRUCTION
- ▨ PHASE II CONSTRUCTION

PROJECT NO. A-0009CA
GRAHAM COUNTY
STATION: 46+41.00 -L-
SHEET 1 OF 14



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH
TRIPLE 12 FT. X 9 FT.
CONCRETE BOX CULVERT
LT & RT EXTENSION
45°-10'-48" SKEW

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED				REVISIONS			SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	C2-1	
1			3			TOTAL SHEETS	
2			4			14	

DRAWN BY :	STM	DATE :	04/21
CHECKED BY :	MGC	DATE :	02/22
DESIGN ENGINEER OF RECORD:	STM	DATE :	04/21

LOAD AND RESISTANCE FACTOR RATING (LRFR) SUMMARY FOR REINFORCED CONCRETE BOX CULVERTS

LEVEL	VEHICLE	WEIGHT (W) (TONS)	CONTROLLING LOAD RATING #	MINIMUM RATING FACTORS (RF)	TONS = W x RF	STRENGTH I LIMIT STATE								COMMENT NUMBER		
						LIVE-LOAD FACTORS (LL)	MOMENT				SHEAR					
							RATING FACTOR	BOX NO.	ELEMENT TYPE	DISTANCE FROM LEFT END OF ELEMENT (ft)	RATING FACTOR	BOX NO.	ELEMENT TYPE		DISTANCE FROM LEFT END OF ELEMENT (ft)	
DESIGN LOAD RATING	HL-93 (INVENTORY)	N/A	①	1.15	--	1.75	1.15	1	EXTERIOR WALL	0.75	2.20	1	EXTERIOR WALL	0.75		
	HL-93 (OPERATING)	N/A		1.48	--	1.35	1.48	1	EXTERIOR WALL	0.75	2.86	1	EXTERIOR WALL	0.75		
	HS-20 (INVENTORY)	36.000	②	1.16	41.76	1.75	1.16	1	EXTERIOR WALL	0.75	2.21	1	EXTERIOR WALL	0.75		
	HS-20 (OPERATING)	36.000		1.51	54.36	1.35	1.51	1	EXTERIOR WALL	0.75	2.87	1	EXTERIOR WALL	0.75		
LEGAL LOAD RATING	SINGLE VEHICLE (SV)	SNSH	13.500		1.53	20.66	1.40	1.53	1	EXTERIOR WALL	0.75	2.89	1	EXTERIOR WALL	0.75	
		SNGARBS2	20.000		1.45	29.00	1.40	1.45	1	EXTERIOR WALL	0.75	2.86	1	EXTERIOR WALL	0.75	
		SNAGRIS2	22.000		1.42	31.24	1.40	1.42	1	EXTERIOR WALL	0.75	2.87	1	EXTERIOR WALL	0.75	
		SNCOTTS3	27.250		1.43	38.97	1.40	1.43	1	EXTERIOR WALL	0.75	2.75	1	EXTERIOR WALL	0.75	
		SNAGGRS4	34.925		1.44	50.29	1.40	1.44	1	EXTERIOR WALL	0.75	2.27	1	TOP SLAB	11.67	
		SNS5A	35.550		1.45	51.55	1.40	1.45	1	EXTERIOR WALL	0.75	2.38	1	TOP SLAB	11.67	
		SNS6A	39.950		1.43	57.13	1.40	1.43	1	EXTERIOR WALL	0.75	2.33	1	TOP SLAB	11.67	
		SNS7B	42.000		1.39	58.38	1.40	1.39	1	EXTERIOR WALL	0.75	2.26	1	TOP SLAB	11.67	
	TRUCK TRACTOR SEMI-TRAILER (TTST)	TNAGRIT3	33.000		1.43	47.19	1.40	1.43	1	EXTERIOR WALL	0.75	2.82	1	EXTERIOR WALL	0.75	
		TNT4A	33.075		1.44	47.63	1.40	1.44	1	EXTERIOR WALL	0.75	2.70	1	TOP SLAB	11.67	
		TNT6A	41.600		1.43	59.49	1.40	1.43	1	EXTERIOR WALL	0.75	2.46	1	TOP SLAB	11.67	
		TNT7A	42.000		1.41	59.22	1.40	1.41	1	EXTERIOR WALL	0.75	2.66	1	TOP SLAB	11.67	
		TNT7B	42.000		1.44	60.48	1.40	1.44	1	EXTERIOR WALL	0.75	2.38	1	TOP SLAB	11.67	
		TNAGRIT4	43.000		1.43	61.49	1.40	1.43	1	EXTERIOR WALL	0.75	2.31	1	TOP SLAB	11.67	
TNAGT5A	45.000	③	1.38	62.10	1.40	1.38	1	EXTERIOR WALL	0.75	2.43	1	TOP SLAB	11.67			
TNAGT5B	45.000		1.42	63.90	1.40	1.42	1	EXTERIOR WALL	0.75	2.14	1	TOP SLAB	11.67			

LOAD FACTORS:

DESIGN LOAD RATING FACTORS

LOAD TYPE	MAX FACTOR	MIN FACTOR
DC	1.25	0.90
DW	1.50	0.65
EV	1.30	0.90
EH	1.35	0.90
ES	1.35	0.90
LS	1.75	--
WA	1.00	--

NOTE:

RATING FACTORS ARE BASED ON THE STRENGTH I LIMIT STATE.

COMMENTS:

- 1.
- 2.
- 3.
- 4.


CONTROLLING LOAD RATING

① DESIGN LOAD RATING (HL-93)

② DESIGN LOAD RATING (HS-20)

③ LEGAL LOAD RATING **


** SEE CHART FOR VEHICLE TYPE



LRFR SUMMARY
(LOOKING DOWNSTREAM)

PROJECT NO. A-0009CA
GRAHAM COUNTY
 STATION: 46+41.00 -L-

SHEET 2 OF 14




STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
 STANDARD
 LRFR SUMMARY FOR
 REINFORCED CONCRETE
 BOX CULVERT

ASSEMBLED BY : STM	DATE : 12/21
CHECKED BY : MGC	DATE : 02/22
DRAWN BY : WMC	7/11
CHECKED BY : GM	7/11
REV. 10/1/11	MAA/GM
REV. 12/17	MAA/THC


DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

TGS ENGINEERS
 706 HILLSBOROUGH STREET
 SUITE 200
 RALEIGH, NC 27603
 PH (919) 773-8887
 CORP. LICENSE NO.: C-0275


REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	C2-2
1			3			TOTAL SHEETS
2			4			14



DETAIL
CONNECTION OF WING FOOTING AND FLOOR SLAB WHEN SLAB IS THICKER THAN FOOTING





OUTLET END ELEVATION NORMAL TO SKEW



RIGHT ANGLE SECTION OF BARREL

THERE ARE 138 "C" BARS IN SECTION OF BARREL. (LOOKING DOWNSTREAM)






PLAN OF FLOOR SLAB

NOTE: FOR S1 IN FLOOR SLAB & WING FOOTINGS, SEE WING SHEET.
FOR DOWELS IN EXTERIOR WALLS, SEE SHEET 3 OF 14.

PROJECT NO. A-0009CA
GRAHAM COUNTY
STATION: 46+41.00 -L-

SHEET 4 OF 14




STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH
**TRIPLE 12 FT. X 9 FT.
CONCRETE BOX CULVERT
LEFT EXTENSION
45°-10'-48" SKEW**

DRAWN BY : STM DATE : 11/21
CHECKED BY : MGC DATE : 02/22
DESIGN ENGINEER OF RECORD: STM DATE : 04/21

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED
TGS ENGINEERS
706 HILLSBOROUGH STREET
SUITE 200
RALEIGH, NC 27603
PH (919) 773-8887
CORP. LICENSE NO.: C-0275

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	C2-4
1			3			TOTAL SHEETS
2			4			14



PLAN OF ROOF SLAB

PROJECT NO. A-0009CA
GRAHAM COUNTY
 STATION: 46+41.00 -L-

SHEET 5 OF 14



STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
**TRIPLE 12 FT. X 9 FT.
 CONCRETE BOX CULVERT
 LEFT EXTENSION
 45°-10'-48" SKEW**

DRAWN BY : STM DATE : 11/21
 CHECKED BY : MGC DATE : 02/22
 DESIGN ENGINEER OF RECORD: STM DATE : 04/21

DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED


TGS ENGINEERS
 706 HILLSBOROUGH STREET
 SUITE 200
 RALEIGH, NC 27603
 PH (919) 773-8887
 CORP. LICENSE NO.: C-0275

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	C2-5
1			3			TOTAL SHEETS
2			4			14

BAR SCHEDULE

BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT	BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT	BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT	BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT	BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
A1	58	#5	5	7'-1"	428	A200	17	#6	STR	19'-0"	485	A300	29	#6	STR	19'-0"	828	A400	17	#6	STR	19'-0"	485	B1	58	#4	STR	11'-0"	426
A2	136	#4	5	6'-9"	613																			B2	58	#4	STR	8'-4"	323
						A201	2	#6	STR	17'-11"	54	A301	4	#6	STR	17'-11"	108	A401	2	#6	STR	17'-11"	54	B3	78	#4	STR	11'-0"	573
A100	29	#6	STR	19'-0"	828	A202	2	#6	STR	16'-6"	50	A302	4	#6	STR	16'-6"	99	A402	2	#6	STR	16'-6"	50						
						A203	2	#6	STR	15'-2"	46	A303	4	#6	STR	15'-2"	91	A403	2	#6	STR	15'-2"	46	C1	138	#4	STR	19'-2"	1767
A101	4	#6	STR	17'-11"	108	A204	2	#6	STR	13'-10"	42	A304	4	#6	STR	13'-10"	83	A404	2	#6	STR	13'-10"	42						
A102	4	#6	STR	16'-6"	99	A205	2	#6	STR	12'-6"	38	A305	4	#6	STR	12'-6"	75	A405	2	#6	STR	12'-6"	38	D1	64	#6	STR	2'-6"	240
A103	4	#6	STR	15'-2"	91	A206	2	#6	STR	11'-2"	34	A306	4	#6	STR	11'-2"	67	A406	2	#6	STR	11'-2"	34						
A104	4	#6	STR	13'-10"	83	A207	2	#6	STR	9'-10"	30	A307	4	#6	STR	9'-10"	59	A407	2	#6	STR	9'-10"	30	G1	4	#5	STR	54'-6"	227
A105	4	#6	STR	12'-6"	75	A208	2	#6	STR	8'-6"	26	A308	4	#6	STR	8'-6"	51	A408	2	#6	STR	8'-6"	26						
A106	4	#6	STR	11'-2"	67	A209	2	#6	STR	7'-2"	22	A309	4	#6	STR	7'-2"	43	A409	2	#6	STR	7'-2"	22	S2	3	#8	STR	42'-3"	338
A107	4	#6	STR	9'-10"	59	A210	2	#6	STR	5'-10"	18	A310	4	#6	STR	5'-10"	35	A410	2	#6	STR	5'-10"	18	S3	3	#8	STR	16'-0"	128
A108	4	#6	STR	8'-6"	51	A211	2	#6	STR	4'-6"	14	A311	4	#6	STR	4'-6"	27	A411	2	#6	STR	4'-6"	14	S4	6	#6	STR	42'-5"	382
A109	4	#6	STR	7'-2"	43	A212	2	#6	STR	3'-2"	10	A312	4	#6	STR	3'-2"	19	A412	2	#6	STR	3'-2"	10	S5	6	#6	STR	16'-0"	144
A110	4	#6	STR	5'-10"	35	A213	2	#6	STR	17'-8"	53							A413	2	#6	STR	17'-8"	53	S6	3	#8	STR	54'-6"	437
A111	4	#6	STR	4'-6"	27	A214	2	#6	STR	16'-4"	49							A414	2	#6	STR	16'-4"	49	S7	6	#6	STR	54'-6"	491
A112	4	#6	STR	3'-2"	19	A215	2	#6	STR	15'-0"	45							A415	2	#6	STR	15'-0"	45						
						A216	2	#6	STR	13'-8"	41							A416	2	#6	STR	13'-8"	41						
						A217	2	#6	STR	12'-4"	37							A417	2	#6	STR	12'-4"	37						
						A218	2	#6	STR	11'-0"	33							A418	2	#6	STR	11'-0"	33						
						A219	2	#6	STR	9'-7"	29							A419	2	#6	STR	9'-7"	29						
						A220	2	#6	STR	8'-3"	25							A420	2	#6	STR	8'-3"	25						
						A221	2	#6	STR	6'-11"	21							A421	2	#6	STR	6'-11"	21						
						A222	2	#6	STR	5'-7"	17							A422	2	#6	STR	5'-7"	17						
						A223	2	#6	STR	4'-3"	13							A423	2	#6	STR	4'-3"	13						
						A250	12	#6	STR	11'-5"	206							A450	12	#6	STR	11'-5"	206						
						A251	4	#6	STR	10'-1"	61							A451	4	#6	STR	10'-1"	61						
						A252	4	#6	STR	8'-9"	53							A452	4	#6	STR	8'-9"	53						
						A253	4	#6	STR	7'-5"	45							A453	4	#6	STR	7'-5"	45						
						A254	4	#6	STR	6'-1"	37							A454	4	#6	STR	6'-1"	37						
						A255	4	#6	STR	4'-9"	29							A455	4	#6	STR	4'-9"	29						
						A256	4	#6	STR	3'-5"	21							A456	4	#6	STR	3'-5"	21						

REINFORCING STEEL 13,055 LBS



LEFT EXTENSION QUANTITIES	
CLASS A CONCRETE	
BARREL @ 4.50 CY/FT	87.8 C.Y.
WINGS, ETC.	26.4 C.Y.
EDGE BEAMS	4.1 C.Y.
TOTAL	118.3 C.Y.
REINFORCING STEEL	
BARREL	13,055 LBS.
WINGS, ETC.	2,440 LBS.
TOTAL	15,495 LBS.
CULVERT EXCAVATION	LUMP SUM
FOUNDATION COND. MAT'L.	59 TONS

PROJECT NO. A-0009CA
GRAHAM COUNTY
 STATION: 46+41.00 -L-

SHEET 6 OF 14


STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

TRIPLE 12 FT. X 9 FT.
 CONCRETE BOX CULVERT
 LEFT EXTENSION
 45°-10'-48" SKEW

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED


REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			C2-6
2			4			TOTAL SHEETS 14

DRAWN BY : STM DATE : 04/21
 CHECKED BY : MGC DATE : 02/22
 DESIGN ENGINEER OF RECORD: STM DATE : 04/21




PLAN W1


* CENTER ALL #6 C1 ON C COUNTERFORT




PLAN W2




ELEVATION W1



ELEVATION W2




WING SECTION



SECTION A-A


STANDARD REINFORCING STEEL IN BARREL NOT SHOWN



SECTION B-B

BILL OF MATERIAL					
BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
B1	2	#4	STR	10'-0"	13
C1	14	#6	STR	9'-0"	189
H6	8	#4	STR	17'-10"	95
H7	2	#4	STR	13'-5"	18
H8	2	#4	STR	7'-6"	10
H9	14	#4	1	3'-3"	30
H10	2	#4	STR	18'-5"	25
M1	5	#8	2	16'-4"	218
N5	3	#4	3	7'-2"	14
N6	3	#5	3	7'-11"	25
N7	4	#5	3	8'-8"	36
N8	4	#5	3	9'-8"	40
N9	4	#6	3	10'-8"	64
N10	2	#6	3	11'-6"	35
P1	2	#9	4	7'-3"	49
P2	2	#9	5	13'-2"	90
S2	1	#4	6	11'-9"	8
S3	1	#4	6	11'-1"	7
S4	1	#4	6	10'-5"	7
S5	1	#4	6	9'-9"	7
S6	1	#4	6	9'-1"	6
S7	1	#4	6	8'-3"	6
S8	1	#4	6	7'-7"	5
S9	1	#4	6	6'-11"	5
S10	1	#4	6	6'-3"	4
T2	4	#5	STR	19'-8"	82
T3	2	#5	STR	13'-0"	27
V5	3	#4	STR	5'-1"	10
V6	3	#4	STR	5'-9"	12
V7	4	#4	STR	6'-6"	17
V8	4	#4	STR	7'-5"	20
V9	4	#4	STR	8'-5"	22
V10	2	#4	STR	9'-4"	12
V11	2	#4	STR	3'-0"	4
V12	2	#4	STR	7'-3"	10
Z4	3	#4	7	3'-6"	7
Z5	3	#4	7	4'-3"	9
Z6	4	#5	7	5'-1"	21
Z7	4	#5	7	6'-1"	25
Z8	4	#8	7	7'-6"	80
Z9	5	#10	7	9'-1"	195
Z10	5	#10	STR	10'-1"	217
Z11	5	#10	STR	9'-4"	201
Z12	4	#10	STR	8'-7"	148
REINFORCING STEEL FOR 1 W1 WING					2,125 LBS.

LONG WING W1



DIMENSIONS ARE OUT TO OUT

BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
H1	8	#4	STR	6'-1"	33
H2	2	#4	STR	4'-2"	6
H3	2	#4	STR	1'-11"	3
H4	14	#4	1	3'-3"	30
H5	2	#4	STR	9'-1"	12
N1	2	#6	3	11'-5"	34
N2	2	#6	3	10'-3"	31
N3	2	#5	3	8'-11"	19
N4	3	#4	3	7'-0"	14
S1	3	#6	STR	6'-0"	27
T1	3	#5	STR	8'-0"	25
V1	2	#4	STR	9'-2"	12
V2	2	#4	STR	7'-11"	11
V3	2	#4	STR	6'-8"	9
V4	3	#4	STR	4'-10"	10
Z1	2	#5	7	6'-3"	13
Z2	3	#5	7	4'-10"	15
Z3	3	#5	7	3'-6"	11
REINFORCING STEEL FOR 1 W2 WING					315 LBS.

SHORT WING W2

NOTES

A 3 FOOT STRIP OF FILTER FABRIC SHALL BE ATTACHED TO THE FILL FACE OF THE WING COVERING THE ENTIRE LENGTH OF THE EXPANSION JOINT.
G1 BARS IN HEADWALL ARE INCLUDED WITH THE BARREL REINFORCING STEEL.

WING QUANTITIES	
REINFORCING STEEL FOR 2 WINGS	2,440 LBS.
CLASS A CONCRETE	
2 WINGS	20.8 C.Y.
1 END CURTAIN WALL	3.1 C.Y.
1 HEADWALL	2.5 C.Y.
TOTAL	26.4 C.Y.

PROJECT NO. A-0009CA
GRAHAM COUNTY
 STATION: 46+41.00 -L-

SHEET 7 OF 14

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

TGS ENGINEERS
 706 HILLSBOROUGH STREET
 SUITE 200
 RALEIGH, NC 27603
 PH (919) 773-8887
 CORP. LICENSE NO.: C-0275


Professional Engineer
 Marshall G. Cheek, Jr.
 SEAL 20125
 6/1/2022

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH


WINGS FOR LEFT EXTENSION
 H = 9'-0" SLOPE = 1.5:1
 45° SKEW

REVISIONS		SHEET NO.
NO.	DATE	C2-7
1		TOTAL SHEETS
2		14


ASSEMBLED BY : STM DATE : 09/21
 CHECKED BY : MGC DATE : 02/22



CULVERT EXTENSION SECTION NORMAL TO ROADWAY




INLET END ELEVATION



RIGHT ANGLE SECTION OF BARREL


THERE ARE 138 "C" IN SECTION OF BARREL. (LOOKING DOWNSTREAM)



CONNECTION OF WING FOOTING AND FLOOR SLAB WHEN SLAB IS THICKER THAN FOOTING

PROJECT NO. A-0009CA
GRAHAM COUNTY
 STATION: 46+41.00 -L-

SHEET 8 OF 14




STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
TRIPLE 12 FT. X 9 FT. CONCRETE BOX CULVERT RIGHT EXTENSION
45°-10'-48" SKEW


DRAWN BY: STM DATE: 04/21
 CHECKED BY: MGC DATE: 02/22
 DESIGN ENGINEER OF RECORD: STM DATE: 04/21

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED
TGS ENGINEERS
 706 HILLSBOROUGH STREET
 SUITE 200
 RALEIGH, NC 27603
 PH (919) 773-8887
 CORP. LICENSE NO.: C-0275

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	C2-8
1			3			TOTAL SHEETS
2			4			14



PROJECT NO. A-0009CA
GRAHAM COUNTY
 STATION: 46+41.00 -L-
 SHEET 9 OF 14




STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
**TRIPLE 12 FT. X 9 FT.
 CONCRETE BOX CULVERT
 RIGHT EXTENSION
 45°-10'-48" SKEW**

PLAN OF FLOOR SLAB

NOTES: FOR S1 BARS IN FLOOR SLAB & WING FOOTINGS, SEE WING SHEET.
 FOR D1 DOWELS IN WALLS, SEE SHEET 8 OF 14.

DRAWN BY :	STM	DATE :	04/21
CHECKED BY :	MGC	DATE :	02/22
DESIGN ENGINEER OF RECORD:	STM	DATE :	04/21

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED					
TGS ENGINEERS					
706 HILLSBOROUGH STREET					
SUITE 200					
RALEIGH, NC 27603					
PH (919) 773-8887					
CORP. LICENSE NO.: C-0275					
REVISIONS					
NO.	BY:	DATE:	NO.	BY:	DATE:
1			3		
2			4		
					SHEET NO. C2-9
					TOTAL SHEETS 14



PLAN OF ROOF SLAB

PROJECT NO. A-0009CA
GRAHAM COUNTY
 STATION: 46+41.00-L-
 SHEET 10 OF 14




STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
 TRIPLE 12 FT. X 9 FT.
 CONCRETE BOX CULVERT
 RIGHT EXTENSION
 45°-10'-48" SKEW

DRAWN BY : STM DATE : 04/21
 CHECKED BY : MGC DATE : 02/22
 DESIGN ENGINEER OF RECORD: STM DATE : 04/21


DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED

TGS ENGINEERS
 706 HILLSBOROUGH STREET
 SUITE 200
 RALEIGH, NC 27603
 PH (919) 773-8887
 CORP. LICENSE NO.: C-0275

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	C2-10
1			3			TOTAL SHEETS
2			4			14




DETAIL A
FLOOR SLAB



DETAIL B
ROOF SLAB

PROJECT NO. A-0009CA
GRAHAM COUNTY
 STATION: 46+41.00 -L-

SHEET 11 OF 14




STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
 TRIPLE 12 FT. X 9 FT.
 CONCRETE BOX CULVERT
 RIGHT EXTENSION
 45°-10'-48" SKEW


DRAWN BY : STM DATE : 04/21
 CHECKED BY : MGC DATE : 02/22

DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED
 TGS ENGINEERS
 706 HILLSBOROUGH STREET
 SUITE 200
 RALEIGH, NC 27603
 PH (919) 773-8887
 CORP. LICENSE NO.: C-0275


REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			C2-11
2			4			TOTAL SHEETS 14




PLAN W3



TYPICAL WING SECTION



ELEVATION W3



Z7	6'-2"	7"
Z8	5'-5"	7"
Z9	4'-10"	6"
Z10	4'-3"	6"
Z11	3'-8"	6"
Z12	3'-0"	6"

ALL BAR DIMENSIONS ARE OUT TO OUT.

BILL OF MATERIAL					
BAR NO.	SIZE	TYPE	LENGTH	WEIGHT	
H6	22	#4	STR	26'-1"	383
H7	2	#4	STR	24'-5"	33
H8	2	#4	STR	20'-11"	28
H9	2	#4	STR	17'-5"	23
H10	2	#4	STR	13'-11"	19
H11	2	#4	STR	10'-5"	14
H12	2	#4	STR	6'-11"	9
H13	2	#4	STR	3'-5"	5
H14	5	#4	STR	27'-2"	91
H15	22	#4	1	3'-3"	48
N3	14	#6	2	6'-8"	140
N4	14	#6	2	6'-5"	135
S1	3	#6	STR	6'-0"	27
T1	4	#5	STR	27'-11"	116
V13	2	#4	STR	8'-6"	11
V14	6	#4	STR	9'-0"	36
V15	5	#5	STR	10'-8"	56
V16	5	#5	STR	12'-1"	63
V17	5	#6	STR	13'-6"	101
V18	5	#6	STR	14'-11"	112
V19	2	#4	STR	10'-5"	14
V20	6	#4	STR	10'-10"	43
V21	5	#5	STR	12'-6"	65
V22	5	#5	STR	14'-0"	73
V23	5	#6	STR	15'-5"	116
V24	5	#6	STR	16'-10"	126
Z7	3	#5	3	6'-9"	21
Z8	6	#5	3	6'-0"	38
Z9	5	#4	3	5'-4"	18
Z10	5	#4	3	4'-9"	16
Z11	5	#4	3	4'-2"	14
Z12	5	#4	3	3'-6"	12
REINFORCING STEEL FOR 1 WING					2006 LBS
CLASS A CONCRETE					
1 WING					22.7 CY
1 HEADWALL					1.8 CY
1 END CURTAIN WALL					3.0 CY
TOTAL					27.5 CY

NOTES

- A 3 FOOT STRIP OF FILTER FABRIC SHALL BE ATTACHED TO THE FILL FACE OF THE WING COVERING THE ENTIRE LENGTH OF THE EXPANSION JOINT.
- G1 BARS IN HEADWALL ARE INCLUDED WITH THE BARREL REINFORCING STEEL.

PROJECT NO. A-0009CA
 COUNTY GRAHAM
 STATION: 46+41.00 -L-
 SHEET 13 OF 14




STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
**WING W3 FOR
 TRIPLE 12 FT. X 9 FT.
 CONCRETE BOX CULVERT
 RIGHT EXTENSION**


DRAWN BY : STM DATE : 12/21
 CHECKED BY : MGC DATE : 02/22
 DESIGN ENGINEER OF RECORD: STM DATE : 12/21

DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED
TGS ENGINEERS
 706 HILLSBOROUGH STREET
 SUITE 200
 RALEIGH, NC 27603
 PH (919) 773-8887
 CORP. LICENSE NO.: C-0275

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			C2-13
2			4			TOTAL SHEETS 14




PLAN W4




BILL OF MATERIAL					
BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
H1	20	#4	STR	24'-1"	322
H2	2	#4	STR	20'-7"	27
H3	2	#4	STR	9'-0"	12
H4	5	#4	STR	24'-3"	81
H5	20	#4	1	3'-3"	43
N1	12	#6	2	6'-8"	120
N2	15	#6	2	6'-5"	145
S1	3	#6	STR	6'-0"	27
T1	4	#5	STR	25'-10"	108
V1	2	#4	STR	9'-6"	13
V2	5	#4	STR	9'-10"	33
V3	5	#5	STR	10'-3"	53
V4	5	#5	STR	10'-9"	56
V5	5	#6	STR	11'-3"	84
V6	5	#6	STR	11'-8"	88
V7	2	#4	STR	8'-0"	11
V8	5	#4	STR	8'-1"	27
V9	5	#5	STR	8'-6"	44
V10	5	#5	STR	9'-0"	47
V11	5	#6	STR	9'-5"	71
V12	5	#6	STR	9'-10"	74
Z1	3	#5	3	6'-10"	21
Z2	4	#5	3	6'-4"	26
Z3	5	#4	3	5'-7"	19
Z4	5	#4	3	4'-11"	16
Z5	5	#4	3	4'-2"	14
Z6	5	#4	3	3'-6"	12

REINFORCING STEEL FOR 1 WING 1594 LBS
 CLASS A CONCRETE 1 WING TOTAL 18.1 CY




ALL BAR DIMENSIONS ARE OUT TO OUT.

NOTES
 A 3 FOOT STRIP OF FILTER FABRIC SHALL BE ATTACHED TO THE FILL FACE OF THE WING COVERING THE ENTIRE LENGTH OF THE EXPANSION JOINT.
 G1 BARS IN HEADWALL ARE INCLUDED WITH THE BARREL REINFORCING STEEL.



TYPICAL WING SECTION



ELEVATION W4

PROJECT NO. A-0009CA
 GRAHAM COUNTY
 STATION: 46+41.00 -L-
 SHEET 14 OF 14

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

WING W4 FOR
 TRIPLE 12 FT. X 9 FT.
 CONCRETE BOX CULVERT
 RIGHT EXTENSION

6/1/2022

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED


TGS ENGINEERS
 706 HILLSBOROUGH STREET
 SUITE 200
 RALEIGH, NC 27603
 PH (919) 773-8887
 CORP. LICENSE NO.: C-0275

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	C2-14
1			3			TOTAL SHEETS 14
2			4			


DRAWN BY : STM DATE : 12/21
 CHECKED BY : MGC DATE : 02/22
 DESIGN ENGINEER OF RECORD: STM DATE : 12/21

BENCH MARK #6: SPIKE NAIL IN BASE OF 24" WHITE OAK; 56' RT OF STA. 118+67 -L-; ELEV. = 2100.03

F.A. PROJECT NO. : APD-0074(178)



LOCATION SKETCH



PROFILE ALONG CULVERT

DRAWN BY : ZCS DATE : 1/21
 CHECKED BY : MGC DATE : 4/21
 DESIGN ENGINEER OF RECORD : ZCS DATE : 4/21

TOTAL STRUCTURE QUANTITIES		
CLASS A CONCRETE		
BARREL @ 0.92 CY/FT	94.3	C.Y.
WINGS, ETC.	31.0	C.Y.
SILLS	1.3	C.Y.
TOTAL	126.6	C.Y.
REINFORCING STEEL		
BARREL & SILLS	9,442	LBS.
WINGS, ETC.	1,858	LBS.
TOTAL	11,300	LBS.
CULVERT EXCAVATION	LUMP SUM	
FOUNDATION COND. MAT'L.	90 TONS	

ROADWAY DATA

GRADE POINT ELEV. @ STA. 108+27.00-L- = 2084.41
 BED ELEV. @ STA. 108+27.00-L- = 2069.8
 ROADWAY SLOPES = 2:1

HYDROGRAPHIC DATA

DESIGN DISCHARGE = 430 CFS
 FREQUENCY OF DESIGN FLOOD = 50 YRS
 DESIGN HIGH WATER ELEVATION = 2079.8
 DRAINAGE AREA = 0.58 SQ. MI.
 BASE DISCHARGE (Q100) = 530 CFS
 BASE HIGH WATER ELEVATION = 2081.3

OVERTOPPING FLOOD DATA

OVERTOPPING DISCHARGE = 700 CFS
 FREQUENCY OF OVERTOPPING FLOOD = >100 YRS
 OVERTOPPING FLOOD ELEVATION = 2084.2

SAMPLE BAR REPLACEMENT

SIZE	LENGTH
#3	6'-2"
#4	7'-4"
#5	8'-6"
#6	9'-8"
#7	10'-10"
#8	12'-0"
#9	13'-2"
#10	14'-6"
#11	15'-10"

NOTE:
 SAMPLE BAR REPLACEMENT LENGTHS BASED ON 30" (SAMPLE LENGTH) PLUS TWO SPLICE LENGTHS AND f_y = 60ksi.

NOTES:

- ASSUMED LIVE LOAD ----- HL-93 OR ALTERNATE LOADING.
- DESIGN FILL----- 6.0' MAX.
- FOR OTHER DESIGN DATA AND NOTES, SEE STANDARD NOTES SHEET.
- 3" Ø WEEP HOLES INDICATED TO BE IN ACCORDANCE WITH THE SPECIFICATIONS.
- CONCRETE IN CULVERT TO BE POURED IN THE FOLLOWING ORDER:
 1. WING FOOTINGS AND FLOOR SLAB INCLUDING 4" OF ALL VERTICAL WALLS.
 2. THE REMAINING PORTIONS OF THE WALLS AND WINGS FULL HEIGHT FOLLOWED BY ROOF SLAB AND HEADWALLS.
- THE RESIDENT ENGINEER SHALL CHECK THE LENGTH OF CULVERT BEFORE STAKING IT OUT TO MAKE CERTAIN THAT IT WILL PROPERLY TAKE CARE OF THE FILL.
- DIMENSIONS FOR WING LAYOUT AS WELL AS ADDITIONAL REINFORCING STEEL EMBEDDED IN BARREL ARE SHOWN ON WING SHEET.
- TRANSVERSE CONSTRUCTION JOINTS SHALL BE USED IN THE BARREL, SPACED TO LIMIT THE POURS TO A MAXIMUM OF 70 FT. LOCATION OF JOINTS SHALL BE SUBJECT TO APPROVAL OF THE ENGINEER.

AT THE CONTRACTOR'S OPTION, HE MAY SPLICE THE VERTICAL REINFORCING STEEL IN THE INTERIOR FACE OF EXTERIOR WALL ABOVE LOWER WALL CONSTRUCTION JOINT. THE SPLICE LENGTH SHALL BE AS PROVIDED IN THE SPLICE LENGTH CHART SHOWN ON THE PLANS. EXTRA WEIGHT OF STEEL DUE TO THE SPLICES SHALL BE PAID FOR BY THE CONTRACTOR.

FOR CULVERT DIVERSION DETAILS AND PAY ITEM, SEE EROSION CONTROL PLANS.

FOR CRANE SAFETY, SEE SPECIAL PROVISIONS.

FOR SUBMITTAL OF WORKING DRAWINGS, SEE SPECIAL PROVISIONS.

FOR FALSEWORK AND FORMWORK, SEE SPECIAL PROVISIONS.

FOR GROUT FOR STRUCTURES, SEE SPECIAL PROVISIONS.

FOR EROSION CONTROL MEASURES, SEE EROSION CONTROL PLANS.

AT THE CONTRACTOR'S OPTION HE MAY SUBMIT, TO THE ENGINEER FOR APPROVAL, DESIGN AND DETAIL DRAWINGS FOR A PRECAST REINFORCED CONCRETE BOX CULVERT IN LIEU OF THE CAST-IN-PLACE CULVERT SHOWN ON THE PLANS. THE DESIGN SHALL PROVIDE THE SAME SIZE AND NUMBER OF BARRELS AS USED ON THE CAST-IN-PLACE DESIGN. FOR OPTIONAL PRECAST REINFORCED CONCRETE BOX CULVERT, SEE SPECIAL PROVISIONS.

THE CONTRACTOR SHALL PROVIDE INDEPENDENT ASSURANCE SAMPLES OF REINFORCING STEEL AS FOLLOWS: FOR PROJECTS REQUIRING UP TO 400 TONS OF REINFORCING STEEL, ONE 30 INCH SAMPLE OF EACH SIZE BAR USED, AND FOR PROJECTS REQUIRING OVER 400 TONS OF REINFORCING STEEL, TWO 30 INCH SAMPLES OF EACH SIZE BAR USED. THE SAMPLE BARS SHOULD COME FROM STEEL ACTUALLY USED IN THE PROJECT AND THE SAMPLE BARS SHOULD BE REPLACED BY SPICED BARS AS SPECIFIED IN THE SAMPLE BAR REPLACEMENT CHART. PAYMENT FOR THE SAMPLE BARS AND REPLACEMENT REINFORCING STEEL SHALL BE CONSIDERED INCIDENTAL TO VARIOUS PAY ITEMS.


EXCAVATE 1 FOOT BELOW CULVERT AND REPLACE WITH FOUNDATION CONDITIONING MATERIAL IN ACCORDANCE WITH ARTICLE 414-4 OF THE STANDARD SPECIFICATIONS. FOUNDATION CONDITIONING MATERIAL SHOULD CONSIST OF SELECT MATERIAL CLASS V OR VI FOR RCBC.

IF REQUIRED, UNDERCUT LOOSE SOILS THAT MAY BE ENCOUNTERED BENEATH THE BOTTOM OF THE FOUNDATION CONDITIONING MATERIAL. BACKFILL UNDERCUT AREAS WITH FOUNDATION CONDITIONING MATERIAL.

FOR TRAFFIC PHASING, SEE TRAFFIC CONTROL PLANS.

PROJECT NO. A-0009CA
GRAHAM COUNTY
 STATION: 108+27.00 -L-

SHEET 1 OF 6



STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

SINGLE 7 FT. x 8 FT.
 CONCRETE BOX CULVERT
 130° SKEW

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

TGS ENGINEERS
 804-C N. LAFAYETTE ST
 SHELBY, NC 28150
 PH (704) 476-0003
 CORP. LICENSE NO.: C-0275

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	C3-1
1			3			TOTAL SHEETS 6
2			4			

LOAD AND RESISTANCE FACTOR RATING (LRFR) SUMMARY FOR REINFORCED CONCRETE BOX CULVERTS

LEVEL	VEHICLE	WEIGHT (W) (TONS)	CONTROLLING LOAD RATING #	MINIMUM RATING FACTORS (RF)	TONS = W x RF	STRENGTH I LIMIT STATE								COMMENT NUMBER		
						MOMENT				SHEAR						
						LIVE-LOAD FACTORS (γ _{LL})	RATING FACTOR	BOX NO.	ELEMENT TYPE	DISTANCE FROM LEFT END OF ELEMENT (ft)	RATING FACTOR	BOX NO.	ELEMENT TYPE		DISTANCE FROM LEFT END OF ELEMENT (ft)	
DESIGN LOAD RATING	HL-93 (INVENTORY)	N/A	①	1.11	--	1.75	1.11	1	BOTTOM SLAB	4.25	1.75	1	BOTTOM SLAB	0.75		
	HL-93 (OPERATING)	N/A		1.43	--	1.35	1.43	1	BOTTOM SLAB	4.25	2.27	1	BOTTOM SLAB	0.75		
	HS-20 (INVENTORY)	36.000	②	1.15	47.52	1.75	1.15	1	BOTTOM SLAB	4.25	1.83	1	BOTTOM SLAB	0.75		
	HS-20 (OPERATING)	36.000		1.50	61.56	1.35	1.50	1	BOTTOM SLAB	4.25	2.37	1	BOTTOM SLAB	0.75		
LEGAL LOAD RATING	SINGLE VEHICLE (SV)	SNSH		2.06	23.22	1.40	2.06	1	TOP SLAB	4.25	4.01	1	TOP SLAB	0.75		
		SNGARBS2	20.000		1.92	33.40	1.40	1.92	1	TOP SLAB	4.25	3.75	1	TOP SLAB	0.75	
		SNAGRIS2	22.000		2.06	37.84	1.40	2.06	1	TOP SLAB	4.25	4.01	1	TOP SLAB	0.75	
		SNCOTTS3	27.250	③	1.39	44.15	1.40	1.39	1	BOTTOM SLAB	4.25	2.19	1	BOTTOM SLAB	0.75	
		SNAGGRS4	34.925		1.78	62.26	1.40	1.78	1	BOTTOM SLAB	4.25	2.82	1	BOTTOM SLAB	0.75	
		SNS5A	35.550		2.01	62.57	1.40	2.01	1	TOP SLAB	4.25	3.61	1	BOTTOM SLAB	0.75	
		SNS6A	39.950		1.63	70.31	1.40	1.63	1	BOTTOM SLAB	4.25	2.58	1	BOTTOM SLAB	0.75	
	SNS7B	42.000		1.63	73.92	1.40	1.63	1	BOTTOM SLAB	4.25	2.58	1	BOTTOM SLAB	0.75		
	TRUCK TRACTOR SEMI-TRAILER (TTST)	TNAGRIT3	33.000		2.05	56.76	1.40	2.05	1	TOP SLAB	4.25	4.01	1	TOP SLAB	0.75	
		TNT4A	33.075		1.65	58.21	1.40	1.65	1	BOTTOM SLAB	4.25	2.61	1	BOTTOM SLAB	0.75	
		TNT6A	41.600		1.63	73.22	1.40	1.63	1	BOTTOM SLAB	4.25	2.58	1	BOTTOM SLAB	0.75	
		TNT7A	42.000		1.64	73.92	1.40	1.64	1	BOTTOM SLAB	4.25	2.60	1	BOTTOM SLAB	0.75	
		TNT7B	42.000		1.63	73.92	1.40	1.63	1	BOTTOM SLAB	4.25	2.58	1	BOTTOM SLAB	0.75	
		TNAGRIT4	43.000		1.65	73.96	1.40	1.65	1	BOTTOM SLAB	4.25	2.61	1	BOTTOM SLAB	0.75	
TNAGT5A		45.000		1.65	74.40	1.40	1.65	1	BOTTOM SLAB	4.25	2.61	1	BOTTOM SLAB	0.75		
TNAGT5B	45.000		1.65	79.20	1.40	1.65	1	BOTTOM SLAB	4.25	2.61	1	BOTTOM SLAB	0.75			

LOAD FACTORS:

DESIGN LOAD RATING FACTORS

LOAD TYPE	MAX FACTOR	MIN FACTOR
DC	1.25	0.90
DW	1.50	0.65
EV	1.30	0.90
EH	1.35	0.90
ES	1.35	0.90
LS	1.75	--
WA	1.00	--

NOTE:

RATING FACTORS ARE BASED ON THE STRENGTH I LIMIT STATE.

COMMENTS:

- 1.
- 2.
- 3.
- 4.


CONTROLLING LOAD RATING

① DESIGN LOAD RATING (HL-93)

② DESIGN LOAD RATING (HS-20)

③ LEGAL LOAD RATING **

** SEE CHART FOR VEHICLE TYPE



LRFR SUMMARY

PROJECT NO. A-0009CA
GRAHAM COUNTY
 STATION: 108+27.00 -L-

SHEET 2 OF 6

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

STANDARD
 LRFR SUMMARY FOR
 REINFORCED CONCRETE
 BOX CULVERTS
 (NON-INTERSTATE TRAFFIC)


DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	C3-2
1			3			TOTAL SHEETS
2			4			6

TGS ENGINEERS
 706 HILLSBOROUGH STREET
 SUITE 200
 RALEIGH, NC 27603
 PH (919) 773-8887
 CORP. LICENSE NO.: C-0275

STR. #3 STD. NO. LRFR5

ASSEMBLED BY : ZCS	DATE : 2/21
CHECKED BY : MGC	DATE : 4/21
DRAWN BY : WMC	7/11
CHECKED BY : GM	7/11
REV. 10/1/11	MAA/GM
REV. 12/17	MAA/THC




PART PLAN - ROOF SLAB

PART PLAN - FLOOR SLAB

NOTE:
FOR S1 BARS IN FLOOR SLAB
& WING FOOTING, SEE WING SHEET.

PROJECT NO. A-0009CA
GRAHAM COUNTY
 STATION: 108+27.00 -L-

SHEET 4 OF 6



STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
**SINGLE 7 FT. X 8 FT.
 CONCRETE BOX CULVERT
 130° SKEW**

DRAWN BY :	ZCS	DATE :	2/21
CHECKED BY :	MGC	DATE :	4/21
DESIGN ENGINEER OF RECORD:	ZCS	DATE :	4/21

DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED

TGS ENGINEERS
 706 HILLSBOROUGH STREET
 SUITE 200
 RALEIGH, NC 27603
 PH (919) 773-8887
 CORP. LICENSE NO.: C-0275

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	C3-4
1			3			TOTAL SHEETS
2			4			6



NOTES

NATIVE MATERIAL CONSISTS OF MATERIAL THAT IS EXCAVATED FROM THE STREAM BED OR FLOODPLAIN AT THE PROJECT SITE DURING CULVERT CONSTRUCTION. RIP-RAP MAY BE USED TO SUPPLEMENT THE NATIVE MATERIAL IN THE CULVERT BARREL. IF RIP-RAP IS USED TO LINE THE BARREL, NATIVE MATERIAL SHOULD BE PLACED ON TOP TO FILL VOIDS AND PROVIDE A FLAT SURFACE FOR ANIMAL PASSAGE. NATIVE MATERIAL IS SUBJECT TO APPROVAL BY THE ENGINEER AND MAY BE SUBJECT TO PERMIT CONDITIONS.


THE ENTIRE COST OF WORK REQUIRED TO PLACE EXCAVATED MATERIAL OR SUPPLEMENTAL MATERIAL AS SHOWN ON THE PLANS SHALL BE INCLUDED IN THE CONTRACT LUMP SUM PRICE BID FOR CULVERT EXCAVATION.

THE ENTIRE COST OF WORK REQUIRED TO CONSTRUCT THE SILLS SHALL BE INCLUDED IN THE VARIOUS PAY ITEMS.


BAR TYPE		BAR SCHEDULE				
BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT	
A1	544	#4	5	4'-6"	1635	
A100	115	#5	STR	8'-1"	970	
A101	2	#5	STR	7'-2"	15	
A102	2	#5	STR	6'-2"	13	
A103	2	#5	STR	5'-2"	11	
A104	2	#5	STR	4'-2"	9	
A105	2	#5	STR	3'-2"	7	
A200	191	#4	STR	8'-1"	1031	
A201	2	#4	STR	7'-7"	10	
A202	2	#4	STR	7'-0"	9	
A203	2	#4	STR	6'-4"	8	
A204	2	#4	STR	5'-9"	8	
A205	2	#4	STR	5'-2"	7	
A206	2	#4	STR	4'-7"	6	
A207	2	#4	STR	4'-0"	5	
A208	2	#4	STR	3'-5"	5	
A209	2	#4	STR	2'-9"	4	
DIMENSIONS ARE OUT TO OUT						
SPLICE LENGTHS CHART						
BAR	SIZE	SPLICE LENGTH				
B1	#4	1'-10"				
C1	#4	1'-11"				
B1	224	#4	STR	8'-6"	1272	
B2	272	#4	STR	8'-0"	1454	
C1	108	#4	STR	35'-8"	2573	
D1	15	#6	STR	1'-3"	28	
G1	4	#4	STR	10'-5"	28	
S2	12	#8	STR	10'-5"	334	
REINFORCING STEEL					9,442 LBS	



INLET ELEVATION




ELEVATION



SECTION THROUGH SILL

* DOWELS MAY BE PUSHED INTO GREEN CONCRETE AFTER SLAB HAS BEEN FLOAT FINISHED.

SILL DETAILS



PLAN OF FLOOR SILL LAYOUT

PROJECT NO. A-0009CA
GRAHAM COUNTY
 STATION: 108+27.00 -L-

SHEET 5 OF 6




STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
**SINGLE 7 FT. X 8 FT.
 CONCRETE BOX CULVERT
 130° SKEW**

DRAWN BY :	ZCS	DATE :	2/21
CHECKED BY :	MGC	DATE :	4/21
DESIGN ENGINEER OF RECORD:	ZCS	DATE :	4/21


DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED

TGS ENGINEERS
 706 HILLSBOROUGH STREET
 SUITE 200
 RALEIGH, NC 27603
 PH (919) 773-8887
 CORP. LICENSE NO.: C-0275


REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			C3-5
2			4			TOTAL SHEETS 6




PLAN W1




PLAN W2



TYPICAL WING SECTION



ELEVATION W1



ELEVATION W2

BAR TYPES	
1	Diagram of bar type 1: 2'-0" length, 1'-10 1/8" width, 9/8" diameter.
2	Diagram of bar type 2: 2'-0" length, 1'-3" width, 1'-10 1/8" width, 9/8" diameter.
3	Diagram of bar type 3: 6" RAD. curve, 8" width, 9/2" diameter. Includes list of bars N1-N12 with lengths: N1: 8'-6 1/2", N2: 7'-7 1/2", N3: 6'-3 1/2", N4: 4'-11 1/2", N5: 8'-10 1/2", N6: 8'-1 1/2", N7: 7'-7 1/2", N8: 7'-0 1/2", N9: 6'-6 1/2", N10: 5'-11 1/2", N11: 5'-5 1/2", N12: 4'-10 1/2".
4	Diagram of bar type 4: HK. Includes list of bars Z1-Z12 with lengths: Z1: 5'-4", Z2: 4'-8", Z3: 3'-8", Z4: 2'-8", Z5: 5'-5", Z6: 4'-11", Z7: 4'-7", Z8: 4'-2", Z9: 3'-9", Z10: 3'-4", Z11: 3'-0", Z12: 2'-7".

ALL BAR DIMENSIONS ARE OUT TO OUT.

BILL OF MATERIAL					
BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
H1	12	#4	STR	7'-7"	61
H2	4	#4	STR	6'-9"	18
H3	4	#4	STR	3'-5"	9
H4	24	#4	1	3'-3"	52
H5	4	#4	STR	8'-4"	22
H6	12	#4	STR	21'-4"	171
H7	4	#4	STR	19'-3"	51
H8	4	#4	STR	11'-0"	29
H9	4	#4	STR	2'-9"	7
H10	24	#4	2	3'-3"	52
H11	4	#4	STR	21'-8"	58
N1	4	#5	3	10'-0"	42
N2	4	#5	3	9'-1"	38
N3	6	#5	3	7'-9"	48
N4	6	#4	3	6'-5"	26
N5	4	#5	3	10'-4"	43
N6	8	#5	3	9'-7"	80
N7	6	#5	3	9'-1"	57
N8	6	#5	3	8'-6"	53
N9	6	#4	3	8'-0"	32
N10	6	#4	3	7'-5"	30
N11	6	#4	3	6'-11"	28
N12	6	#4	3	6'-4"	25
S1	12	#6	STR	6'-0"	108
T1	4	#5	STR	9'-6"	40
T2	2	#5	STR	9'-3"	19
T3	4	#5	STR	23'-3"	97
T4	2	#5	STR	22'-7"	47
V1	4	#4	STR	7'-8"	20
V2	4	#4	STR	6'-10"	18
V3	6	#4	STR	5'-7"	22
V4	6	#4	STR	4'-4"	17
V5	4	#4	STR	8'-1"	22
V6	8	#4	STR	7'-4"	39
V7	6	#4	STR	6'-10"	27
V8	6	#4	STR	6'-3"	25
V9	6	#4	STR	5'-9"	23
V10	6	#4	STR	5'-3"	21
V11	6	#4	STR	4'-9"	19
V12	6	#4	STR	4'-3"	17
Z1	4	#5	4	5'-11"	25
Z2	4	#5	4	5'-3"	22
Z3	6	#4	4	4'-2"	17
Z4	6	#4	4	3'-2"	13
Z5	4	#5	4	6'-0"	25
Z6	8	#5	4	5'-6"	46
Z7	6	#4	4	5'-1"	20
Z8	6	#4	4	4'-8"	19
Z9	6	#4	4	4'-3"	17
Z10	6	#4	4	3'-10"	15
Z11	6	#4	4	3'-6"	14
Z12	6	#4	4	3'-1"	12
REINFORCING STEEL					1858 LBS
FOR 4 WINGS					
CLASS A CONCRETE					
4 WINGS					29.1 CY
2 HEADWALLS					1.0 CY
2 END CURTAIN WALLS					0.9 CY
TOTAL					31.0 CY

NOTES:

- G1 BARS IN HEADWALL ARE INCLUDED WITH THE BARREL REINFORCING STEEL.
- A 3 FOOT STRIP OF FILTER FABRIC SHALL BE ATTACHED TO THE FILL FACE OF THE WING COVERING THE ENTIRE LENGTH OF THE EXPANSION JOINT.

PROJECT NO. A-0009CA
GRAHAM COUNTY
 STATION: 108+27.00 -L-
 SHEET 6 OF 6

6/1/2022

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

TGS ENGINEERS
 706 HILLSBOROUGH STREET
 SUITE 200
 RALEIGH, NC 27603
 PH (919) 773-8887
 CORP. LICENSE NO.: C-0275

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	C3-6
1			3			TOTAL SHEETS
2			4			6

ASSEMBLED BY :	ZCS	DATE :	4/21
CHECKED BY :	MGC	DATE :	4/21
DRAWN BY :	CCJ 01/00	REV. 6/19	MAA/THC
CHECKED BY :	RWW 03/00		

LOAD AND RESISTANCE FACTOR RATING (LRFR) SUMMARY FOR REINFORCED CONCRETE BOX CULVERTS

LEVEL	VEHICLE	WEIGHT (W) (TONS)	CONTROLLING LOAD RATING #	MINIMUM RATING FACTORS (RF)	TONS = W x RF	STRENGTH I LIMIT STATE								COMMENT NUMBER		
						MOMENT				SHEAR						
						LIVE-LOAD FACTORS (γ _{LL})	RATING FACTOR	BOX NO.	ELEMENT TYPE	DISTANCE FROM LEFT END OF ELEMENT (ft)	RATING FACTOR	BOX NO.	ELEMENT TYPE		DISTANCE FROM LEFT END OF ELEMENT (ft)	
DESIGN LOAD RATING	HL-93 (INVENTORY)	N/A	1	1.12	--	1.75	1.12	1	TOP SLAB	6.21	1.27	1	BOTTOM SLAB	11.71		
	HL-93 (OPERATING)	N/A		1.45	--	1.35	1.45	1	TOP SLAB	6.21	1.64	1	TOP SLAB	11.71		
	HS-20 (INVENTORY)	36.000	2	1.16	41.76	1.75	1.16	1	TOP SLAB	6.21	1.52	1	TOP SLAB	11.71		
	HS-20 (OPERATING)	36.000		1.51	54.36	1.35	1.51	1	TOP SLAB	6.21	1.98	1	TOP SLAB	11.71		
LEGAL LOAD RATING	SINGLE VEHICLE (SV)	SNSH		2.34	31.59	1.40	2.34	1	TOP SLAB	6.21	3.01	1	BOTTOM SLAB	11.71		
		SNGARBS2	20,000		2.19	43.80	1.40	2.19	1	TOP SLAB	6.21	2.75	1	TOP SLAB	11.71	
		SNAGRIS2	22,000		2.18	47.96	1.40	2.18	1	TOP SLAB	11.71	2.58	1	BOTTOM SLAB	11.71	
		SNCOTTS3	27,250		1.40	38.15	1.40	1.40	1	TOP SLAB	6.21	1.81	1	BOTTOM SLAB	11.71	
		SNAGGRS4	34,925		1.48	51.69	1.40	1.48	1	TOP SLAB	6.21	1.64	1	BOTTOM SLAB	11.71	
		SNS5A	35,550		1.62	57.59	1.40	1.67	1	TOP SLAB	6.21	1.62	1	BOTTOM SLAB	11.71	
		SNS6A	39,950		1.44	57.53	1.40	1.55	1	TOP SLAB	6.21	1.44	1	BOTTOM SLAB	11.71	
		SNS7B	42,000		1.40	58.80	1.40	1.48	1	TOP SLAB	11.71	1.40	1	BOTTOM SLAB	11.71	
	TRUCK TRACTOR SEMI-TRAILER (TTST)	TNAGRIT3	33,000		1.75	57.75	1.40	1.93	1	TOP SLAB	11.71	1.75	1	BOTTOM SLAB	11.71	
		TNT4A	33,075		1.66	54.90	1.40	1.66	1	TOP SLAB	6.21	1.74	1	BOTTOM SLAB	11.71	
		TNT6A	41,600		1.45	60.32	1.40	1.62	1	TOP SLAB	11.71	1.45	1	BOTTOM SLAB	11.71	
		TNT7A	42,000		1.44	60.48	1.40	1.63	1	TOP SLAB	11.71	1.44	1	BOTTOM SLAB	11.71	
		TNT7B	42,000		1.44	60.48	1.40	1.54	1	TOP SLAB	6.21	1.44	1	BOTTOM SLAB	11.71	
		TNAGRIT4	43,000		1.34	57.62	1.40	1.54	1	TOP SLAB	11.71	1.34	1	BOTTOM SLAB	11.71	
TNAGT5A	45,000		1.28	57.60	1.40	1.52	1	TOP SLAB	11.71	1.28	1	BOTTOM SLAB	11.71			
TNAGT5B	45,000		3	1.28	57.60	1.40	1.34	1	TOP SLAB	11.71	1.28	1	BOTTOM SLAB	11.71		

LOAD FACTORS:

DESIGN LOAD RATING FACTORS

LOAD TYPE	MAX FACTOR	MIN FACTOR
DC	1.25	0.90
DW	1.50	0.65
EV	1.30	0.90
EH	1.35	0.90
ES	1.35	0.90
LS	1.75	--
WA	1.00	--

NOTE:

RATING FACTORS ARE BASED ON THE STRENGTH I LIMIT STATE.

COMMENTS:

- 1.
- 2.
- 3.
- 4.


CONTROLLING LOAD RATING

1 DESIGN LOAD RATING (HL-93)

2 DESIGN LOAD RATING (HS-20)

3 LEGAL LOAD RATING **


** SEE CHART FOR VEHICLE TYPE



LRFR SUMMARY
(LOOKING DOWNSTREAM)

PROJECT NO. A-0009CA
GRAHAM COUNTY
 STATION: 113+69.00 -L-

SHEET 2 OF 8




STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
 STANDARD
 LRFR SUMMARY FOR
 REINFORCED CONCRETE
 BOX CULVERTS
 (NON-INTERSTATE TRAFFIC)

ASSEMBLED BY : ZCS	DATE : 6/21
CHECKED BY : MGC	DATE : 9/21
DRAWN BY : WMC	7/11
CHECKED BY : GM	7/11
REV. 10/1/11	MAA/GM
REV. 12/17	MAA/THC


DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

TGS ENGINEERS
 706 HILLSBOROUGH STREET
 SUITE 200
 RALEIGH, NC 27603
 PH (919) 773-8887
 CORP. LICENSE NO.: C-0275


REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			C4-2
2			4			TOTAL SHEETS 8



CULVERT EXTENSION SECTION NORMAL TO ROADWAY



INLET END ELEVATION NORMAL TO SKEW




RIGHT ANGLE SECTION OF BARREL EXTENSION

THERE ARE 130 "C" BARS IN SECTION OF BARREL.
 LOOKING UPSTREAM

PROJECT NO. A-0009CA
GRAHAM COUNTY
 STATION: 113+69.00 -L-

SHEET 3 OF 8




STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
**TRIPLE 11 FT. X 9.2 FT.
 CONCRETE BOX CULVERT
 LEFT EXTENSION
 130° SKEW**

DRAWN BY : ZCS DATE : 3/21
 CHECKED BY : MGC DATE : 8/21
 DESIGN ENGINEER OF RECORD : ZCS DATE : 11/21

DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED
TGS ENGINEERS
 706 HILLSBOROUGH STREET
 SUITE 200
 RALEIGH, NC 27603
 PH (919) 773-8887
 CORP. LICENSE NO.: C-0275

NO.		REVISIONS		DATE		BY	
1		3					
2		4					

SHEET NO. C4-3
 TOTAL SHEETS 8



PLAN OF FLOOR SLAB

NOTES: FOR S1 BARS IN FLOOR SLAB & WING FOOTINGS, SEE WING SHEET.
FOR D1 DOWELS IN EXTERIOR WALLS, SEE SHEET 3 OF 8.

PROJECT NO. A-0009CA
GRAHAM COUNTY
STATION: 113+69.00 -L-

SHEET 4 OF 8




STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH
**TRIPLE 11 FT. X 9.2 FT.
CONCRETE BOX CULVERT
LEFT EXTENSION**

DRAWN BY :	ZCS	DATE :	3/21
CHECKED BY :	MGC	DATE :	9/21
DESIGN ENGINEER OF RECORD:	ZCS	DATE :	4/22

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

TGS ENGINEERS
706 HILLSBOROUGH STREET
SUITE 200
RALEIGH, NC 27603
PH (919) 773-8887
CORP. LICENSE NO.: C-0275

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	C4-4
1			3			TOTAL SHEETS
2			4			8



PLAN OF ROOF SLAB

PROJECT NO. A-0009CA
GRAHAM COUNTY
 STATION: 113+69.00 -L-

SHEET 5 OF 8




STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
**TRIPLE 11 FT. X 9.2 FT.
 CONCRETE BOX CULVERT
 LEFT EXTENSION**

DRAWN BY : ZCS DATE : 3/21
 CHECKED BY : MGC DATE : 9/21
 DESIGN ENGINEER OF RECORD: ZCS DATE : 4/22

DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED


TGS ENGINEERS
 706 HILLSBOROUGH STREET
 SUITE 200
 RALEIGH, NC 27603
 PH (919) 773-8887
 CORP. LICENSE NO.: C-0275

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	C4-5
1			3			TOTAL SHEETS
2			4			8




PLAN OF LOW FLOW SILL

NOTE: FOR SLAB EXTENSION REINFORCEMENT, SEE PLAN OF FLOOR SLAB, SHEET 4 OF 8.



SECTION THROUGH WALL

* DOWELS MAY BE PUSHED INTO GREEN CONCRETE AFTER SLAB HAS BEEN FLOAT FINISHED.




ELEVATION

WALL DETAILS

PROJECT NO. A-0009CA
GRAHAM COUNTY
 STATION: 113+69.00 -L-

SHEET 6 OF 8



STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
**TRIPLE 11 FT. X 9.2 FT.
 CONCRETE BOX CULVERT
 LEFT EXTENSION**

DRAWN BY :	ZCS	DATE :	6/21
CHECKED BY :	MGC	DATE :	9/21
DESIGN ENGINEER OF RECORD:	ZCS	DATE :	4/22


DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED

TGS ENGINEERS
 706 HILLSBOROUGH STREET
 SUITE 200
 RALEIGH, NC 27603
 PH (919) 773-8887
 CORP. LICENSE NO.: C-0275

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			C4-6
2			4			TOTAL SHEETS 8

BAR SCHEDULE

BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT	BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT	BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT	BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT	BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT	
A1	87	#5	5	5'-11"	537	A200	29	#5	STR	27'-5"	829	A300	18	#5	STR	35'-4"	663	A400	37	#6	STR	27'-9"	1542	A450	35	#6	STR	10'-4"	543	
A2	191	#5	5	5'-5"	1079	A201	1	#5	STR	25'-9"	27	A301	1	#5	STR	33'-10"	35	A401	1	#6	STR	27'-6"	41	A451	1	#6	STR	8'-9"	13	
						A202	1	#5	STR	23'-8"	25	A302	1	#5	STR	32'-3"	34	A402	1	#6	STR	25'-10"	39	A452	1	#6	STR	7'-1"	11	
A100	16	#5	STR	35'-4"	590	A203	1	#5	STR	21'-6"	22	A303	1	#5	STR	30'-7"	32	A403	1	#6	STR	24'-3"	36	A453	1	#6	STR	5'-5"	8	
A101	1	#5	STR	33'-8"	35	A204	1	#5	STR	19'-5"	20	A304	1	#5	STR	28'-11"	30	A404	1	#6	STR	22'-7"	34	A454	1	#6	STR	3'-10"	6	
A102	1	#5	STR	31'-9"	33	A205	1	#5	STR	17'-3"	18	A305	1	#5	STR	27'-3"	28	A405	1	#6	STR	20'-11"	31	A455	1	#6	STR	11'-1"	17	
A103	1	#5	STR	29'-10"	31	A206	1	#5	STR	15'-2"	16	A306	1	#5	STR	25'-8"	27	A406	1	#6	STR	19'-3"	29	A456	1	#6	STR	12'-0"	18	
A104	1	#5	STR	28'-0"	29	A207	1	#5	STR	13'-1"	14	A307	1	#5	STR	24'-0"	25	A407	1	#6	STR	17'-8"	27	A457	1	#6	STR	13'-0"	20	
A105	1	#5	STR	26'-1"	27	A208	1	#5	STR	10'-11"	11	A308	1	#5	STR	22'-4"	23	A408	1	#6	STR	16'-0"	24	A458	1	#6	STR	14'-0"	21	
A106	1	#5	STR	24'-3"	25	A209	1	#5	STR	8'-10"	9	A309	1	#5	STR	20'-8"	22	A409	1	#6	STR	14'-4"	22	A459	1	#6	STR	14'-11"	22	
A107	1	#5	STR	22'-4"	23	A210	1	#5	STR	6'-8"	7	A310	1	#5	STR	19'-1"	20	A410	1	#6	STR	12'-8"	19	A460	1	#6	STR	15'-11"	24	
A108	1	#5	STR	20'-5"	21	A211	1	#5	STR	4'-7"	5	A311	1	#5	STR	17'-5"	18	A411	1	#6	STR	11'-0"	17	A461	1	#6	STR	15'-11"	24	
A109	1	#5	STR	18'-7"	19	A212	1	#5	STR	27'-9"	29	A312	1	#5	STR	15'-9"	16	A412	1	#6	STR	9'-5"	14	A462	1	#6	STR	14'-9"	22	
A110	1	#5	STR	16'-8"	17	A213	1	#5	STR	26'-4"	27	A313	1	#5	STR	14'-1"	15	A413	1	#6	STR	7'-9"	12	A463	1	#6	STR	13'-8"	21	
A111	1	#5	STR	14'-10"	15	A214	1	#5	STR	24'-11"	26	A314	1	#5	STR	12'-6"	13	A414	1	#6	STR	6'-1"	9	A464	1	#6	STR	12'-7"	19	
A112	1	#5	STR	12'-11"	13	A215	1	#5	STR	23'-5"	24	A315	1	#5	STR	10'-10"	11	A415	1	#6	STR	4'-5"	7	A465	1	#6	STR	11'-5"	17	
A113	1	#5	STR	11'-1"	12	A216	1	#5	STR	22'-0"	23	A316	1	#5	STR	9'-2"	10	A416	1	#6	STR	27'-6"	41	A466	1	#6	STR	10'-4"	16	
A114	1	#5	STR	9'-2"	10	A217	1	#5	STR	20'-7"	21	A317	1	#5	STR	7'-6"	8	A417	1	#6	STR	26'-4"	40	A467	1	#6	STR	9'-2"	14	
A115	1	#5	STR	7'-3"	8	A218	1	#5	STR	19'-2"	20	A318	1	#5	STR	5'-10"	6	A418	1	#6	STR	25'-3"	38	A468	1	#6	STR	8'-1"	12	
A116	1	#5	STR	5'-5"	6	A219	1	#5	STR	17'-8"	18	A319	1	#5	STR	4'-3"	4	A419	1	#6	STR	24'-1"	36	A469	1	#6	STR	6'-11"	10	
A117	1	#5	STR	3'-6"	4	A220	1	#5	STR	16'-3"	17							A420	1	#6	STR	23'-0"	35	A470	1	#6	STR	5'-10"	9	
						A221	1	#5	STR	14'-10"	15	A350	1	#5	STR	34'-4"	36	A421	1	#6	STR	21'-11"	33	A471	1	#6	STR	4'-9"	7	
A150	1	#5	STR	34'-0"	35	A222	1	#5	STR	13'-4"	14	A351	1	#5	STR	33'-3"	35	A422	1	#6	STR	20'-9"	31	B1	57	#4	STR	10'-7"	403	
A151	1	#5	STR	32'-9"	34	A223	1	#5	STR	12'-2"	13	A352	1	#5	STR	32'-1"	33	A423	1	#6	STR	19'-8"	30	B2	87	#4	STR	8'-11"	518	
A152	1	#5	STR	31'-5"	33	A224	1	#5	STR	11'-3"	12	A353	1	#5	STR	31'-0"	32	A424	1	#6	STR	18'-6"	28	B3	104	#4	STR	10'-7"	735	
A153	1	#5	STR	30'-2"	31	A225	1	#5	STR	10'-3"	11	A354	1	#5	STR	29'-10"	31	A425	1	#6	STR	17'-5"	26	C1	92	#4	STR	19'-1"	1173	
A154	1	#5	STR	28'-11"	30	A226	1	#5	STR	9'-3"	10	A355	1	#5	STR	28'-9"	30	A426	1	#6	STR	16'-3"	24	C2	168	#4	STR	15'-3"	1711	
A155	1	#5	STR	27'-8"	29	A227	1	#5	STR	8'-3"	9	A356	1	#5	STR	27'-7"	29	A427	1	#6	STR	15'-2"	23	D1	60	#6	STR	2'-6"	225	
A156	1	#5	STR	26'-4"	27	A228	1	#5	STR	7'-3"	8	A357	1	#5	STR	26'-6"	28	A428	1	#6	STR	14'-1"	21	D2	26	#6	STR	1'-11"	75	
A157	1	#5	STR	25'-1"	26	A229	1	#5	STR	6'-4"	7	A358	1	#5	STR	25'-5"	27	A429	1	#6	STR	12'-11"	19							
A158	1	#5	STR	23'-9"	25	A230	1	#5	STR	5'-4"	6	A359	1	#5	STR	24'-3"	25	A430	1	#6	STR	12'-2"	18							
A159	1	#5	STR	22'-6"	23	A231	1	#5	STR	4'-4"	5	A360	1	#5	STR	23'-2"	24	A431	1	#6	STR	11'-5"	17							
A160	1	#5	STR	21'-3"	22	A232	1	#5	STR	3'-4"	3	A361	1	#5	STR	22'-0"	23	A432	1	#6	STR	10'-8"	16							
A161	1	#5	STR	19'-11"	21							A362	1	#5	STR	20'-11"	22	A433	1	#6	STR	9'-11"	15	G1	4	#5	STR	39'-8"	165	
A162	1	#5	STR	18'-8"	19	A250	27	#5	STR	10'-4"	291	A363	1	#5	STR	19'-9"	21	A434	1	#6	STR	9'-2"	14							
A163	1	#5	STR	17'-5"	18	A251	1	#5	STR	8'-2"	9	A364	1	#5	STR	18'-8"	19	A435	1	#6	STR	8'-4"	13	S2	3	#8	STR	31'-11"	256	
A164	1	#5	STR	16'-1"	17	A252	1	#5	STR	6'-1"	6	A365	1	#5	STR	17'-6"	18	A436	1	#6	STR	7'-7"	11	S3	6	#6	STR	29'-4"	264	
A165	1	#5	STR	14'-9"	15	A253	1	#5	STR	3'-11"	4	A366	1	#5	STR	16'-5"	17	A437	1	#6	STR	6'-10"	10	S4	3	#8	STR	11'-8"	93	
A166	1	#5	STR	13'-6"	14	A254	1	#5	STR	10'-9"	11	A367	1	#5	STR	15'-4"	16	A438	1	#6	STR	6'-1"	9	S5	6	#6	STR	10'-11"	98	
A167	1	#5	STR	12'-3"	13	A255	1	#5	STR	12'-0"	13	A368	1	#5	STR	14'-2"	15	A439	1	#6	STR	5'-4"	8	S6	3	#8	STR	39'-8"	318	
A168	1	#5	STR	11'-0"	11	A256	1	#5	STR	13'-3"	14	A369	1	#5	STR	13'-1"	14	A440	1	#6	STR	4'-7"	7	S7	6	#6	STR	37'-6"	338	
A169	1	#5	STR	9'-9"	10	A257	1	#5	STR	14'-6"	15	A370	1	#5	STR	11'-11"	12	A441	1	#6	STR	3'-9"	6							
A170	1	#5	STR	8'-5"	9	A258	1	#5	STR	15'-8"	16	A371	1	#5	STR	10'-10"	11	A442	1	#6	STR	3'-0"	5							
A171	1	#5	STR	7'-2"	7	A259	1	#5	STR	15'-8"	16	A372	1	#5	STR	9'-8"	10													
A172	1	#5	STR	5'-11"	6	A260	1	#5	STR	14'-3"	15	A373	1	#5	STR	8'-7"	9													
A173	1	#5	STR	4'-7"	5	A261	1	#5	STR	12'-10"	13	A374	1	#5	STR	7'-6"	8													
A174	1	#5	STR	3'-4"	3	A262	1	#5	STR	11'-5"	12	A375	1	#5	STR	6'-4"	7													
						A263	1	#5	STR	9'-11"	10	A376	1	#5	STR	5'-3"	5													
						A264	1	#5	STR	8'-6"	9	A377	1	#5	STR	4'-1"	4													
						A265	1	#5	STR	7'-1"	7	A378	1	#5	STR	3'-0"	3													
						A266	1	#5	STR	5'-8"	6																			
						A267	1	#5	STR	4'-2"	4																			
																						REINFORCING STEEL		16,136 LBS						




PROJECT NO. A-0009CA

GRAHAM COUNTY

STATION: 113+69.00 -L-


SHEET 7 OF 8




STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH
TRIPLE 11 FT. X 9.2 FT.
CONCRETE BOX CULVERT
LEFT EXTENSION

DRAWN BY : ZCS DATE : 7/21
CHECKED BY : MGC DATE : 9/21
DESIGN ENGINEER OF RECORD: ZCS DATE : 4/22


TGS ENGINEERS		REVISIONS		SHEET NO.		
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			C4-7
2			4			TOTAL SHEETS
						8




PLAN W1




PLAN W2




TYPICAL WING SECTION



ELEVATION W1



ELEVATION W2



NOTE:
A 3 FOOT STRIP OF FILTER FABRIC SHALL BE ATTACHED TO THE FILL FACE OF THE WING COVERING THE ENTIRE LENGTH OF THE EXPANSION JOINT.
G1 BARS IN HEADWALL ARE INCLUDED WITH THE BARREL REINFORCING STEEL.

BILL OF MATERIAL					
BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
H1	8	#4	STR	9'-4"	50
H2	2	#4	STR	6'-3"	8
H3	2	#4	STR	2'-10"	4
H4	14	#4	1	3'-3"	30
H5	2	#4	STR	10'-2"	14
H6	8	#4	STR	17'-10"	95
H7	2	#4	STR	12'-4"	16
H8	2	#4	STR	6'-3"	8
H9	14	#4	2	3'-3"	30
H10	2	#4	STR	18'-5"	25
N1	2	#6	3	11'-4"	34
N2	3	#6	3	9'-11"	45
N3	3	#5	3	8'-7"	27
N4	4	#4	3	6'-10"	18
N5	2	#6	3	11'-4"	34
N6	3	#6	3	10'-9"	48
N7	4	#6	3	9'-10"	59
N8	4	#5	3	8'-10"	37
N9	4	#4	3	7'-10"	21
N10	4	#4	3	6'-10"	18
S1	6	#6	STR	6'-0"	54
T1	3	#5	STR	11'-3"	35
T2	3	#5	STR	19'-9"	62
V1	2	#4	STR	9'-1"	12
V2	3	#4	STR	7'-10"	16
V3	3	#4	STR	6'-6"	13
V4	4	#4	STR	4'-10"	13
V5	2	#4	STR	9'-4"	12
V6	3	#4	STR	8'-9"	18
V7	4	#4	STR	7'-9"	21
V8	4	#4	STR	6'-9"	18
V9	4	#4	STR	5'-9"	15
V10	4	#4	STR	4'-9"	13
Z1	2	#5	4	6'-7"	14
Z2	2	#5	4	6'-0"	13
Z3	4	#5	4	4'-9"	20
Z4	4	#4	4	3'-4"	9
Z5	2	#5	4	6'-9"	14
Z6	3	#5	4	6'-3"	20
Z7	5	#5	4	5'-3"	27
Z8	5	#5	4	4'-4"	23
Z9	5	#4	4	3'-4"	11
REINFORCING STEEL				1074 LBS	
FOR 2 WINGS					
CLASS A CONCRETE					
2 WINGS				14.3 CY	
1 HEADWALL				1.9 CY	
1 END CURTAIN WALL				3.4 CY	
2 EDGE BEAMS				2.8 CY	
TOTAL				22.4 CY	

ALL BAR DIMENSIONS ARE OUT TO OUT.

PROJECT NO. A-0009CA
GRAHAM COUNTY
 STATION: 113+69.00 -L-
 SHEET 8 OF 8


STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

WINGS FOR CONCRETE BOX CULVERT


REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	C4-8
1			3			TOTAL SHEETS
2			4			8

DRAWN BY : ZCS DATE : 3/21
 CHECKED BY : MGC DATE : 9/21
 DESIGN ENGINEER OF RECORD: ZCS DATE : 4/22

BENCH MARK #7: SPIKE NAIL SET IN BASE OF 20" POPLAR; 33.6' RT. OF STA. 137+92.90 -L-; ELEV. 2125.10



LOCATION SKETCH



PROFILE ALONG CULVERT

DRAWN BY : ZCS DATE : 12/21
 CHECKED BY : MGC DATE : 1/22

NOTES:

- ASSUMED LIVE LOAD - HL-93 OR ALTERNATE.
- FOR OTHER DESIGN DATA AND NOTES, SEE STANDARD NOTES SHEET.
- THE RESIDENT ENGINEER SHALL CHECK THE LENGTH OF THE CULVERT BEFORE CONSTRUCTION TO MAKE CERTAIN THAT IT WILL PROPERLY TAKE CARE OF THE FILL.
- FILL DEPTH 3'-0".
- EXCAVATE AT LEAST 1 FOOT BELOW THE CULVERT AND REPLACE EXCAVATED MATERIAL WITH FOUNDATION CONDITIONING MATERIAL IN ACCORDANCE WITH ARTICLE 414-4 OF THE STANDARD SPECIFICATIONS. FOUNDATION CONDITIONING MATERIAL SHOULD CONSIST OF SELECT MATERIAL CLASS V OR VI FOR RCBC.
- IF REQUIRED, UNDERCUT LOOSE SOILS THAT MAY BE ENCOUNTERED BENEATH THE BOTTOM OF THE FOUNDATION CONDITIONING MATERIAL. BACKFILL UNDERCUT AREAS WITH FOUNDATION CONDITIONING MATERIAL.
- FOR FALSEWORK AND FORMWORK, SEE SPECIAL PROVISIONS.
- FOR SUBMITTAL OF WORKING DRAWINGS, SEE SPECIAL PROVISIONS.
- FOR CRANE SAFETY, SEE SPECIAL PROVISIONS.
- FOR GROUT FOR STRUCTURES, SEE SPECIAL PROVISIONS.
- FOR EROSION CONTROL MEASURES, SEE EROSION CONTROL PLANS.
- THE CONTRACTOR SHALL PROVIDE INDEPENDENT ASSURANCE SAMPLES OF REINFORCING STEEL AS FOLLOWS: FOR PROJECTS REQUIRING UP TO 400 TONS OF REINFORCING STEEL, ONE 30 INCH SAMPLE OF EACH SIZE BAR USED, AND FOR PROJECTS REQUIRING OVER 400 TONS OF REINFORCING STEEL, TWO 30 INCH SAMPLES OF EACH SIZE BAR USED. THE SAMPLE BARS SHOULD COME FROM STEEL ACTUALLY USED IN THE PROJECT AND THE SAMPLE BARS SHOULD BE REPLACED BY SPICED BARS AS SPECIFIED IN THE SAMPLE BAR REPLACEMENT CHART. PAYMENT FOR THE SAMPLE BARS AND REPLACEMENT REINFORCING STEEL SHALL BE CONSIDERED INCIDENTAL TO VARIOUS PAY ITEMS.
- FOR CULVERT DIVERSION DETAILS AND PAY ITEM, SEE EROSION CONTROL PLANS.
- THE ENTIRE AREA OF THE ALUMINUM PIPES IN CONTACT WITH THE CONCRETE HEADWALL SHALL BE THOROUGHLY COATED WITH NEOPRENE SEALANT FOR CORROSION PROTECTION AT THE DIRECTION OF THE ENGINEER.
- FOR CORRUGATED ALUMINUM PIPE CULVERT, SEE SPECIAL PROVISIONS.

F.A. PROJECT NO. : APD-0074(178)

TOTAL STRUCTURE QUANTITIES

CORRUGATED ALUMINUM PIPE CULVERT	LUMP SUM
CULVERT EXCAVATION	LUMP SUM
FOUNDATION CONDITIONING MATERIAL	89 TONS

SAMPLE BAR REPLACEMENT

SIZE	LENGTH
#3	6'-2"
#4	7'-4"
#5	8'-6"
#6	9'-8"
#7	10'-10"
#8	12'-0"
#9	13'-2"
#10	14'-6"
#11	15'-10"

NOTE:
 SAMPLE BAR REPLACEMENT LENGTHS BASED ON 30" (SAMPLE LENGTH) PLUS TWO SPLICE LENGTHS AND f_y = 60ksi.

ROADWAY DATA

GRADE POINT ELEV. @ STA. 144+74.50-L- = 2147.65'
 BED ELEV. @ STA. 144+74.50-L- = 2138.3'
 ROADWAY SLOPES = VARIES

HYDRAULIC DATA


DESIGN DISCHARGE = 330 CFS
 FREQUENCY OF DESIGN FLOOD = 50 YRS
 DESIGN HIGH WATER ELEVATION = 2146.5'
 DRAINAGE AREA = 0.39 SQ. MI.
 BASE DISCHARGE (Q100) = 410 CFS
 BASE HIGH WATER ELEVATION = 2146.8'

OVERTOPPING FLOOD DATA

OVERTOPPING DISCHARGE = 410 CFS
 FREQUENCY OF OVERTOPPING FLOOD = 100 YRS
 OVERTOPPING FLOOD ELEVATION = 2146.8'

PROJECT NO. A-0009CA
GRAHAM COUNTY
 STATION: 144+74.50 -L-


SHEET 1 OF 4




STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
 CORRUGATED ALUMINUM PIPE CULVERT
 94° SKEW

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED
 TGS ENGINEERS
 804-C N. LAFAYETTE ST
 SHELBY, NC 28150
 PH (704) 476-0003
 CORP. LICENSE NO.: C-0275


REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			C5-1
2			4			TOTAL SHEETS 4



INLET ELEVATION
DIMENSIONS AND REINFORCING STEEL SYMMETRICAL ABOUT CL HEADWALL.




SECTION B-B
PIPES NOT SHOWN FOR CLARITY



SECTION A-A

BILL OF MATERIAL FOR INLET HEADWALL					
BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
B1	8	#4	STR	6'-1"	33
B2	4	#4	STR	5'-1"	14
B3	4	#4	STR	7'-0"	19
G1	2	#7	STR	18'-6"	76
H1	10	#4	1	6'-4"	42
H2	2	#4	1	4'-9"	6
H3	4	#4	1	2'-11"	8
N1	14	#5	2	4'-5"	64
N2	6	#4	2	3'-11"	16
T1	6	#4	STR	23'-0"	92
T2	6	#4	STR	6'-0"	24
T3	76	#4	STR	2'-6"	127
V1	12	#4	STR	7'-3"	58
V2	6	#4	STR	5'-8"	23
V3	6	#4	STR	4'-7"	18
V4	6	#4	STR	3'-4"	13
Z1	6	#6	3	4'-6"	41
Z2	4	#5	3	3'-11"	16
Z3	4	#4	3	3'-3"	9
REINFORCING STEEL					699 LBS
CLASS A CONCRETE					TOTAL 9.5 CY




PLAN
DIMENSIONS AND REINFORCING STEEL SYMMETRICAL ABOUT CL HEADWALL.

NOTES


NO SEPARATE PAYMENT WILL BE MADE FOR REINFORCING STEEL OR CLASS A CONCRETE. THE ENTIRE COST OF THESE ITEMS SHALL BE PAID FOR UNDER THE LUMP SUM PRICE BID FOR CORRUGATED ALUMINUM PIPE CULVERT.

CHAMFER ALL EXPOSED CORNERS 1".


PLACE A STONE DRAIN CONSISTING OF ONE (1) CUBIC FOOT OF NUMBER 78M STONE CONTAINED IN A POROUS FABRIC AT EACH WEEP HOLE. PLACE SUBDRAIN FINE AGGREGATE BENEATH AND OVER THE STONE DRAIN SO THE STONE DRAIN IS COMPLETELY COVERED BY A LAYER OF SUBDRAIN FINE AGGREGATE AT LEAST ONE (1) FOOT THICK. WHERE THERE IS MORE THAN ONE WEEP HOLE IN A WING WALL, PLACE A HORIZONTAL DRAIN OF SUBDRAIN FINE AGGREGATE AT LEAST ONE (1) FOOT SQUARE IN CROSS SECTION TO CONNECT ALL STONE DRAINS. PLACE A VERTICAL DRAIN OF SUBDRAIN FINE AGGREGATE AT LEAST ONE (1) FOOT SQUARE IN CROSS SECTION AT EACH WEEP HOLE TO AN ELEVATION OF TWO (2) FEET BELOW THE SURFACE OF THE EMBANKMENT.




TAPER DETAIL



1



2




3

BAR TYPES

ALL DIMENSIONS ARE SHOWN OUT TO OUT

DRAWN BY : ZCS DATE : 12/21
CHECKED BY : MGC DATE : 1/22



WING ELEVATION

PROJECT NO. A-0009CA
GRAHAM COUNTY
STATION: 144+74.50 -L-

SHEET 2 OF 4

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

**CORRUGATED ALUMINUM PIPE CULVERT
94° SKEW
INLET HEADWALL**


6/1/2022

ENGINEER
MARSHALL G. CHECK, JR.
20125


REVISIONS

NO.	BY:	DATE:	NO.	BY:	DATE:
1			3		
2			4		

SHEET NO. C5-2
TOTAL SHEETS 4




OUTLET ELEVATION
DIMENSIONS AND REINFORCING STEEL
SYMMETRICAL ABOUT CL HEADWALL.



SECTION B-B
PIPES NOT SHOWN FOR CLARITY

SECTION A-A

BILL OF MATERIAL FOR OUTLET HEADWALL					
BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
B1	8	#4	STR	7'-0"	37
B2	4	#4	STR	5'-10"	16
B3	4	#4	STR	7'-0"	19
G1	2	#7	STR	18'-6"	76
H1	10	#4	1	6'-4"	42
H2	2	#4	1	4'-10"	6
H3	4	#4	1	3'-3"	9
N1	14	#5	2	4'-11"	72
N2	6	#4	2	4'-5"	18
T1	6	#4	STR	23'-0"	92
T2	6	#4	STR	6'-0"	24
T3	76	#4	STR	2'-6"	127
V1	12	#4	STR	7'-9"	62
V2	6	#4	STR	6'-2"	25
V3	6	#4	STR	5'-1"	20
V4	6	#4	STR	3'-11"	16
Z1	6	#6	3	4'-6"	41
Z2	4	#5	3	3'-11"	16
Z3	4	#4	3	3'-3"	9
REINFORCING STEEL					727 LBS
CLASS A CONCRETE					TOTAL 9.7 CY




PLAN
DIMENSIONS AND REINFORCING STEEL
SYMMETRICAL ABOUT CL HEADWALL.

NOTES


NO SEPARATE PAYMENT WILL BE MADE FOR REINFORCING STEEL OR CLASS A CONCRETE. THE ENTIRE COST OF THESE ITEMS SHALL BE PAID FOR UNDER THE LUMP SUM PRICE BID FOR CORRUGATED ALUMINUM PIPE CULVERT.

CHAMFER ALL EXPOSED CORNERS 1".


PLACE A STONE DRAIN CONSISTING OF ONE (1) CUBIC FOOT OF NUMBER 78M STONE CONTAINED IN A POROUS FABRIC AT EACH WEEP HOLE. PLACE SUBDRAIN FINE AGGREGATE BENEATH AND OVER THE STONE DRAIN SO THE STONE DRAIN IS COMPLETELY COVERED BY A LAYER OF SUBDRAIN FINE AGGREGATE AT LEAST ONE (1) FOOT THICK WHERE THERE IS MORE THAN ONE WEEP HOLE IN A WING WALL. PLACE A HORIZONTAL DRAIN OF SUBDRAIN FINE AGGREGATE AT LEAST ONE (1) FOOT SQUARE IN CROSS SECTION TO CONNECT ALL STONE DRAINS. PLACE A VERTICAL DRAIN OF SUBDRAIN FINE AGGREGATE AT LEAST ONE (1) FOOT SQUARE IN CROSS SECTION AT EACH WEEP HOLE TO AN ELEVATION OF TWO (2) FEET BELOW THE SURFACE OF THE EMBANKMENT.



TAPER DETAIL



WING ELEVATION




BAR TYPES

ALL DIMENSIONS ARE SHOWN OUT TO OUT

PROJECT NO. A-0009CA
GRAHAM COUNTY
STATION: 144+74.50 -L-

SHEET 3 OF 4




STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH
CORRUGATED ALUMINUM
PIPE CULVERT
94° SKEW
OUTLET HEADWALL

DRAWN BY : ZCS DATE : 12/21
CHECKED BY : MGC DATE : 1/22


DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

TGS ENGINEERS
804-C N. LAFAYETTE ST
SHELBY, NC 28150
PH (704) 476-0003
CORP. LICENSE NO.: C-0275

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	TOTAL SHEETS
1			3			C5-3
2			4			4




ELEVATION
(LOOKING DOWNSTREAM)



FLOOR SILL LAYOUT

NOTES:


- PLACE A 3" Ø WEEP HOLE IN THE HIGH FLOW SILL AT THE OUTLET END.
- NATIVE MATERIAL EXCAVATED FROM THE EXISTING STREAM BED OR FLOOD PLAIN SHALL BE STOCKPILED AND LATER PLACED IN THE PROPOSED CULVERT BETWEEN SILLS TO PROVIDE A CONTINUOUS FLOW CHANNEL. RIP RAP MAY BE USED TO SUPPLEMENT THE NATIVE MATERIAL. IF RIP RAP IS USED, NATIVE MATERIAL SHALL BE PLACED ON TOP TO FILL VOIDS AND PROVIDE A LEVEL SURFACE FOR ANIMAL PASSAGE. NATIVE MATERIAL IS SUBJECT TO APPROVAL BY THE ENGINEER AND MAY BE SUBJECT TO PERMIT CONDITIONS.
- THE ENTIRE COST OF WORK REQUIRED TO PLACE THE EXCAVATED MATERIAL SHALL BE INCLUDED IN THE CONTRACT LUMP SUM PRICE BID FOR CULVERT EXCAVATION.
- THE ENTIRE COST OF THE SILLS SHALL BE INCLUDED IN THE LUMP SUM PRICE BID FOR CORRUGATED ALUMINUM PIPE CULVERT.



CULVERT SECTION NORMAL TO ROADWAY

PROJECT NO. A-0009CA
GRAHAM COUNTY
 STATION: 144+74.50 -L-

SHEET 4 OF 4




STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
**CORRUGATED ALUMINUM
 PIPE CULVERT
 94° SKEW**

DRAWN BY : ZCS DATE : 12/21
 CHECKED BY : MGC DATE : 1/22


DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED
TGS ENGINEERS
 706 HILLSBOROUGH STREET
 SUITE 200
 RALEIGH, NC 27603
 PH (919) 773-8887
 CORP. LICENSE NO.: C-0275

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			C5-4
2			4			TOTAL SHEETS 4

BENCH MARK #10: SPIKE NAIL IN BASE OF 14" DBL POPLAR; 40' RT OF STA. 197+38 -L-; ELEV. = 2200.60



LOCATION SKETCH



PROFILE ALONG CULVERT

DRAWN BY : ZCS DATE : 1/21
 CHECKED BY : MGC DATE : 6/21
 DESIGN ENGINEER OF RECORD : ZCS DATE : 11/21

TOTAL STRUCTURE QUANTITIES		
CLASS A CONCRETE		
BARREL @ 3.02 CY/FT	315.6	C.Y.
WINGS, ETC.	45.5	C.Y.
SILLS	8.0	C.Y.
TOTAL	369.1	C.Y.
REINFORCING STEEL		
BARREL & SILLS	39,286	LBS.
WINGS, ETC.	4,751	LBS.
TOTAL	44,037	LBS.
CULVERT EXCAVATION	LUMP SUM	
FOUNDATION COND. MAT'L.	223 TONS	

ROADWAY DATA	
GRADE POINT ELEV. @ STA. 195+16.00-L-	= 2203.83'
BED ELEV. @ STA. 195+16.00-L-	= 2190.0'
ROADWAY SLOPES	= 2:1
HYDROGRAPHIC DATA	
DESIGN DISCHARGE	= 1400 CFS
FREQUENCY OF DESIGN FLOOD	= 50 YRS
DESIGN HIGH WATER ELEVATION	= 2200.3'
DRAINAGE AREA	= 4.39 SQ. MI.
BASE DISCHARGE (Q100)	= 1700 CFS
BASE HIGH WATER ELEVATION	= 2201.4'
OVERTOPPING FLOOD DATA	
OVERTOPPING DISCHARGE	= 1600 CFS
FREQUENCY OF OVERTOPPING FLOOD	= >50 YRS
OVERTOPPING FLOOD ELEVATION	= 2201.0'

SAMPLE BAR REPLACEMENT

SIZE	LENGTH
#3	6'-2"
#4	7'-4"
#5	8'-6"
#6	9'-8"
#7	10'-10"
#8	12'-0"
#9	13'-2"
#10	14'-6"
#11	15'-10"

NOTE:
 SAMPLE BAR REPLACEMENT LENGTHS BASED ON 30" (SAMPLE LENGTH) PLUS TWO SPLICE LENGTHS AND f_c = 60ksi.

NOTES:

- ASSUMED LIVE LOAD ----- HL-93 OR ALTERNATE LOADING.
- DESIGN FILL----- 7.4' MAX.; 1.0' MIN.
- FOR OTHER DESIGN DATA AND NOTES, SEE STANDARD NOTES SHEET.
- 3" Ø WEEP HOLES INDICATED TO BE IN ACCORDANCE WITH THE SPECIFICATIONS.
- CONCRETE IN CULVERT TO BE POURED IN THE FOLLOWING ORDER:
 1. WING FOOTINGS AND FLOOR SLAB INCLUDING 4" OF ALL VERTICAL WALLS.
 2. THE REMAINING PORTIONS OF THE WALLS AND WINGS FULL HEIGHT FOLLOWED BY ROOF SLAB AND HEADWALLS.
- THE RESIDENT ENGINEER SHALL CHECK THE LENGTH OF CULVERT BEFORE STAKING IT OUT TO MAKE CERTAIN THAT IT WILL PROPERLY TAKE CARE OF THE FILL.
- DIMENSIONS FOR WING LAYOUT AS WELL AS ADDITIONAL REINFORCING STEEL EMBEDDED IN BARREL ARE SHOWN ON WING SHEET.
- TRANSVERSE CONSTRUCTION JOINTS SHALL BE USED IN THE BARREL, SPACED TO LIMIT THE POURS TO A MAXIMUM OF 70 FT. LOCATION OF JOINTS SHALL BE SUBJECT TO APPROVAL OF THE ENGINEER.
- AT THE CONTRACTOR'S OPTION, HE MAY SPLICE THE VERTICAL REINFORCING STEEL IN THE INTERIOR FACE OF EXTERIOR WALL ABOVE LOWER WALL CONSTRUCTION JOINT. THE SPLICE LENGTH SHALL BE AS PROVIDED IN THE SPLICE LENGTH CHART SHOWN ON THE PLANS. EXTRA WEIGHT OF STEEL DUE TO THE SPLICES SHALL BE PAID FOR BY THE CONTRACTOR.
- FOR CULVERT DIVERSION DETAILS AND PAY ITEM, SEE EROSION CONTROL PLANS.
- FOR CRANE SAFETY, SEE SPECIAL PROVISIONS.
- FOR SUBMITTAL OF WORKING DRAWINGS, SEE SPECIAL PROVISIONS.
- FOR FALSEWORK AND FORMWORK, SEE SPECIAL PROVISIONS.
- FOR GROUT FOR STRUCTURES, SEE SPECIAL PROVISIONS.
- FOR EROSION CONTROL MEASURES, SEE EROSION CONTROL PLANS.
- AT THE CONTRACTOR'S OPTION HE MAY SUBMIT, TO THE ENGINEER FOR APPROVAL, DESIGN AND DETAIL DRAWINGS FOR A PRECAST REINFORCED CONCRETE BOX CULVERT IN LIEU OF THE CAST-IN-PLACE CULVERT SHOWN ON THE PLANS. THE DESIGN SHALL PROVIDE THE SAME SIZE AND NUMBER OF BARRELS AS USED ON THE CAST-IN-PLACE DESIGN. FOR OPTIONAL PRECAST REINFORCED CONCRETE BOX CULVERT, SEE SPECIAL PROVISIONS.
- THE CONTRACTOR SHALL PROVIDE INDEPENDENT ASSURANCE SAMPLES OF REINFORCING STEEL AS FOLLOWS: FOR PROJECTS REQUIRING UP TO 400 TONS OF REINFORCING STEEL, ONE 30 INCH SAMPLE OF EACH SIZE BAR USED, AND FOR PROJECTS REQUIRING OVER 400 TONS OF REINFORCING STEEL, TWO 30 INCH SAMPLES OF EACH SIZE BAR USED. THE SAMPLE BARS SHOULD COME FROM STEEL ACTUALLY USED IN THE PROJECT AND THE SAMPLE BARS SHOULD BE REPLACED BY SPICED BARS AS SPECIFIED IN THE SAMPLE BAR REPLACEMENT CHART. PAYMENT FOR THE SAMPLE BARS AND REPLACEMENT REINFORCING STEEL SHALL BE CONSIDERED INCIDENTAL TO VARIOUS PAY ITEMS.
- EXCAVATE 1 FOOT BELOW CULVERT AND REPLACE WITH FOUNDATION CONDITIONING MATERIAL IN ACCORDANCE WITH ARTICLE 414-4 OF THE STANDARD SPECIFICATIONS. FOUNDATION CONDITIONING MATERIAL SHOULD CONSIST OF SELECT MATERIAL CLASS V OR VI FOR RCBC.
- IF REQUIRED, UNDERCUT LOOSE SOILS THAT MAY BE ENCOUNTERED BENEATH THE BOTTOM OF THE FOUNDATION CONDITIONING MATERIAL. BACKFILL UNDERCUT AREAS WITH FOUNDATION CONDITIONING MATERIAL.

PROJECT NO. A-0009CA
GRAHAM COUNTY
 STATION: 195+16.00 -L-

SHEET 1 OF 7

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

DOUBLE 12 FT. x 8 FT. CONCRETE BOX CULVERT
 48° SKEW

6/1/2022

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

TGS ENGINEERS
 804-C N. LAFAYETTE ST
 SHELBY, NC 28150
 PH (704) 476-0003
 CORP. LICENSE NO.: C-0275

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			C6-1
2			4			TOTAL SHEETS 7

LOAD AND RESISTANCE FACTOR RATING (LRFR) SUMMARY FOR REINFORCED CONCRETE BOX CULVERTS

LEVEL	VEHICLE	WEIGHT (W) (TONS)	CONTROLLING LOAD RATING #	MINIMUM RATING FACTORS (RF)	TONS = W x RF	STRENGTH I LIMIT STATE								COMMENT NUMBER		
						LIVE-LOAD FACTORS (γ _{LL})	MOMENT				SHEAR					
							RATING FACTOR	BOX NO.	ELEMENT TYPE	DISTANCE FROM LEFT END OF ELEMENT (ft)	RATING FACTOR	BOX NO.	ELEMENT TYPE		DISTANCE FROM LEFT END OF ELEMENT (ft)	
DESIGN LOAD RATING	HL-93 (INVENTORY)	N/A	1	1.09	--	1.75	1.11	1	TOP SLAB	6.75	1.09	1	TOP SLAB	12.75		
	HL-93 (OPERATING)	N/A		1.41	--	1.35	1.43	1	TOP SLAB	6.75	1.41	1	TOP SLAB	12.75		
	HS-20 (INVENTORY)	36.000	2	1.14	41.04	1.75	1.15	1	TOP SLAB	6.75	1.14	1	TOP SLAB	12.75		
	HS-20 (OPERATING)	36.000		1.47	52.92	1.35	1.49	1	TOP SLAB	6.75	1.47	1	TOP SLAB	12.75		
LEGAL LOAD RATING	SINGLE VEHICLE (SV)	SNSH	13.500		2.30	31.05	1.40	2.30	1	TOP SLAB	6.75	2.88	1	TOP SLAB	12.75	
		SNGARBS2	20.000		2.15	43.00	1.40	2.15	1	TOP SLAB	6.75	2.49	1	TOP SLAB	12.75	
		SNAGRIS2	22.000		2.30	50.60	1.40	2.30	1	TOP SLAB	6.75	2.61	1	TOP SLAB	12.75	
		SNCOTTS3	27.250	3	1.35	36.79	1.40	1.38	1	TOP SLAB	6.75	1.35	1	TOP SLAB	12.75	
		SNAGGRS4	34.925		1.59	55.53	1.40	1.66	1	TOP SLAB	6.75	1.59	1	TOP SLAB	12.75	
		SNS5A	35.550		1.49	52.97	1.40	1.58	1	TOP SLAB	6.75	1.49	1	TOP SLAB	12.75	
		SNS6A	39.950		1.48	59.13	1.40	1.57	1	TOP SLAB	6.75	1.48	1	TOP SLAB	12.75	
		SNS7B	42.000		1.48	62.16	1.40	1.63	1	TOP SLAB	6.75	1.48	1	TOP SLAB	12.75	
	TRUCK TRACTOR SEMI-TRAILER (TTST)	TNAGRIT3	33.000		1.98	65.34	1.40	2.22	1	BOTTOM SLAB	6.75	1.98	1	BOTTOM SLAB	12.75	
		TNT4A	33.075		1.57	51.93	1.40	1.65	1	TOP SLAB	6.75	1.57	1	TOP SLAB	12.75	
		TNT6A	41.600		1.48	61.57	1.40	1.69	1	TOP SLAB	6.75	1.48	1	TOP SLAB	12.75	
		TNT7A	42.000		1.51	63.42	1.40	1.66	1	TOP SLAB	6.75	1.51	1	TOP SLAB	12.75	
		TNT7B	42.000		1.55	65.10	1.40	1.60	1	TOP SLAB	6.75	1.55	1	TOP SLAB	12.75	
		TNAGRIT4	43.000		1.52	65.36	1.40	1.65	1	BOTTOM SLAB	6.75	1.52	1	BOTTOM SLAB	12.75	
TNAGT5A	45.000		1.53	68.85	1.40	1.85	1	TOP SLAB	6.75	1.53	1	TOP SLAB	12.75			
TNAGT5B	45.000		1.49	67.05	1.40	1.65	1	TOP SLAB	6.75	1.49	1	TOP SLAB	12.75			

LOAD FACTORS:

DESIGN LOAD RATING FACTORS

LOAD TYPE	MAX FACTOR	MIN FACTOR
DC	1.25	0.90
DW	1.50	0.65
EV	1.30	0.90
EH	1.35	0.90
ES	1.35	0.90
LS	1.75	--
WA	1.00	--

NOTE:

RATING FACTORS ARE BASED ON THE STRENGTH I LIMIT STATE.

COMMENTS:

- 1.
- 2.
- 3.
- 4.


CONTROLLING LOAD RATING

1 DESIGN LOAD RATING (HL-93)

2 DESIGN LOAD RATING (HS-20)

3 LEGAL LOAD RATING **

** SEE CHART FOR VEHICLE TYPE



LRFR SUMMARY
(LOOKING DOWNSTREAM)

PROJECT NO. A-0009CA
GRAHAM COUNTY
 STATION: 195+16.00 -L-

SHEET 2 OF 7


STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

STANDARD
 LRFR SUMMARY FOR
 REINFORCED CONCRETE
 BOX CULVERTS
 (NON-INTERSTATE TRAFFIC)

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED


REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	C6-2
1			3			TOTAL SHEETS
2			4			7

ASSEMBLED BY : ZCS	DATE : 2/21
CHECKED BY : MGC	DATE : 6/21
DRAWN BY : WMC	7/11
CHECKED BY : GM	7/11
REV. 10/1/11	MAA/GM
REV. 12/17	MAA/THC




PART PLAN - ROOF SLAB **PART PLAN - FLOOR SLAB**

NOTE: FOR S1 BARS IN FLOOR SLAB & WING FOOTING, SEE WING SHEET.



OUTLET END ELEVATION NORMAL TO SKEW

PROJECT NO. A-0009CA
GRAHAM COUNTY
 STATION: 195+16.00 -L-
 SHEET 4 OF 7



STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
 DOUBLE 12 FT. x 8 FT.
 CONCRETE BOX CULVERT
 48° SKEW

DRAWN BY : ZCS DATE : 2/21
 CHECKED BY : MGC DATE : 6/21
 DESIGN ENGINEER OF RECORD: ZCS DATE : 11/21


DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED
TGS ENGINEERS
 706 HILLSBOROUGH STREET
 SUITE 200
 RALEIGH, NC 27603
 PH (919) 773-8887
 CORP. LICENSE NO.: C-0275

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	C6-4
1			3			TOTAL SHEETS
2			4			7

BILL OF MATERIAL

BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT	BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT	BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT	BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT	BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
A1	270	#5	1	7'-1"	1995	A200	108	#5	STR	25'-11"	2919	A300	108	#7	STR	25'-11"	5721	A400	108	#7	STR	25'-11"	5721	B1	140	#5	STR	9'-11"	1448
A2	270	#5	1	5'-9"	1619	A201	2	#5	STR	25'-4"	53	A301	2	#7	STR	25'-4"	104	A401	2	#7	STR	25'-4"	104	B2	278	#4	STR	7'-4"	1362
A100	97	#6	STR	25'-11"	3776	A202	2	#5	STR	24'-6"	51	A302	2	#7	STR	24'-6"	100	A402	2	#7	STR	24'-6"	100	B3	208	#4	STR	9'-11"	1378
A101	2	#6	STR	25'-4"	76	A203	2	#5	STR	23'-8"	49	A303	2	#7	STR	23'-8"	97	A403	2	#7	STR	23'-8"	97						
A102	2	#6	STR	24'-5"	73	A204	2	#5	STR	22'-10"	48	A304	2	#7	STR	22'-10"	93	A404	2	#7	STR	22'-10"	93	C1	276	#4	STR	36'-4"	6699
A103	2	#6	STR	23'-6"	71	A205	2	#5	STR	22'-0"	46	A305	2	#7	STR	22'-0"	90	A405	2	#7	STR	22'-0"	90						
A104	2	#6	STR	22'-7"	68	A206	2	#5	STR	21'-2"	44	A306	2	#7	STR	21'-2"	87	A406	2	#7	STR	21'-2"	87	D1	24	#6	STR	2'-9"	99
A105	2	#6	STR	21'-8"	65	A207	2	#5	STR	20'-4"	42	A307	2	#7	STR	20'-4"	83	A407	2	#7	STR	20'-4"	83	D2	24	#6	STR	1'-9"	63
A106	2	#6	STR	20'-9"	62	A208	2	#5	STR	19'-6"	41	A308	2	#7	STR	19'-6"	80	A408	2	#7	STR	19'-6"	80						
A107	2	#6	STR	19'-10"	60	A209	2	#5	STR	18'-8"	39	A309	2	#7	STR	18'-8"	76	A409	2	#7	STR	18'-8"	76	G1	8	#5	STR	34'-10"	291
A108	2	#6	STR	18'-10"	57	A210	2	#5	STR	17'-10"	37	A310	2	#7	STR	17'-10"	73	A410	2	#7	STR	17'-10"	73						
A109	2	#6	STR	17'-11"	54	A211	2	#5	STR	17'-0"	35	A311	2	#7	STR	17'-0"	69	A411	2	#7	STR	17'-0"	69	S10	12	#8	STR	34'-10"	1116
A110	2	#6	STR	17'-0"	51	A212	2	#5	STR	16'-2"	34	A312	2	#7	STR	16'-2"	66	A412	2	#7	STR	16'-2"	66						
A111	2	#6	STR	16'-1"	48	A213	2	#5	STR	15'-4"	32	A313	2	#7	STR	15'-4"	63	A413	2	#7	STR	15'-4"	63						
A112	2	#6	STR	15'-2"	46	A214	2	#5	STR	14'-6"	30	A314	2	#7	STR	14'-6"	59	A414	2	#7	STR	14'-6"	59						
A113	2	#6	STR	14'-3"	43	A215	2	#5	STR	13'-8"	29	A315	2	#7	STR	13'-8"	56	A415	2	#7	STR	13'-8"	56						
A114	2	#6	STR	13'-4"	40	A216	2	#5	STR	12'-10"	27	A316	2	#7	STR	12'-10"	52	A416	2	#7	STR	12'-10"	52						
A115	2	#6	STR	12'-5"	37	A217	2	#5	STR	12'-0"	25	A317	2	#7	STR	12'-0"	49	A417	2	#7	STR	12'-0"	49						
A116	2	#6	STR	11'-6"	35	A218	2	#5	STR	11'-2"	23	A318	2	#7	STR	11'-2"	46	A418	2	#7	STR	11'-2"	46						
A117	2	#6	STR	11'-6"	35	A219	2	#5	STR	10'-4"	22	A319	2	#7	STR	10'-4"	42	A419	2	#7	STR	10'-4"	42						
A118	2	#6	STR	10'-7"	32	A220	2	#5	STR	9'-6"	20	A320	2	#7	STR	9'-6"	39	A420	2	#7	STR	9'-6"	39						
A119	2	#6	STR	9'-7"	29	A221	2	#5	STR	8'-8"	18	A321	2	#7	STR	8'-8"	35	A421	2	#7	STR	8'-8"	35						
A120	2	#6	STR	8'-8"	26	A222	2	#5	STR	7'-10"	16	A322	2	#7	STR	7'-10"	32	A422	2	#7	STR	7'-10"	32						
A121	2	#6	STR	7'-9"	23	A223	2	#5	STR	7'-0"	15	A323	2	#7	STR	7'-0"	29	A423	2	#7	STR	7'-0"	29						
A122	2	#6	STR	6'-10"	21	A224	2	#5	STR	6'-2"	13	A324	2	#7	STR	6'-2"	25	A424	2	#7	STR	6'-2"	25						
A123	2	#6	STR	5'-11"	18	A225	2	#5	STR	5'-11"	18	A325	2	#7	STR	5'-4"	22	A425	2	#7	STR	5'-4"	22						
A124	2	#6	STR	5'-0"	15	A226	2	#5	STR	4'-6"	9	A326	2	#7	STR	4'-6"	18	A426	2	#7	STR	4'-6"	18						
A124	2	#6	STR	4'-1"	12	A227	2	#5	STR	3'-8"	8	A327	2	#7	STR	3'-8"	15	A427	2	#7	STR	3'-8"	15						
REINFORCING STEEL																								LBS.	39,286				

BAR TYPE



BAR DIMENSIONS ARE OUT TO OUT

SPLICE LENGTHS CHART





BAR	SIZE	SPLICE LENGTH
"B"	#4	1'-10"
C1	#4	1'-11"
"S"	#6	2'-9"
"S"	#8	3'-8"

NOTES


NATIVE MATERIAL BETWEEN SILLS IN THE CULVERT SHALL PROVIDE A CONTINUOUS FLOW CHANNEL. NATIVE MATERIAL CONSISTS OF MATERIAL THAT IS EXCAVATED FROM THE STREAM BED AT THE PROJECT SITE DURING CONSTRUCTION. NATIVE MATERIAL IS SUBJECT TO APPROVAL BY THE ENGINEER AND MAY BE SUBJECT TO PERMIT CONDITIONS.

THE ENTIRE COST OF WORK REQUIRED TO PLACE EXCAVATED MATERIAL OR SUPPLEMENTAL MATERIAL AS SHOWN ON THE PLANS SHALL BE INCLUDED IN THE CONTRACT LUMP SUM PRICE BID FOR CULVERT EXCAVATION.

THE ENTIRE COST OF WORK REQUIRED TO CONSTRUCT THE SILLS SHALL BE INCLUDED IN THE VARIOUS PAY ITEMS.



PROJECT NO. A-0009CA
GRAHAM COUNTY
 STATION: 195+16.00 -L-
 SHEET 5 OF 7




STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
**DOUBLE 12 FT. X 8 FT.
 CONCRETE BOX CULVERT
 48° SKEW**

DRAWN BY : ZCS DATE : 2/21
 CHECKED BY : MGC DATE : 6/21
 DESIGN ENGINEER OF RECORD: ZCS DATE : 11/21


DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED
TGS ENGINEERS
 706 HILLSBOROUGH STREET
 SUITE 200
 RALEIGH, NC 27603
 PH (919) 773-8887
 CORP. LICENSE NO.: C-0275

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			C6-5
2			4			TOTAL SHEETS
						7




PLAN W3


*CENTER ALL #6 C2 BARS ON C CENTERFORT




PLAN W2




ELEVATION W3




ELEVATION W2



SECTION B-B




WING SECTION



SECTION A-A

STANDARD REINFORCING STEEL IN BARREL NOT SHOWN

BILL OF MATERIAL					
BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
B4	2	#4	STR	9'-0"	12
C2	12	#6	STR	8'-0"	144
H12	4	#4	STR	31'-1"	83
H13	2	#4	STR	27'-8"	37
H14	2	#4	STR	19'-7"	26
H15	2	#4	STR	11'-7"	15
H16	2	#4	STR	3'-7"	5
H17	12	#4	1	3'-6"	28
H18	2	#4	STR	31'-8"	42
M1	5	#8	2	16'-4"	218
N13	3	#4	3	4'-7"	9
N14	3	#4	3	5'-2"	10
N15	3	#4	3	5'-8"	11
N16	3	#4	3	6'-3"	13
N17	3	#4	3	6'-10"	14
N18	3	#4	3	7'-4"	15
N19	3	#4	3	7'-11"	16
N20	3	#5	3	8'-5"	26
N21	3	#5	3	9'-1"	28
N22	3	#5	3	9'-7"	30
N23	2	#5	3	10'-2"	21
N24	2	#5	3	10'-5"	22
P1	2	#9	4	6'-9"	46
P2	2	#9	5	12'-6"	85
S2	1	#4	6	11'-3"	8
S3	1	#4	6	10'-5"	7
S4	1	#4	6	9'-9"	7
S5	1	#4	6	9'-1"	6
S6	1	#4	6	8'-5"	6
S7	1	#4	6	7'-9"	5
S8	1	#4	6	7'-1"	5
S9	1	#4	6	6'-5"	4
T3	2	#5	STR	12'-0"	25
T4	4	#5	STR	33'-0"	138
V15	3	#4	STR	2'-6"	5
V16	3	#4	STR	3'-1"	6
V17	3	#4	STR	3'-7"	7
V18	3	#4	STR	4'-2"	8
V19	3	#4	STR	4'-9"	10
V20	3	#4	STR	5'-4"	11
V21	3	#4	STR	5'-10"	12
V22	3	#4	STR	6'-5"	13
V23	3	#4	STR	7'-0"	14
V24	3	#4	STR	7'-7"	15
V25	2	#4	STR	8'-2"	11
V26	2	#4	STR	8'-9"	12
V27	2	#4	STR	4'-0"	5
V28	2	#4	STR	8'-0"	11
Z17	3	#4	7	3'-1"	6
Z18	3	#4	7	3'-7"	7
Z19	3	#5	7	4'-2"	13
Z20	3	#5	7	4'-8"	15
Z21	3	#5	7	5'-2"	16
Z22	3	#5	7	5'-7"	17
Z23	3	#5	7	6'-1"	19
Z24	3	#5	7	6'-7"	21
Z25	3	#5	7	7'-1"	22
Z26	3	#5	7	7'-7"	24
Z27	2	#5	7	8'-1"	17
Z28	2	#6	7	8'-5"	25
Z29	4	#10	7	8'-10"	152
Z30	5	#10	STR	9'-2"	197
Z31	5	#10	STR	8'-4"	179
Z32	5	#10	STR	7'-8"	165
REINFORCING STEEL FOR 1 W2 WING				2,202 LBS.	
REINFORCING STEEL FOR 1 W3 WING				2,202 LBS.	




DIMENSIONS ARE OUT TO OUT

SHORT WING W2					
BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
H1	6	#4	STR	7'-7"	30
H2	2	#4	STR	6'-10"	9
H3	2	#4	STR	3'-7"	5
H4	12	#4	1	3'-3"	26
H5	2	#4	STR	8'-5"	11
N1	2	#5	3	10'-1"	21
N2	2	#5	3	9'-2"	19
N3	3	#5	3	7'-9"	24
N4	3	#4	3	6'-5"	13
S1	3	#6	STR	6'-0"	27
T1	3	#5	STR	9'-6"	30
V1	2	#4	STR	8'-1"	11
V2	2	#4	STR	7'-1"	9
V3	3	#4	STR	5'-9"	12
V4	3	#4	STR	4'-4"	9
Z1	2	#5	7	6'-2"	13
Z2	2	#5	7	5'-3"	11
Z3	3	#4	7	3'-8"	8
Z4	3	#4	7	2'-8"	6
REINFORCING STEEL FOR 1 W2 WING				294 LBS.	

TOTAL WING QUANTITIES	
REINFORCING STEEL FOR 2 WINGS	2,496 LBS.
CLASS A CONCRETE	
2 WINGS	20.5 C.Y.
1 END CURTAIN WALL	1.9 C.Y.
1 HEADWALL	1.6 C.Y.
TOTAL	24.0 C.Y.

NOTE:
A 3 FOOT STRIP OF FILTER FABRIC SHALL BE ATTACHED TO THE FILL FACE OF THE WING COVERING THE ENTIRE LENGTH OF THE EXPANSION JOINT.
G1 BARS IN HEADWALL ARE INCLUDED WITH THE BARREL REINFORCING STEEL.




DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED
TGS ENGINEERS
 706 HILLSBOROUGH STREET SUITE 200
 RALEIGH, NC 27603
 PH (919) 773-8887
 CORP. LICENSE NO.: C-0275

PROJECT NO. A-0009CA
 COUNTY GRAHAM
 STATION: 195+16.00 -L-
 SHEET 7 OF 7

DEPARTMENT OF TRANSPORTATION RALEIGH					
OUTLET WINGS W2 AND W3					
REVISIONS					
NO.	BY:	DATE:	NO.	BY:	DATE:
1			3		
2			4		

DRAWN BY :	ZCS	DATE :	2/21
CHECKED BY :	MGC	DATE :	6/21
DESIGN ENGINEER OF RECORD:	ZCS	DATE :	11/21

BENCH MARK #8: SPIKE NAIL SET IN BASE OF 14" POPLAR
28' LT. OF STA. 157+59 -L-; ELEV. 2148.72'



LOCATION SKETCH

TOTAL STRUCTURE QUANTITIES			
CLASS A CONCRETE			
BARREL @	2.032	CY/FT	130.0 C.Y.
SILLS			3.0 C.Y.
WINGS, ETC.			34.4 C.Y.
TOTAL			167.4 C.Y.
REINFORCING STEEL			
BARREL			22,438 LBS.
WINGS, ETC.			2,093 LBS.
TOTAL			24,531 LBS.
CULVERT EXCAVATION			LUMP SUM
FOUNDATION COND. MAT'L.			98 TONS


SAMPLE BAR REPLACEMENT	
SIZE	LENGTH
#3	6'-2"
#4	7'-4"
#5	8'-6"
#6	9'-8"
#7	10'-10"
#8	12'-0"
#9	13'-2"
#10	14'-6"
#11	15'-10"

NOTE:
SAMPLE BAR REPLACEMENT LENGTHS BASED ON 30" (SAMPLE LENGTH) PLUS TWO SPLICE LENGTHS AND f_y = 60ksi.

ROADWAY DATA	
GRADE POINT ELEV. @ STA. 10+59.00 -DR1A-	= 2164.10'
BED ELEV. @ STA. 10+59.00 -DR1A-	= 2145.90'
ROADWAY SLOPES	= 2 : 1
HYDROGRAPHIC DATA	
DESIGN DISCHARGE	= 610 CFS
FREQUENCY OF DESIGN FLOOD	= 2 YRS
DESIGN HIGH WATER ELEVATION	= 2152.5'
DRAINAGE AREA	= 9.07 SQ. MI.
BASE DISCHARGE (Q100)	= 2980 CFS
BASE HIGH WATER ELEVATION	= 2154.4'
OVERTOPPING FLOOD DATA	
OVERTOPPING DISCHARGE	= 620 CFS
FREQUENCY OF OVERTOPPING FLOOD	= >2 YRS
OVERTOPPING FLOOD ELEVATION	= 2153.8'

NOTES:

- ASSUMED LIVE LOAD ----- HL-93 OR ALTERNATE LOADING.
- DESIGN FILL----- 9.15' MAX.
- FOR OTHER DESIGN DATA AND NOTES, SEE STANDARD NOTES SHEET.
- 3" Ø WEEP HOLES INDICATED TO BE IN ACCORDANCE WITH THE SPECIFICATIONS.
- CONCRETE IN CULVERTS TO BE POURED IN THE FOLLOWING ORDER:
 1. WING FOOTINGS AND FLOOR SLAB INCLUDING 4" OF ALL VERTICAL WALLS.
 2. THE REMAINING PORTIONS OF THE WALLS AND WINGS FULL HEIGHT FOLLOWED BY ROOF SLAB AND HEADWALLS.
- THE RESIDENT ENGINEER SHALL CHECK THE LENGTH OF CULVERT BEFORE STAKING IT OUT TO MAKE CERTAIN THAT IT WILL PROPERLY TAKE CARE OF THE FILL.
- DIMENSIONS FOR WING LAYOUT AS WELL AS ADDITIONAL REINFORCING STEEL EMBEDDED IN BARREL ARE SHOWN ON WING SHEET.
- TRANSVERSE CONSTRUCTION JOINTS SHALL BE USED IN THE BARREL, SPACED TO LIMIT THE POURS TO A MAXIMUM OF 70 FT. LOCATION OF JOINTS SHALL BE SUBJECT TO APPROVAL OF THE ENGINEER.
- AT THE CONTRACTOR'S OPTION, HE MAY SPLICE THE VERTICAL REINFORCING STEEL IN THE INTERIOR FACE OF EXTERIOR WALL ABOVE LOWER WALL CONSTRUCTION JOINT. THE SPLICE LENGTH SHALL BE AS PROVIDED IN THE SPLICE LENGTH CHART SHOWN ON THE PLANS. EXTRA WEIGHT OF STEEL DUE TO THE SPLICES SHALL BE PAID FOR BY THE CONTRACTOR.
- FOR CULVERT DIVERSION DETAILS AND PAY ITEM, SEE EROSION CONTROL PLANS.
- FOR CRANE SAFETY, SEE SPECIAL PROVISIONS.
- FOR SUBMITTAL OF WORKING DRAWINGS, SEE SPECIAL PROVISIONS.
- FOR FALSEWORK AND FORMWORK, SEE SPECIAL PROVISIONS.
- FOR GROUT FOR STRUCTURES, SEE SPECIAL PROVISIONS.
- FOR EROSION CONTROL MEASURES, SEE EROSION CONTROL PLANS.
- AT THE CONTRACTOR'S OPTION HE MAY SUBMIT, TO THE ENGINEER FOR APPROVAL, DESIGN AND DETAIL DRAWINGS FOR A PRECAST REINFORCED CONCRETE BOX CULVERT IN LIEU OF THE CAST-IN-PLACE CULVERT SHOWN ON THE PLANS. THE DESIGN SHALL PROVIDE THE SAME SIZE AND NUMBER OF BARRELS AS USED ON THE CAST-IN-PLACE DESIGN. FOR OPTIONAL PRECAST REINFORCED CONCRETE BOX CULVERT, SEE SPECIAL PROVISIONS.
- THE CONTRACTOR SHALL PROVIDE INDEPENDENT ASSURANCE SAMPLES OF REINFORCING STEEL AS FOLLOWS: FOR PROJECTS REQUIRING UP TO 400 TONS OF REINFORCING STEEL, ONE 30 INCH SAMPLE OF EACH SIZE BAR USED, AND FOR PROJECTS REQUIRING OVER 400 TONS OF REINFORCING STEEL, TWO 30 INCH SAMPLES OF EACH SIZE BAR USED. THE SAMPLE BARS SHOULD COME FROM STEEL ACTUALLY USED IN THE PROJECT AND THE SAMPLE BARS SHOULD BE REPLACED BY SPICED BARS AS SPECIFIED IN THE SAMPLE BAR REPLACEMENT CHART. PAYMENT FOR THE SAMPLE BARS AND REPLACEMENT REINFORCING STEEL SHALL BE CONSIDERED INCIDENTAL TO VARIOUS PAY ITEMS.
- EXCAVATE 1 FOOT BELOW THE BOTTOM OF THE CULVERT AND REPLACE WITH FOUNDATION CONDITIONING MATERIAL IN ACCORDANCE WITH ARTICLE 414-4 OF THE STANDARD SPECIFICATIONS. FOUNDATION CONDITIONING MATERIAL SHOULD CONSIST OF SELECT MATERIAL CLASS V OR VI FOR RCBC.
- IF REQUIRED, UNDERCUT LOOSE SOILS THAT MAY BE ENCOUNTERED BENEATH THE BOTTOM OF THE FOUNDATION CONDITIONING MATERIAL. BACKFILL UNDERCUT AREAS WITH FOUNDATION CONDITIONING MATERIAL.



PROFILE ALONG CULVERT

DRAWN BY : STM DATE : 02/22
 CHECKED BY : MGC DATE : 03/22
 DESIGN ENGINEER OF RECORD: STM DATE : 03/22

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

SINGLE 16 FT. X 9 FT. CONCRETE BOX CULVERT
 90°-00'-00" SKEW

6/1/2022

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

TGS ENGINEERS
 706 HILLSBOROUGH STREET
 SUITE 200
 RALEIGH, NC 27603
 PH (919) 773-8887
 CORP. LICENSE NO.: C-0275

PROJECT NO. A-0009CA
GRAHAM COUNTY
 STATION: 10+59.00 -DR1A-

SHEET 1 OF 8

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	C7-1
1			3			TOTAL SHEETS
2			4			8

LOAD AND RESISTANCE FACTOR RATING (LRFR) SUMMARY FOR REINFORCED CONCRETE BOX CULVERTS

LEVEL	VEHICLE	WEIGHT (W) (TONS)	CONTROLLING LOAD RATING #	MINIMUM RATING FACTORS (RF)	TONS = W x RF	STRENGTH I LIMIT STATE								COMMENT NUMBER		
						MOMENT				SHEAR						
						LIVE-LOAD FACTORS (γ _{LL})	RATING FACTOR	BOX NO.	ELEMENT TYPE	DISTANCE FROM LEFT END OF ELEMENT (ft)	RATING FACTOR	BOX NO.	ELEMENT TYPE		DISTANCE FROM LEFT END OF ELEMENT (ft)	
DESIGN LOAD RATING	HL-93 (INVENTORY)	N/A	①	1.14	--	1.75	1.14	1	EXTERIOR WALL	0.42	1.79	1	BOTTOM SLAB	0.33		
	HL-93 (OPERATING)	N/A		1.48	--	1.35	1.48	1	EXTERIOR WALL	0.42	2.32	1	BOTTOM SLAB	0.33		
	HS-20 (INVENTORY)	36.000	②	1.18	42.48	1.75	1.18	1	EXTERIOR WALL	0.42	1.86	1	BOTTOM SLAB	0.33		
	HS-20 (OPERATING)	36.000		1.53	55.08	1.35	1.53	1	EXTERIOR WALL	0.42	2.41	1	BOTTOM SLAB	0.33		
LEGAL LOAD RATING	SINGLE VEHICLE (SV)	SNSH	13.500		2.63	35.51	1.40	2.63	1	EXTERIOR WALL	0.42	4.73	1	TOP SLAB	0.33	
		SNGARBS2	20.000		2.38	47.60	1.40	2.38	1	EXTERIOR WALL	0.42	4.02	1	BOTTOM SLAB	0.33	
		SNAGRIS2	22.000		2.43	53.46	1.40	2.43	1	EXTERIOR WALL	0.42	4.05	1	BOTTOM SLAB	0.33	
		SNCOTTS3	27.250		1.42	38.70	1.40	1.42	1	EXTERIOR WALL	0.42	2.20	1	BOTTOM SLAB	0.33	
		SNAGGRS4	34.925		1.42	49.59	1.40	1.42	1	EXTERIOR WALL	0.42	2.10	1	BOTTOM SLAB	15.67	
		SNS5A	35.550		1.48	52.61	1.40	1.48	1	EXTERIOR WALL	0.42	2.27	1	BOTTOM SLAB	0.33	
		SNS6A	39.950		1.30	51.94	1.40	1.30	1	EXTERIOR WALL	0.42	1.94	1	BOTTOM SLAB	0.33	
		SNS7B	42.000	③	1.25	52.50	1.40	1.25	1	EXTERIOR WALL	0.42	1.86	1	BOTTOM SLAB	0.33	
	TRUCK TRACTOR SEMI-TRAILER (TTST)	TNAGRIT3	33.000		1.74	57.42	1.40	1.74	1	EXTERIOR WALL	0.42	2.72	1	BOTTOM SLAB	15.67	
		TNT4A	33.075		1.56	51.60	1.40	1.56	1	EXTERIOR WALL	0.42	2.40	1	BOTTOM SLAB	0.33	
		TNT6A	41.600		1.38	57.41	1.40	1.38	1	EXTERIOR WALL	0.42	2.05	1	BOTTOM SLAB	15.67	
		TNT7A	42.000		1.50	63.00	1.40	1.50	1	EXTERIOR WALL	0.42	2.29	1	BOTTOM SLAB	15.67	
		TNT7B	42.000		1.40	58.80	1.40	1.40	1	EXTERIOR WALL	0.42	2.16	1	BOTTOM SLAB	0.33	
		TNAGRIT4	43.000		1.47	63.21	1.40	1.47	1	EXTERIOR WALL	0.42	2.22	1	BOTTOM SLAB	0.33	
TNAGT5A	45.000		1.43	64.35	1.40	1.43	1	EXTERIOR WALL	0.42	2.09	1	BOTTOM SLAB	0.33			
TNAGT5B	45.000		1.39	62.55	1.40	1.39	1	EXTERIOR WALL	0.42	2.07	1	BOTTOM SLAB	0.33			

LOAD FACTORS:

DESIGN LOAD RATING FACTORS

LOAD TYPE	MAX FACTOR	MIN FACTOR
DC	1.25	0.90
DW	1.50	0.65
EV	1.30	0.90
EH	1.35	0.90
ES	1.35	0.90
LS	1.75	--
WA	1.00	--

NOTE:

RATING FACTORS ARE BASED ON THE STRENGTH I LIMIT STATE.

COMMENTS:

- 1.
- 2.
- 3.
- 4.


CONTROLLING LOAD RATING

① DESIGN LOAD RATING (HL-93)

② DESIGN LOAD RATING (HS-20)

③ LEGAL LOAD RATING **

** SEE CHART FOR VEHICLE TYPE




LRFR SUMMARY

(LOOKING DOWNSTREAM)

PROJECT NO. A-0009CA
GRAHAM COUNTY
 STATION: 10+59.00 -DR1A-

SHEET 2 OF 8




STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
 STANDARD
 LRFR SUMMARY FOR
 REINFORCED CONCRETE
 BOX CULVERT

ASSEMBLED BY : STM	DATE : 02/22
CHECKED BY : MGC	DATE : 03/22
DRAWN BY : WMC	7/11
CHECKED BY : GM	7/11
REV. 10/1/11	MAA/GM
REV. 12/17	MAA/THC


DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

TGS ENGINEERS
 706 HILLSBOROUGH STREET
 SUITE 200
 RALEIGH, NC 27603
 PH (919) 773-8887
 CORP. LICENSE NO.: C-0275


REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			C7-2
2			4			TOTAL SHEETS 8




CULVERT SECTION NORMAL TO ROADWAY



INLET END ELEVATION




OUTLET END ELEVATION



RIGHT ANGLE SECTION OF BARREL

THERE ARE 54 C1 BARS IN SECTION OF BARREL



DETAIL

CONNECTION OF WING FOOTING AND FLOOR SLAB WHEN SLAB IS THICKER THAN FOOTING

PROJECT NO. A-0009CA
GRAHAM COUNTY
 STATION: 10+59.00 -DR1A-

SHEET 3 OF 8

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

**SINGLE 16 FT. X 9 FT. CONCRETE BOX CULVERT
 90°-00'-00" SKEW**


6/1/2022

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

TGS ENGINEERS
 706 HILLSBOROUGH STREET
 SUITE 200
 RALEIGH, NC 27603
 PH (919) 773-8887
 CORP. LICENSE NO.: C-0275

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	C7-3
1			3			TOTAL SHEETS
2			4			8

ASSEMBLED BY: STM DATE: 02/22
 CHECKED BY: MGC DATE: 03/22




PROJECT NO. A-0009CA
GRAHAM COUNTY
 STATION: 10+59.00 -DR1A-
 SHEET 4 OF 8

PLAN OF FLOOR SLAB
 FOR S1 BARS IN FLOOR SLAB AND WING FOOTINGS, SEE WING SHEET.

		STATE OF NORTH CAROLINA		SHEET NO. C7-4			
		DEPARTMENT OF TRANSPORTATION RALEIGH					
TGS ENGINEERS 706 HILLSBOROUGH STREET SUITE 200 RALEIGH, NC 27603 PH (919) 773-8887 CORP. LICENSE NO.: C-0275		SINGLE 16 FT. X 9 FT. CONCRETE BOX CULVERT 90°-00'-00" SKEW		TOTAL SHEETS 8			
		REVISIONS					
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED		NO.	BY:	DATE:	NO.	BY:	DATE:
		1			3		
		2			4		

DRAWN BY : STM DATE : 02/22
 CHECKED BY : MGC DATE : 03/22
 DESIGN ENGINEER OF RECORD: STM DATE : 03/22



PLAN OF ROOF SLAB

PROJECT NO. A-0009CA
GRAHAM COUNTY
 STATION: 10+59.00 -DR1A-

SHEET 5 OF 8



STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH


SINGLE 16 FT. X 9 FT.
 CONCRETE BOX CULVERT
 90°-00'-00" SKEW

DRAWN BY :	STM	DATE :	02/22
CHECKED BY :	MGC	DATE :	03/22
DESIGN ENGINEER OF RECORD:	STM	DATE :	03/22

DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED

TGS ENGINEERS
 706 HILLSBOROUGH STREET
 SUITE 200
 RALEIGH, NC 27603
 PH (919) 773-8887
 CORP. LICENSE NO.: C-0275

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	C7-5
1			3			TOTAL SHEETS
2			4			8



PLAN OF FLOOR SILL LAYOUT

BAR TYPE		BAR SCHEDULE					
VERTICAL LEG ① 6" R. 3'-2 1/2" 3'-1 1/2"		BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
		A1	256	#6	1	7'-5"	2852
		A2	256	#6	1	7'-0"	2692
		A100	128	#8	STR	17'-4"	5924
		A200	128	#8	STR	17'-4"	5924
		B1	256	#4	STR	10'-10"	1853
		B2	128	#4	STR	8'-4"	713
		C1	108	#4	STR	33'-0"	2381
		D1	20	#6	STR	1'-9"	53
		G1	4	#4	STR	17'-4"	46
REINFORCING STEEL						22,438 LBS	

DIMENSIONS ARE OUT TO OUT.


SPLICE LENGTHS CHART		
BAR	SIZE	SPLICE LENGTH
C1	#4	1'-10"

NOTES

MATERIAL EXCAVATED FROM THE EXISTING BED SHALL BE STOCKPILED FOR USE IN THE PROPOSED CULVERT. BED MATERIAL MAY BE SUPPLEMENTED WITH CLASS B RIP RAP AS NECESSARY. NATIVE MATERIAL SHOULD BE PLACED ON TOP TO PROVIDE A FLAT SURFACE FOR ANIMAL PASSAGE. BED MATERIAL IS SUBJECT TO THE APPROVAL BY THE ENGINEER AND MAY BE SUBJECT TO PERMIT CONDITIONS.


THE ENTIRE COST OF WORK REQUIRED TO PLACE EXCAVATED MATERIAL OR SUPPLEMENTAL MATERIAL AS SHOWN ON THE PLANS SHALL BE INCLUDED IN THE CONTRACT LUMP SUM PRICE BID FOR CULVERT EXCAVATION.

THE ENTIRE COST OF WORK REQUIRED TO CONSTRUCT THE SILLS SHALL BE INCLUDED IN THE VARIOUS PAY ITEMS.



SECTION THROUGH SILL

* DOWELS MAY BE PUSHED INTO GREEN CONCRETE AFTER SLAB HAS BEEN FLOAT FINISHED.



ELEVATION

SILL DETAILS

PROJECT NO. A-0009CA
GRAHAM COUNTY
 STATION: 10+59.00 -DR1A-


SHEET 6 OF 8




STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
**SINGLE 16 FT. X 9 FT.
 CONCRETE BOX
 CULVERT**

DRAWN BY :	STM	DATE :	02/22
CHECKED BY :	MGC	DATE :	03/22
DESIGN ENGINEER OF RECORD:	STM	DATE :	03/22


DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED		REVISIONS			SHEET NO.
TGS ENGINEERS	706 HILLSBOROUGH STREET	NO.	BY:	DATE:	C7-6
RALEIGH, NC 27603	SUITE 200	1			TOTAL SHEETS
PH (919) 773-8887		2			8
CORP. LICENSE NO.: C-0275		3			
		4			




PLAN W2



PLAN W1




TYPICAL WING SECTION




ALL BAR DIMENSIONS ARE OUT TO OUT.

NOTES
 A 3 FOOT STRIP OF FILTER FABRIC SHALL BE ATTACHED TO THE FILL FACE OF THE WING COVERING THE ENTIRE LENGTH OF THE EXPANSION JOINT.
 G1 BARS IN HEADWALL ARE INCLUDED WITH THE BARREL REINFORCING STEEL.

INLET WINGS BILL OF MATERIAL					
BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
H1	8	#4	STR	12'-4"	66
H2	2	#4	STR	9'-9"	13
H3	2	#4	STR	5'-1"	7
H4	14	#4	1	3'-3"	30
H5	2	#4	STR	12'-11"	17
H6	6	#4	STR	12'-4"	49
H7	2	#4	STR	9'-11"	13
H8	2	#4	STR	6'-5"	9
H9	2	#4	STR	3'-2"	4
H10	14	#4	1	3'-3"	30
H11	2	#4	STR	13'-5"	18
N1	2	#6	2	11'-6"	35
N2	1	#6	2	11'-2"	17
N3	3	#5	2	10'-2"	32
N4	3	#5	2	9'-3"	29
N5	3	#4	2	8'-3"	17
N6	3	#4	2	7'-3"	15
N7	2	#6	2	11'-5"	34
N8	1	#6	2	10'-11"	16
N9	3	#5	2	9'-7"	30
N10	3	#5	2	8'-3"	26
N11	3	#4	2	6'-11"	14
N12	3	#4	2	5'-7"	11
S1	6	#6	STR	6'-0"	54
T1	6	#5	STR	14'-3"	89
V1	2	#4	STR	9'-4"	12
V2	1	#4	STR	9'-0"	6
V3	3	#4	STR	8'-1"	16
V4	3	#4	STR	7'-2"	14
V5	3	#4	STR	6'-2"	12
V6	3	#4	STR	5'-3"	11
V7	2	#4	STR	9'-2"	12
V8	1	#4	STR	8'-9"	6
V9	3	#4	STR	7'-6"	15
V10	3	#4	STR	6'-3"	13
V11	3	#4	STR	4'-11"	10
V12	3	#4	STR	3'-7"	7
Z1	6	#5	3	6'-6"	41
Z2	6	#5	3	5'-9"	36
Z3	6	#4	3	4'-11"	20
Z4	6	#4	3	4'-1"	16
Z5	6	#4	3	3'-4"	13
REINFORCING STEEL FOR W1 & W2				935 LBS	
CLASS A CONCRETE					
2 WINGS				13.6 CY	
1 HEADWALL				0.8 CY	
1 END CURTAIN WALL				0.9 CY	
TOTAL				15.3 CY	



ELEVATION W2



ELEVATION W1

PROJECT NO. A-0009CA
GRAHAM COUNTY
 STATION: 10+59.00 -DR1A-

SHEET 7 OF 8

6/1/2022


DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

TGS ENGINEERS
 706 HILLSBOROUGH STREET
 SUITE 200
 RALEIGH, NC 27603
 PH (919) 773-8887
 CORP. LICENSE NO.: C-0275


STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH					
INLET WINGS FOR CONCRETE BOX CULVERT					
H = 9'-0" SLOPE = 2:1					
90° SKEW					
REVISIONS					
NO.	BY:	DATE:	NO.	BY:	DATE:
1			3		
2			4		

SHEET NO. C7-7
TOTAL SHEETS 8


ASSEMBLED BY : STM DATE : 03/22
 CHECKED BY : MGC DATE : 03/22




PLAN W1




PLAN W3



TYPICAL WING SECTION



ELEVATION W1



ELEVATION W3

BAR TYPES	
①	
②	
③	

BAR NO.	SIZE	TYPE	LENGTH	WEIGHT
Z1	#5	STR	5'-11"	7"
Z2	#5	STR	5'-2"	7"
Z3	#4	STR	4'-5"	6"
Z4	#4	STR	3'-7"	6"
Z5	#4	STR	2'-10"	6"
Z6	#4	STR	6'-1"	7"
Z7	#4	STR	5'-4"	7"
Z8	#4	STR	4'-8"	6"
Z9	#4	STR	4'-1"	6"
Z10	#4	STR	3'-5"	6"
Z11	#4	STR	2'-10"	6"

ALL BAR DIMENSIONS ARE OUT TO OUT.

NOTES

A 3 FOOT STRIP OF FILTER FABRIC SHALL BE ATTACHED TO THE FILL FACE OF THE WING COVERING THE ENTIRE LENGTH OF THE EXPANSION JOINT.

G1 BARS IN HEADWALL ARE INCLUDED WITH THE BARREL REINFORCING STEEL.

OUTLET WINGS BILL OF MATERIAL					
BAR NO.	SIZE	TYPE	LENGTH	WEIGHT	
H1	#4	STR	12'-4"	49	
H2	#4	STR	9'-10"	13	
H3	#4	STR	6'-5"	9	
H4	#4	STR	3'-2"	4	
H5	#4	STR	3'-3"	30	
H6	#4	STR	13'-5"	18	
H7	#4	STR	21'-1"	85	
H8	#4	STR	20'-7"	27	
H9	#4	STR	14'-2"	19	
H10	#4	STR	7'-8"	10	
H11	#4	STR	3'-3"	30	
H12	#4	STR	21'-7"	29	
N1	#6	STR	11'-5"	34	
N2	#6	STR	10'-11"	16	
N3	#5	STR	9'-7"	30	
N4	#5	STR	8'-3"	26	
N5	#4	STR	6'-11"	14	
N6	#4	STR	5'-7"	11	
N7	#6	STR	11'-6"	35	
N8	#6	STR	11'-3"	17	
N9	#5	STR	10'-2"	53	
N10	#5	STR	9'-3"	39	
N11	#4	STR	8'-4"	22	
N12	#4	STR	7'-5"	20	
N13	#4	STR	6'-6"	17	
S1	#6	STR	6'-0"	54	
T1	#5	STR	14'-3"	45	
T2	#5	STR	23'-0"	72	
V1	#4	STR	9'-2"	12	
V2	#4	STR	8'-9"	6	
V3	#4	STR	7'-6"	15	
V4	#4	STR	6'-3"	13	
V5	#4	STR	4'-11"	10	
V6	#4	STR	3'-7"	7	
V7	#4	STR	9'-3"	12	
V8	#4	STR	9'-1"	6	
V9	#4	STR	8'-2"	27	
V10	#4	STR	7'-3"	19	
V11	#4	STR	6'-4"	17	
V12	#4	STR	5'-5"	14	
V13	#4	STR	4'-6"	12	
Z1	#5	STR	6'-6"	20	
Z2	#5	STR	5'-9"	18	
Z3	#4	STR	4'-11"	10	
Z4	#4	STR	4'-1"	8	
Z5	#4	STR	3'-4"	7	
Z6	#5	STR	6'-8"	21	
Z7	#5	STR	5'-11"	31	
Z8	#4	STR	5'-2"	14	
Z9	#4	STR	4'-7"	12	
Z10	#4	STR	3'-11"	10	
Z11	#4	STR	3'-4"	9	
REINFORCING STEEL FOR W1 & W3					1158 LBS
CLASS A CONCRETE					
2 WINGS					17.4 CY
1 HEADWALL					0.8 CY
1 END CURTAIN WALL					0.9 CY
TOTAL					19.1 CY

PROJECT NO. A-0009CA
GRAHAM COUNTY
 STATION: 10+59.00 -DR1A-
 SHEET 8 OF 8

6/1/2022

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

TGS ENGINEERS
 706 HILLSBOROUGH STREET
 SUITE 200
 RALEIGH, NC 27603
 PH (919) 773-8887
 CORP. LICENSE NO.: C-0275

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH					
OUTLET WINGS FOR CONCRETE BOX CULVERT					
H = 9'-0" SLOPE = 2:1					
90° SKEW					
REVISIONS					
NO.	BY:	DATE:	NO.	BY:	DATE:
1			3		
2			4		

SHEET NO. C8-8
TOTAL SHEETS 8

ASSEMBLED BY : STM DATE : 03/22
 CHECKED BY : MGC DATE : 03/22

STANDARD NOTES

DESIGN DATA:

SPECIFICATIONS	-----	A.A.S.H.T.O. (CURRENT)
LIVE LOAD	-----	SEE PLANS
IMPACT ALLOWANCE	-----	SEE A.A.S.H.T.O.
STRESS IN EXTREME FIBER OF STRUCTURAL STEEL - AASHTO M270 GRADE 36	- -	20,000 LBS. PER SQ. IN.
	- -	27,000 LBS. PER SQ. IN.
	- -	27,000 LBS. PER SQ. IN.
REINFORCING STEEL IN TENSION - GRADE 60	- - -	24,000 LBS. PER SQ. IN.
CONCRETE IN COMPRESSION	-----	1,200 LBS. PER SQ. IN.
CONCRETE IN SHEAR	-----	SEE A.A.S.H.T.O.
STRUCTURAL TIMBER - TREATED OR UNTREATED EXTREME FIBER STRESS	- - -	1,800 LBS. PER SQ. IN.
COMPRESSION PERPENDICULAR TO GRAIN OF TIMBER	- - - -	375 LBS. PER SQ. IN.
EQUIVALENT FLUID PRESSURE OF EARTH	- - - - -	30 LBS. PER CU. FT. (MINIMUM)

MATERIAL AND WORKMANSHIP:

EXCEPT AS MAY OTHERWISE BE SPECIFIED ON PLANS OR IN THE SPECIAL PROVISIONS, ALL MATERIAL AND WORKMANSHIP SHALL BE IN ACCORDANCE WITH THE 2018 "STANDARD SPECIFICATIONS FOR ROADS AND STRUCTURES" OF THE N.C. DEPARTMENT OF TRANSPORTATION.

STEEL SHEET PILING FOR PERMANENT OR TEMPORARY APPLICATIONS SHALL BE HOT ROLLED.

CONCRETE:

UNLESS OTHERWISE REQUIRED ON PLANS, CLASS A CONCRETE SHALL BE USED FOR ALL PORTIONS OF ALL STRUCTURES WITH THE EXCEPTION THAT: CLASS AA CONCRETE SHALL BE USED IN BRIDGE SUPERSTRUCTURES, ABUTMENT BACKWALLS, AND APPROACH SLABS; AND CLASS B CONCRETE SHALL BE USED FOR SLOPE PROTECTION AND RIP RAP.

CONCRETE CHAMFERS:

UNLESS OTHERWISE NOTED ON THE PLANS, ALL EXPOSED CORNERS ON STRUCTURES SHALL BE CHAMFERED 3/4" WITH THE FOLLOWING EXCEPTIONS: TOP CORNERS OF CURBS MAY BE ROUNDED TO 1/2" RADIUS WHICH IS BUILT INTO CURB FORMS; CORNERS OF TRANSVERSE FLOOR EXPANSION JOINTS SHALL BE ROUNDED WITH A 1/4" FINISHING TOOL UNLESS OTHERWISE REQUIRED ON PLANS; AND CORNERS OF EXPANSION JOINTS IN THE ROADWAY FACES AND TOPS OF CURBS AND SIDEWALKS SHALL BE ROUNDED TO A 1/4" RADIUS WITH A FINISHING STONE OR TOOL UNLESS OTHERWISE REQUIRED ON PLANS.

DOWELS:

DOWELS WHEN INDICATED ON PLANS AS FOR CULVERT EXTENSIONS, SHALL BE EMBEDDED AT LEAST 12" INTO THE OLD CONCRETE AND GROUTED INTO PLACE WITH 1:2 CEMENT MORTAR.

ALLOWANCE FOR DEAD LOAD DEFLECTION, SETTLEMENT, ETC. IN CASTING SUPERSTRUCTURES:

BRIDGES SHALL BE BUILT ON THE GRADE OR VERTICAL CURVE SHOWN ON PLANS. SLABS, CURBS AND PARAPETS SHALL CONFORM TO THE GRADE OR CURVE.

ALL DIMENSIONS WHICH ARE GIVEN IN SECTION AND ARE AFFECTED BY DEAD LOAD DEFLECTIONS ARE DIMENSIONS AT CENTER LINE OF BEARING UNLESS OTHERWISE NOTED ON PLANS. IN SETTING FORMS FOR STEEL BEAM BRIDGES AND PRESTRESSED CONCRETE GIRDER BRIDGES, ADJUSTMENTS SHALL BE MADE DUE TO THE DEAD LOAD DEFLECTIONS FOR THE ELEVATIONS SHOWN. WHERE BLOCKS ARE SHOWN OVER BEAMS FOR BUILDING UP TO THE SLAB, THE VERTICAL DIMENSIONS OF THE BLOCKS SHALL BE ADJUSTED BETWEEN BEARINGS TO COMPENSATE FOR DEAD LOAD DEFLECTIONS, VERTICAL CURVE ORDINATE, AND ACTUAL BEAM CAMBER. WHERE BOTTOM OF SLAB IS IN LINE WITH BOTTOM OF TOP FLANGES, DEPTH OF SLAB BETWEEN BEARINGS SHALL BE ADJUSTED TO COMPENSATE FOR DEAD LOAD DEFLECTION, VERTICAL CURVE ORDINATE, AND ACTUAL BEAM CAMBER.

IN SETTING FALSEWORK AND FORMS FOR REINFORCED CONCRETE SPANS, AN ALLOWANCE SHALL BE MADE FOR DEAD LOAD DEFLECTIONS, SETTLEMENT OF FALSEWORK, AND PERMANENT CAMBER WHICH SHALL BE PROVIDED FOR IN ADDITION TO THE ELEVATIONS SHOWN. AFTER REMOVAL OF THE FALSEWORK, THE FINISHED STRUCTURES SHALL CONFORM TO THE PROFILE AND ELEVATIONS SHOWN ON THE PLANS AND CONSTRUCTION ELEVATIONS FURNISHED BY THE ENGINEER.

DETAILED DRAWINGS FOR FALSEWORK OR FORMS FOR BRIDGE SUPERSTRUCTURE AND ANY STRUCTURE OR PARTS OF A STRUCTURE AS NOTED ON THE PLANS SHALL BE SUBMITTED TO THE ENGINEER FOR APPROVAL BEFORE CONSTRUCTION OF THE FALSEWORK OR FORMS IS STARTED.

REINFORCING STEEL:

ALL REINFORCING STEEL SHALL BE DEFORMED. DIMENSIONS RELATIVE TO PLACEMENT OF REINFORCING ARE TO CENTERS OF BARS UNLESS OTHERWISE INDICATED IN THE PLANS. DIMENSIONS ON BAR DETAILS ARE TO CENTERS OF BARS OR ARE OUT TO OUT AS INDICATED ON PLANS.

WIRE BAR SUPPORTS SHALL BE PROVIDED FOR REINFORCING STEEL WHERE INDICATED ON THE PLANS. WHEN BAR SUPPORT PIECES ARE PLACED IN CONTINUOUS LINES, THEY SHALL BE SO PLACED THAT THE ENDS OF THE SUPPORTING WIRES SHALL BE LAPPED TO LOCK LEGS ON ADJOINING PIECES.

STRUCTURAL STEEL:

AT THE CONTRACTOR'S OPTION, HE MAY SUBSTITUTE 7/8" Ø SHEAR STUDS FOR THE 3/4" Ø STUDS SPECIFIED ON THE PLANS. THIS SUBSTITUTION SHALL BE MADE AT THE RATE OF 3 - 7/8" Ø STUDS FOR 4 - 3/4" Ø STUDS, AND STUD SPACING CHANGES SHALL BE MADE AS NECESSARY TO PROVIDE THE SAME EQUIVALENT NUMBER OF 7/8" Ø STUDS ALONG THE BEAM AS SHOWN FOR 3/4" Ø STUDS BASED ON THE RATIO OF 3 - 7/8" Ø STUDS FOR 4 - 3/4" Ø STUDS. STUDS OF THE LENGTH SPECIFIED ON THE PLANS MUST BE PROVIDED. THE MAXIMUM SPACING SHALL BE 2'-0".

EXCEPT AT THE INTERIOR SUPPORTS OF CONTINUOUS BEAMS WHERE THE COVER PLATE IS IN CONTACT WITH BEARING PLATE, THE CONTRACTOR MAY, AT HIS OPTION, SUBSTITUTE FOR THE COVER PLATES DESIGNATED ON THE PLANS COVER PLATES OF THE EQUIVALENT AREA PROVIDED THESE PLATES ARE AT LEAST 3/16" IN THICKNESS AND DO NOT EXCEED A WIDTH EQUAL TO THE FLANGE WIDTH LESS 2" OR A THICKNESS EQUAL TO 2 TIMES THE FLANGE THICKNESS. THE SIZE OF FILLET WELDS SHALL CONFORM TO THE REQUIREMENTS OF THE CURRENT ANSI/AASHTO/AWS "BRIDGE WELDING CODE". ELECTROSLAG WELDING WILL NOT BE PERMITTED.

WITH THE SOLE EXCEPTION OF EDGES AT SURFACES WHICH BEAR ON OTHER SURFACES, ALL SHARP EDGES AND ENDS OF SHAPES AND PLATES SHALL BE SLIGHTLY ROUNDED BY SUITABLE MEANS TO A RADIUS OF APPROXIMATELY 1/16" INCH OR EQUIVALENT FLAT SURFACE AT A SUITABLE ANGLE PRIOR TO PAINTING, GALVANIZING, OR METALLIZING.

HANDRAILS AND POSTS:

METAL STANDARDS AND FACES OF THE CONCRETE END POSTS FOR THE METAL RAIL SHALL BE SET NORMAL TO THE GRADE OF THE CURB, UNLESS OTHERWISE SHOWN ON PLANS. THE METAL RAIL AND TOPS OF CONCRETE POSTS USED WITH THE ALUMINUM RAIL SHALL BE BUILT PARALLEL TO THE GRADE OF THE CURB.

METAL HANDRAILS SHALL BE IN ACCORDANCE WITH THE PLANS. RAILS SHALL BE AS MANUFACTURED FOR BRIDGE RAILING. CASTINGS SHALL BE OF A UNIFORM APPEARANCE. FINS AND OTHER DEFORMATIONS RESULTING FROM CASTING OR OTHERWISE SHALL BE REMOVED IN A MANNER SO THAT A UNIFORM COLORING OF THE COMPLETED CASTING SHALL BE OBTAINED. CASTINGS WITH DISCOLORATIONS OR OF NON-UNIFORM COLORING WILL NOT BE ACCEPTED. CERTIFIED MILL REPORTS ARE REQUIRED FOR METAL RAILS AND POSTS.

SPECIAL NOTES:

GENERALLY, IN CASE OF DISCREPANCY, THIS STANDARD SHEET OF NOTES SHALL GOVERN OVER THE SPECIFICATIONS, BUT THE REMAINDER OF THE PLANS SHALL GOVERN OVER NOTES HEREON, AND SPECIAL PROVISIONS SHALL GOVERN OVER ALL. SEE SPECIFICATIONS ARTICLE 105-4.



ENGLISH

JANUARY, 1990

STD. NO. SN