

DIVISION OF HIGHWAYS  
STATE OF NORTH CAROLINA

PROJECT REFERENCE NO. R-3830	SHEET NO. EC-3
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

**SOIL STABILIZATION SUMMARY SHEET**

**MATTING FOR EROSION CONTROL**

**MATTING FOR EROSION CONTROL**

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
5	-Y3-	17+20	18+00	RT	95
7	-L-	62+95	62+95	RT	75
8	-Y8-	10+84	11+50	LT	55
9	-L-	88+10	88+10	LT	35
11	-L-	110+50	111+00	RT	130
14	-Y15-	11+75	12+00	RT	45
16	-Y16-	11+00	11+25	LT	65
16	-L-	176+00	178+00	LT	140
16	-L-	179+50	183+00	LT	940
16	-L-	184+00	185+00	LT	185
17	-L-	185+00	187+50	LT	405
17	-L-	194+00	196+00	LT	540
17	-L-	192+50	198+00	RT	1235
18	-L-	199+50	203+00	RT	790
18	-L-	203+00	205+50	RT	205
18	-L-	199+50	204+50	LT	1125
18	-L-	206+00	211+00	LT	405
19	-L-	212+00	224+00	LT	2695
19	-L-	212+50	223+00	RT	845
19	-L-	224+00	225+50	LT	275
20	-L-	225+50	226+50	LT	185
20	-L-	228+50	236+00	RT	1370
20	-L-	236+00	239+50	RT	565
20	-L-	238+50	239+50	LT	85
21	-L-	239+50	246+00	LT	525
21	-L-	250+00	253+00	LT	485
21	-L-	242+50	244+50	RT	450
21	-L-	245+50	246+50	RT	225
21	-L-	248+00	250+00	RT	165
21	-Y18-	10+50	11+10	LT	100

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
22	-L-	253+00	254+00	LT	85
22	-L-	253+00	254+00	RT	270
				SUBTOTAL	14,795
	MISCELLANEOUS MATTING TO BE INSTALLED AS DIRECTED BY THE ENGINEER				69,565
				TOTAL	84,360
				SAY	84,360