


**EDI MODEL 2018ECL-NC CONFLICT MONITOR PROGRAMMING DETAIL**

(remove jumpers and set switches as shown)



**NOTES:**

- Card is provided with all diode jumpers in place. Removal of any jumper allows its channels to run concurrently.
- Ensure jumpers SEL2-SEL5 and SEL9 are present on the monitor board.
- Ensure that Red Enable is active at all times during normal operation.
- Connect serial cable from conflict monitor to comm. port 1 of 2070 controller. Ensure conflict monitor communicates with 2070.

**NOTES**

- To prevent "flash-conflict" problems, insert red flash program blocks for all unused vehicle load switches in the output file. The installer shall verify that signal heads flash in accordance with the Signal Plans.
- Program phases 4 and 8 for Dual Entry.
- Enable Simultaneous Gap-Out for all Phases.
- Program phases 2 and 6 for Variable Initial and Gap Reduction.
- Program phases 2 and 6 for Startup In Green.
- Program phases 2 and 6 for Yellow Flash, and overlaps 1 and 2 as Wag Overlaps.
- If this signal will be managed by an ATMS software, enable controller and detector logging for all detectors used at this location.

**EQUIPMENT INFORMATION**

CONTROLLER.....2070  
 CABINET.....332 W/ AUX  
 SOFTWARE.....ECONOLITE OASIS  
 CABINET MOUNT.....BASE  
 OUTPUT FILE POSITIONS...18 WITH AUX. OUTPUT FILE  
 LOAD SWITCHES USED.....S1,S2,S5,S8,S11,AUXS1,AUXS2,AUXS4  
 PHASES USED.....1,2,4,6,8  
 OVERLAP "A".....1+2  
 OVERLAP "B".....4  
 OVERLAP "C".....6  
 OVERLAP "D".....NOT USED


**SIGNAL HEAD HOOK-UP CHART**

LOAD SWITCH NO.	S1	S2	S3	S4	S5	S6	S7	S8	S9	S10	S11	S12	AUX S1	AUX S2	AUX S3	AUX S4	AUX S5	AUX S6
CMU CHANNEL NO.	1	2	13	3	4	14	5	6	15	7	8	16	9	10	17	11	12	18
PHASE	1	2	2 PED	3	4	4 PED	5	6	6 PED	7	8	8 PED	OLA	OLB	SPARE	OLC	OLD	SPARE
SIGNAL HEAD NO.	11	22,23	NU	NU	41,42	NU	NU	61,62	NU	NU	82,83,84	NU	11	81	NU	21	NU	NU
RED		128			101			134			107							
YELLOW	*	129			102			135			108							
GREEN		130			103			136			109							
RED ARROW													A121	A124		A114		
YELLOW ARROW													A122	A125		A115		
FLASHING YELLOW ARROW													A123	A126		A116		
GREEN ARROW	127																	

NU = Not Used  
 \* Denotes install load resistor. See load resistor installation detail this sheet.  
 ★ See pictorial of head wiring in detail this sheet.

**FYA SIGNAL WIRING DETAIL**

(wire signal heads as shown)



**NOTE**

The sequence display for signal head 11 requires special logic programming. See sheet 2 for programming instructions.

**INPUT FILE POSITION LAYOUT**

(front view)

FILE	U	1	2	3	4	5	6	7	8	9	10	11	12	13	14	
"I"	U	∅ 1	-ORS	-ORS	-ORS	-ORS	-ORS	-ORS	-ORS	-ORS	-ORS	-ORS	-ORS	-ORS	-ORS	FS
	L	1A	-ORS	-ORS	-ORS	-ORS	-ORS	-ORS	-ORS	-ORS	-ORS	-ORS	-ORS	-ORS	-ORS	DC ISOLATOR
"J"	U	NOT USED	-ORS	-ORS	-ORS	-ORS	-ORS	-ORS	-ORS	-ORS	-ORS	-ORS	-ORS	-ORS	-ORS	ST
	L	-ORS	-ORS	-ORS	-ORS	-ORS	-ORS	-ORS	-ORS	-ORS	-ORS	-ORS	-ORS	-ORS	-ORS	DC ISOLATOR


EX.: 1A, 2A, ETC. = LOOP NO.'S  
 FS = FLASH SENSE  
 ST = STOP TIME  
 ⊗ Wired Input - Do not populate slot with detector card

**INPUT FILE CONNECTION & PROGRAMMING CHART**

LOOP NO.	LOOP TERMINAL	INPUT FILE POS.	PIN NO.	INPUT ASSIGNMENT NO.	DETECTOR NO.	NEMA PHASE	CALL	EXTEND	FULL TIME DELAY	STRETCH TIME	DELAY TIME
1A <sup>1</sup>	TB2-1,2	I1U	56	18	1	1	Y	Y			15
	-	J4U	48	10★	26	6	Y	Y	Y		3
	-	I1U	56	18★	51	1	Y	Y			3

<sup>1</sup>Add jumper from I1-W to J4-W, on rear of input file.  
 ★ See Input Page Assignment programming details on sheet 3.

**INPUT FILE POSITION LEGEND: J2L**




**DETECTOR NOTES**

- For all loops install a video detection system for vehicle detection. Perform installation according to manufacturer's directions and NCDOT engineer-approved mounting locations to accomplish the detection schemes shown on the Signal Design Plans.
- For loop 1A, detector card placement and slot reserved for wired input are typical for a NCDOT installation. Input associated with this slot are compatible with time of day instructions located on sheet 3 of this electrical detail.

**LOAD RESISTOR INSTALLATION DETAIL**

(install resistor as shown below)



THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 08-0649T3  
 DESIGNED: JANUARY 2022  
 SEALED: 4/20/2022  
 REVISED: N/A

Temporary Design 3 - (TMP Phase II)  
 Electrical Detail - Sheet 1 of 4

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

Electrical and Programming Details for:  
 NC 42 (Broadway Road) at SR 1529 (Cox Mill Road) and Bill's Body Shop  
 Division 8 Lee County Sanford  
 PLAN DATE: April 2022 REVIEWED BY: Todd Joyce  
 PREPARED BY: Keith M. Mims REVIEWED BY: -  
 REVISIONS: INIT. DATE  
 750 N. Greenfield Pkwy, Corner, NC 27529

SEAL  
 NORTH CAROLINA PROFESSIONAL ENGINEER  
 KEITH M. MIMS  
 036880  
 Keith M. Mims 04/21/2022  
 SIG. INVENTORY NO. 08-0649T3

21-APR-2022 14:10  
 S:\TAS\UMTS - Signal\Workgroups\519 Man\Projects From Signal Design\Act1ive Projects\Wm\m-n-house\08-0649T3\080649-sm-le-13-xxxxx.dgn  
 km/mms