



NOTES

1: CONTRACTOR TO RECORD EXISTING SPLICE ARRANGEMENT FOR COMPARISON TO THE SUPPLIED SPLICE DETAILS. IF DISCREPANCIES EXIST, CONTACT THE ENGINEER TO DETERMINE HOW TO PROCEED WITH RESPLICING. PROVIDE AS-BUILT PLANS TO THE ENGINEER IF FINAL SPLICE ARRANGEMENT DIFFERS FROM THE SUPPLIED SPLICE DETAILS.

2: CONTRACTOR BACK PULL EXISTING FIBER TO EXISTING CABLE STORAGE RACKS. REMOVE ENOUGH STORED FIBER FROM EACH RACK TO REACH THE NEW CABINET LOCATION AND PROVIDE A MINIMUM 20' STORAGE OF EACH CABLE IN THE SIGNAL CABINET. ADJUST EXISTING RACK SPACING ACCORDINGLY. RELASH EXISTING FIBER TO EXISTING AND NEW MESSENGER CABLE TO REACH THE NEW CABINET LOCATION.

10/2/2019
SCP_3 - Temporary.dgn
11:48:27 AM

**DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED**

5410 Trinity Road
Suite 102
Raleigh, NC 27607
Tel: 919.866.4951
Fax: 919.859.5663
License: C-1652

Prepared for the Offices of:

750 N. Greenfield Pkwy., Garner, NC 27529

TEMPORARY COMMUNICATIONS CABLE AND CONDUIT ROUTING PLAN	
Division 6	Lee County SANFORD
PLAN DATE: August 2019	REVIEWED BY: J Hochanadel
PREPARED BY: C Lawson	REVIEWED BY:
REVISIONS	INIT. DATE

SEAL

Designed by: Jeffrey P. Hochanadel
DATE: 10/2/2019
SIG. INVENTORY NO.