

PROJECT NO.: B-4442
 COMPUTED BY: MF
 CHECKED BY: AM

SHEET 1 OF 1

SECTION: 620

ASPHALT BINDER FOR PLANT MIX

GRADE PG 64-22

SA-1		TONS	X	0.068	=		TONS
S4.75A		TONS	X	0.070	=		TONS
S9.5B		TONS	X	0.067	=		TONS
S9.5C	7,800	TONS	X	0.060	=	468.00	TONS
I19.0C	8,920	TONS	X	0.048	=	428.16	TONS
B25.0C	9,300	TONS	X	0.045	=	418.50	TONS
PADC, TYPE P-57		TONS	X	0.025	=		TONS
PADC, TYPE P-78M		TONS	X	0.030	=		TONS

SUBTOTAL TONS ASPHALT BINDER
 FOR PLANT MIX, GRADE PG 64-22 = 1,314.66 TONS

TOTAL TONS ASPHALT BINDER
 FOR PLANT MIX = 1,314.66 TONS
 SAY 1,315 TONS