

PROJECT NO. : B-4442

COMPUTED BY: MF

CHECKED BY: AM

SHEET 1 OF 1

SECTION: 300

FOUNDATION CONDITIONING MATERIAL MINOR STRUCTURES

$$\begin{array}{rcccccc} \underline{2,444} & \text{LIN. FT} & \times & 0.106 & = & \underline{259.06 \text{ TONS}} \\ & & & & \text{SAY} & \underline{260 \text{ TONS}} \end{array}$$

FOUNDATION CONDITIONING GEOTEXTILE

$$\begin{array}{rcccccc} \underline{2444} & \text{LIN. FT} & \times & 6 \text{ FT / 18} & = & \underline{814.67 \text{ SY}} \\ & & & & \text{SAY} & \underline{820 \text{ SY}} \end{array}$$