

PROJECT NO.: B-4442

SHEET 1 OF 1

COMPUTED BY: MF

CHECKED BY: AM

SECTION: 250

REMOVAL OF EXISTING ASPHALT PAVEMENT

(FILL IN THE BLANK FOR 'ASPHALT' OR 'CONCRETE' PAVEMENT)

LINE	STATION	STATION	LOCATION	LENGTH OR AREA	WIDTH	SQUARE YARDS
L	303+00	306+50	LT	13348.00		1483.11
L	303+00	306+50	RT	13453.00		1494.78
L	327+00	327+50	LT	1903.00		211.44
L	327+00	327+50	RT	1913.00		212.56
L	297+05	308+95	LT/RT	22500.00		2500.00
L	321+52	333+05	LT/RT	21425.00		2380.56
					TOTAL	8,282.44
					SAY	8,290