SUMMARY OF PILE INFORMATION/INSTALLATION

(Blank entries indicate item is not applicable to structure)

End Bent/		Pile Cut-Off (Top of Pile) Elevation FT	Estimated Pile Lenth per Pile FT	Scour Critical Elevation FT	Driven Piles			Predrilling for Piles*			Drilled-In Piles		
Bent No, Pile(s) ## (e.g., "Bent 1, Piles 1-5")	Factored Resistance per Pile TONS				Min Pile Tip (Tip No Higher Than) Elev FT	Required Driving Resistance (RDR)** per Pile TONS	Total Pile Redrives Quantity EACH	Predrilling Length per Pile Lin FT	Predrilling Elevation (Elev Not To Predrill Below) FT	Maximum Predrilling Dia INCHES	Pile Excavation (Bottom of Hole) Elev FT	Pile Exc Not In Soil per Pile Lin FT	Pile Exc In Soil per Pile Lin FT
End Bent 1, Piles 1-9	144	See Structure Plans	25			240							
End Bent 1, Piles 10-18	144	See Structure Plans	50			240							
End Bent 1, Piles 19-28	144	See Structure Plans	50			240							
End Bent 2, Piles 1-9	135	See Structure Plans	50			225							
End Bent 2, Piles 10-18	135	See Structure Plans	50			225							
End Bent 2, Piles 19-28		See Structure Plans	45			225							

*Predrilling for Piles is required for end bents/bents with a predrilling length and at the Contractor's option for end bents/bents with predrilling information but no predrilling length.

ng for Piles is required for end beinstreams with a production of the factored Dead Load - Factored Resistance + Factored Downdrag Load + Factored Dead Load - Nominal Downdrag Resistance + Nominal Scour Resistance Factor Nominal Scour Resistance

PILE DESIGN INFORMATION

(Blank entries indicate item is not applicable to structure)

End Bent/ Bent No, Pile(s) #-# (e.g., "Bent 1, Piles 1-5")	Factored Axial Load per Pile TONS	Factored Downdrag Load per Pile TONS	Factored Dead Load* per Pile TONS	Dynamic Resistance Factor	Nominal Downdrag Resistance per Pile TONS	Nominal Scour Resistance per Pile TONS	Scour Resistance Factor (Default = 1.00)
End Bent 1, Piles 1-9	143						1.00
End Bent 1, Piles 10-18	143						1.00
End Bent 1, Piles 19-28	143						1.00
End Bent 2, Piles 1-9	135						1.00
End Bent 2, Piles 10-18	135						1.00
End Bent 2, Piles 19-28	135						1.00

*Factored Dead Load is factored weight of pile above the ground line.

SUMMARY OF DRILLED PIER INFORMATION/INSTALLATION

(Blank entries indicate item is not applicable to structure)

End Bent/ Bent No, Pier(s) #- (e.g., "Bent 1, Piers 1-3")	Factored Resistance per Pier TONS	Minimum Pier Tip (Tip No Higher Than) Elevation FT	Required Tip Resistance per Pier TSF	Scour Critical Elevation FT	Minimum Drilled Pier Penetration Into Rock per Pier Lin FT	Drilled Pier Length per Pier Lin FT	Drilled Pier Length Not In Soil per Pier Lin FT	Drilled Pier Length In Soil per Pier Lin FT	Permanent Steel Casing Required? YES or MAYBE	Permanent Steel Casing Tip Elevation (Elev Not To Extend Casing Below) FT	Permanent Steel Casing Length* per Pier Lin FT
Bent 1, Piers 1-3	742	1958.0	100	1968	12.0	25.0			Yes	1970.0	15.0
Bent 1, Piers 4-6	742	1958.0	100	1968	12.0	24.5			Yes	1970.0	15.0
Bent 1, Piers 7-9	742	1958.0	100	1968	12.0	24.0			Yes	1970.0	15.0

*Permanent Steel Casing Length equals the difference between the ground line or top of drilled pier elevation, whichever is higher, and the permanent casing tip elevation.

FOUNDATION NOTES

- 1. FOR PILES, SEE PILES PROVISION AND SECTION 450 OF THE STANDARD SPECIFICATIONS.
- 2. FOR DRILLED PIERS, SEE SECTION 411 OF THE STANDARD SPECIFICATIONS.

- 1. The Pile and Drilled Pier Foundation Tables are based on the bridge substructure design and foundation recommendations sealed by a North Carolina Professional Engineer Shiping Yang, PE, seal # 031361) on 05-03-2022
- 2. Total Pile Driving Equipment Setup quantity (not shown in Pile Foundation Tables) equals the number of driven piles, i.e., the number of piles with a Required Driving Resistance.
- 3. The Engineer will determine the need for PDA Testing, Pipe Pile Plates, Permanent Steel Casing, SPTs, CSL Testing, SID Inspections and PITs when these items may be required.

SUMMARY OF DRILLED PIER TESTING

(Blank entries indicate item is not applicable to structure)

End Bent/ Bent No, Pier(s) #-# (e.g., "Bent 1, Piers 1-3")	Standard Penetration Test (SPT) Required? YES or MAYBE	Crosshole Sonic Logging (CSL) Required?* YES or MAYBE	Total CSL Tube Length (For All Tubes) per Pier Lin FT	Shaft Inspection Device (SID) Required? YES or MAYBE	Pile Integrity Test (PIT) Required? MAYBE	
Bent 1, Piers 1-3		MAYBE	133			
Bent 1, Piers 4-6		MAYBE	130			
Bent 1, Piers 7-9		MAYBE	128			
	, and the second					
TOTAL QTY:			1170			

*CSL Tubes are required if CSL Testing is or may be required. The number of CSL Tubes per drilled pier is equal to one tube per foot of design pier diameter with at least 4 tubes per pier. The length of each CSL Tube is equal to the drilled pier length plus 1.5 ft.

PROJECT NO.	B-4442	
<u>_</u>	Buncombe	COUNTY
STATION:	315+72.39 -L-	



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

PILE AND DRILLED PIER **FOUNDATION TABLES**

SIGNATURE	DATE			SHEET NO.				
DOCUMENT NOT CONSIDERED			BY:	DATE:	NO.	BY:	DATE:	TOTAL
FINAL UNL	1			3			SHEETS	
SIGNATURES COMPLETED					4			