



6/2/2022

PAVEMENT SCHEDULE




C1	PROP. APPROX. 1 1/2" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5C, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD.
C2	PROP. APPROX. 3" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5C, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD. IN EACH OF TWO LAYERS.
C3	PROP. VAR. DEPTH ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5C, AT AN AVERAGE RATE OF 112 LBS PER SQ. YD. PER 1" DEPTH. TO BE PLACED IN LAYERS NOT TO EXCEED 1 1/2" IN DEPTH.
D2	PROP. APPROX. 2 1/2" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0C, AT AN AVERAGE RATE OF 285 LBS. PER SQ. YD.
D3	PROP. VAR. DEPTH ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0C, AT AN AVERAGE RATE OF 114 LBS. PER SQ. YD. PER 1" DEPTH. TO BE PLACED IN LAYERS NOT LESS THAN 2 1/2" OR GREATER THAN 4" IN DEPTH.
E1	PROP. APPROX. 4" ASPHALT CONCRETE BASE COURSE, TYPE B25.0C, AT AN AVERAGE RATE OF 456 LBS. PER SQ. YD.
E2	PROP. VAR. DEPTH ASPHALT CONCRETE BASE COURSE, TYPE B25.0C, AT AN AVERAGE RATE OF 114 LBS. PER SQ. YD. PER 1" DEPTH. TO BE PLACED IN LAYERS NOT LESS THAN 3" OR GREATER THAN 5 1/2" IN DEPTH.
K	CLASS IV SUBGRADE STABILIZATION
J1	PROP. 4" AGGREGATE BASE COURSE.
N	GEOTEXTILE FOR PAVEMENT STABILIZATION
R2	EXPRESSWAY GUTTER
R4	SHOULDER BERM GUTTER
T	EARTH MATERIAL.
U	EXISTING PAVEMENT.
W	WEDGING EXISTING PAVEMENT, SEE THIS SHEET FOR DETAILS
Y1	5 1/2" CONCRETE OVERLAY

PAVEMENT EDGE SLOPES ARE 1:1 UNLESS SHOWN OTHERWISE.



NOTE:
ANYWHERE ALONG THE PROJECT IN WHICH LESS THAN 3" OF OVERLAY HAS BEEN CALLED FOR THE CONTRACTOR SHALL MILL EXISTING PAVEMENT AND PROVIDE A MINIMUM OF TWO FULL LAYERS OF S9.5C TO SATISFY RIDEABILITY REQUIREMENTS PER CONTRACT FOR -L-.

PROJECT REFERENCE NO. A-0009CB	SHEET NO. 2A-1
ROADWAY DESIGN ENGINEER JIMMY L. TERRY 35018	PAVEMENT DESIGN ENGINEER MATTHEW BROWER 041986
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	
TGS ENGINEERS 201 W. MARION ST SHELBY, NC 28150 PH (704) 476-0003 CORP. LICENSE NO.: C-0275	



7/7/2022
 X:\Projects\A-0009CB\Roadway\Proj\A-0009CB_Plan_Sheets\A-0009CB_Rdy_tjy.dgn
 User: jlm