

PROJECT: 32572.1.FS10 REFERENCE: A-0009CB

CONTENTS

| SHEET NO. | DESCRIPTION |
|-----------|--------------------------|
| 1 | TITLE SHEET |
| 2 | LEGEND (SOIL & ROCK) |
| 3 | SITE PLAN |
| 4 | WALL ENVELOPE |
| 5-8 | CROSS SECTIONS |
| 9-10 | BORE LOGS |
| 11-12 | GEOPHYSICAL TEST RESULTS |

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 GEOTECHNICAL ENGINEERING UNIT

STRUCTURE
SUBSURFACE INVESTIGATION

COUNTY GRAHAM
 PROJECT DESCRIPTION UPGRADE NC 143 FROM SR 1223 (BEECH CREEK ROAD) TO 0.5 MILES NORTH OF APPALACHIAN TRAIL
 SITE DESCRIPTION RETAINING WALL #29: SHORED MECHANICALLY STABILIZED EARTH (SMSE) WALL ON -L- FROM 393+90 RT TO 395+90 RT

| STATE | STATE PROJECT REFERENCE NO. | SHEET NO. | TOTAL SHEETS |
|-------|-----------------------------|-----------|--------------|
| N.C. | A-0009CB | 1 | 12 |

CAUTION NOTICE

THE SUBSURFACE INFORMATION AND THE SUBSURFACE INVESTIGATION ON WHICH IT IS BASED WERE MADE FOR THE PURPOSE OF STUDY, PLANNING AND DESIGN, AND NOT FOR CONSTRUCTION OR PAY PURPOSES. THE VARIOUS FIELD BORING LOGS, ROCK CORES AND SOIL TEST DATA AVAILABLE MAY BE REVIEWED OR INSPECTED IN RALEIGH BY CONTACTING THE N. C. DEPARTMENT OF TRANSPORTATION, GEOTECHNICAL ENGINEERING UNIT AT (919) 707-6850. THE SUBSURFACE PLANS AND REPORTS, FIELD BORING LOGS, ROCK CORES AND SOIL TEST DATA ARE NOT PART OF THE CONTRACT.

GENERAL SOIL AND ROCK STRATA DESCRIPTIONS AND INDICATED BOUNDARIES ARE BASED ON A GEOTECHNICAL INTERPRETATION OF ALL AVAILABLE SUBSURFACE DATA AND MAY NOT NECESSARILY REFLECT THE ACTUAL SUBSURFACE CONDITIONS BETWEEN BORINGS OR BETWEEN SAMPLED STRATA WITHIN THE BOREHOLE. THE LABORATORY SAMPLE DATA AND THE IN SITU (IN-PLACE) TEST DATA CAN BE RELIED ON ONLY TO THE DEGREE OF RELIABILITY INHERENT IN THE STANDARD TEST METHOD. THE OBSERVED WATER LEVELS OR SOIL MOISTURE CONDITIONS INDICATED IN THE SUBSURFACE INVESTIGATIONS ARE AS RECORDED AT THE TIME OF THE INVESTIGATION. THESE WATER LEVELS OR SOIL MOISTURE CONDITIONS MAY VARY CONSIDERABLY WITH TIME ACCORDING TO CLIMATIC CONDITIONS INCLUDING TEMPERATURES, PRECIPITATION AND WIND, AS WELL AS OTHER NON-CLIMATIC FACTORS.

THE BIDDER OR CONTRACTOR IS CAUTIONED THAT DETAILS SHOWN ON THE SUBSURFACE PLANS ARE PRELIMINARY ONLY AND IN MANY CASES THE FINAL DESIGN DETAILS ARE DIFFERENT. FOR BIDDING AND CONSTRUCTION PURPOSES, REFER TO THE CONSTRUCTION PLANS AND DOCUMENTS FOR FINAL DESIGN INFORMATION ON THIS PROJECT. THE DEPARTMENT DOES NOT WARRANT OR GUARANTEE THE SUFFICIENCY OR ACCURACY OF THE INVESTIGATION MADE, NOR THE INTERPRETATIONS MADE, OR OPINION OF THE DEPARTMENT AS TO THE TYPE OF MATERIALS AND CONDITIONS TO BE ENCOUNTERED. THE BIDDER OR CONTRACTOR IS CAUTIONED TO MAKE SUCH INDEPENDENT SUBSURFACE INVESTIGATIONS AS HE DEEMS NECESSARY TO SATISFY HIMSELF AS TO CONDITIONS TO BE ENCOUNTERED ON THE PROJECT. THE CONTRACTOR SHALL HAVE NO CLAIM FOR ADDITIONAL COMPENSATION OR FOR AN EXTENSION OF TIME FOR ANY REASON RESULTING FROM THE ACTUAL CONDITIONS ENCOUNTERED AT THE SITE DIFFERING FROM THOSE INDICATED IN THE SUBSURFACE INFORMATION.

- NOTES:
- THE INFORMATION CONTAINED HEREIN IS NOT IMPLIED OR GUARANTEED BY THE N. C. DEPARTMENT OF TRANSPORTATION AS ACCURATE NOR IS IT CONSIDERED PART OF THE PLANS, SPECIFICATIONS OR CONTRACT FOR THE PROJECT.
 - BY HAVING REQUESTED THIS INFORMATION, THE CONTRACTOR SPECIFICALLY WAIVES ANY CLAIMS FOR INCREASED COMPENSATION OR EXTENSION OF TIME BASED ON DIFFERENCES BETWEEN THE CONDITIONS INDICATED HEREIN AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.

PERSONNEL

CG2 EXPLORATION

BRECCIA

C. PIERCY

D. GOODNIGHT

M. BREWER

S. BRAUN

GEL SOLUTIONS

INVESTIGATED BY CG2

DRAWN BY M. BREWER, P.E.

CHECKED BY R. KRAL, P.E.

SUBMITTED BY M. BREWER, P.E.

DATE MAY 2022

Prepared in the Office of:
 **CAROLINAS GEOTECHNICAL GROUP**
 2400 CROWNPOINT EXECUTIVE DRIVE
 SUITE 800
 CHARLOTTE, NC 28227
 (980) 339-8684




DocuSigned by:
D. Matthew Brewer 6/7/2022
 386129C0A4C1462
 SIGNATURE DATE

**DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED**


NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT
SUBSURFACE INVESTIGATION
SOIL AND ROCK LEGEND, TERMS, SYMBOLS, AND ABBREVIATIONS

Table with 4 main columns: SOIL DESCRIPTION, GRADATION, ROCK DESCRIPTION, and TERMS AND DEFINITIONS. Includes sub-sections like SOIL LEGEND AND AASHTO CLASSIFICATION, CONSISTENCY OR DENSENESS, TEXTURE OR GRAIN SIZE, SOIL MOISTURE - CORRELATION OF TERMS, PLASTICITY, COLOR, MISCELLANEOUS SYMBOLS, RECOMMENDATION SYMBOLS, ABBREVIATIONS, EQUIPMENT USED ON SUBJECT PROJECT, FRACTURE SPACING, BEDDING, INDURATION, and ELEVATION.



PROP. RETAINING WALL #29
W/9' WW WILDLIFE FENCE
BEGIN -L- STA. 393+90±
END -L- STA. 395+90±

-L- PT 395+12.74



APPALACHIAN TRAIL

LINE RWAL19.7

LINE RWAL19.8

NC 143 (SWEETWATER RD.)
24' BST

RWAL 29 B-1

RWAL 29 B-2

RWAL 29 B-3

ROCK OUTCROP 23

PROP. RETAINING WALL #29
W/9' WW WILDLIFE FENCE
BEGIN -L- STA. 393+90±
END -L- STA. 395+90±




NOTE:
SOIL, WEATHERED ROCK, AND CRYSTALLINE ROCK
LINE ARE BASED ON AN INTERPRETATION OF
BORE HOLE AND SEISMIC REFRACTION DATA AND
SHALL BE CONSIDERED AS APPROXIMATE.


Prepared in the Office of:



CAROLINAS
 GEOTECHNICAL
 GROUP




| | |
|---|------------------|
| PROJECT REFERENCE NO. | SHEET NO. |
| A-0009CB | 4 |
| RETAINING WALL #29 PROFILE BORINGS PROJECTED ALONG WALL ENVELOPE | |



- (A) -ROADWAY EMBANKMENT- MEDIUM STIFF TO HARD, MOIST TO WET, BROWN-TAN-ORANGE-GRAY, FINE TO COARSE SANDY SILT (A-4), WITH TRACE TO LITTLE GRAVEL
- (B) -ROADWAY EMBANKMENT- LOOSE TO VERY DENSE, MOIST, GRAY-BROWN, SILTY, GRAVELLY FINE TO COARSE SAND (A-I-B) AND SILTY, FINE TO COARSE SAND (A-2-4), WITH TRACE GRAVEL
- (C) -COLLUVIAL- SOFT TO STIFF, MOIST, BROWN-TAN-GRAY, FINE TO COARSE SANDY SILT (A-4(1)), WITH TRACE GRAVEL
- (D) -RESIDUAL- VERY STIFF, MOIST, WET, FINE TO COARSE SANDY SILT (A-4), WITH TRACE GRAVEL-SIZED ROCK FRAGMENTS
- (E) -RESIDUAL- DENSE, MOIST, GRAY-ORANGE, SILTY, GRAVELLY FINE TO COARSE SAND (A-I-B)
- (F) -RESIDUAL- LOOSE TO DENSE, MOIST, GRAY, SILTY FINE TO COARSE SAND (A-2-4), WITH TRACE GRAVEL-SIZED ROCK FRAGMENTS
- (G) -WEATHERED ROCK- (META-SANDSTONE)

6/23/16
I:\MAY-2022\1742\GIS\Projects\0068 - A-0009CB - Future US 74_TGS\A-0009CB\CADD\GEO\TECH\Site\Sub\A-0009CB.GEO_RWAL29_XS1.dgn
C:\Users\jbriver\OneDrive - Carolines Geotechnical Group, PLLC\Projects\0068 - A-0009CB - Future US 74_TGS\A-0009CB\CADD\GEO\TECH\Site\Sub\A-0009CB.GEO_RWAL29_XS1.dgn


NOTE:
SOIL, WEATHERED ROCK, AND CRYSTALLINE ROCK
LINES ARE BASED ON AN INTERPRETATION OF
BORE HOLE AND SEISMIC REFRACTION DATA AND
SHALL BE CONSIDERED AS APPROXIMATE.



-L- EXISTING GROUND LINE TAKEN FROM ROADWAY DESIGN PLANS PROVIDED BY
TGS ENGINEERS ON 11/5/21. INFERRED STRATIGRAPHY IS DRAWN THROUGH THE BORING
OR SEISMIC REFRACTION LINE WITH BOTH PROJECTED ONTO THE CROSS SECTION

-L-

19-MAY-2022 17:42
 C:\Users\jbriver\OneDrive - Carolines Geotechnical Group, PLLC\Projects\0068 - A-0009CB - Future US 74_TGS\A-0009CB\CADD_GEO\TECH\Site\Sub\A-0009CB.GEO_RWAL29_XS1.dgn
 \$\$\$SUBSERIAL\$\$\$



- (A) - COLLUVIAL - VERY STIFF, MOIST, TAN, FINE SANDY SILT (A-4), WITH LITTLE GRAVEL
- (B) - COLLUVIAL - LOOSE TO MEDIUM DENSE, MOIST, SILTY FINE SAND (A-2-4), WITH LITTLE GRAVEL
- (C) - RESIDUAL - VERY STIFF, MOIST, GRAY, FINE TO COARSE SANDY SILT (A-4), WITH TRACE GRAVEL-SIZED ROCK FRAGMENTS
- (D) - RESIDUAL - DENSE, MOIST, GRAY-ORANGE, SILTY, GRAVELLY FINE TO COARSE SAND (A-I-B)


-L- EXISTING GROUND LINE TAKEN FROM ROADWAY DESIGN PLANS PROVIDED BY
 TGS ENGINEERS ON 11/15/21. INFERRED STRATIGRAPHY IS DRAWN THROUGH THE BORING
 OR SEISMIC REFRACTION LINE WITH BOTH PROJECTED ONTO THE CROSS SECTION

19-MAY-2022 17:42
 C:\Users\jbriver\OneDrive - Carolines Geotechnical Group, PLLC\Projects\0068 - A-0009CB - Future US 74_TGS\A-0009CB\CADD_GEO\TECH\Site\A-0009CB_GEO_RWAL29_XSI.dgn
 \$\$\$SUSERRNAME\$\$\$

NOTE:
 SOIL, WEATHERED ROCK, AND CRYSTALLINE ROCK
 LINES ARE BASED ON AN INTERPRETATION OF
 BORE HOLE AND SEISMIC REFRACTION DATA AND
 SHALL BE CONSIDERED AS APPROXIMATE.

SOIL TEST RESULTS


| SAMPLE NO. | OFFSET | STATION | DEPTH INTERVAL | AASHTO CLASS. | L.L. | P.I. | % BY WEIGHT | | | | % PASSING (SIEVES) | | | % MOISTURE | % ORGANIC |
|------------|--------|------------|----------------|---------------|------|------|-------------|---------|------|------|--------------------|----|-----|------------|-----------|
| | | | | | | | C. SAND | F. SAND | SILT | CLAY | 10 | 40 | 200 | | |
| SS-853 | 28' RT | 395+00 -L- | 23.5' - 25.0' | A-4(1) | 27 | 5 | 18 | 22 | 33 | 27 | 95 | 84 | 63 | 22 | - |




Ⓐ -ROADWAY EMBANKMENT- STIFF TO VERY STIFF, MOIST TO WET, BROWN-GRAY, FINE TO COARSE SANDY SILT (A-4), WITH TRACE GRAVEL

Ⓑ -RESIDUAL- VERY STIFF, MOIST, GRAY, FINE TO COARSE SANDY SILT (A-4), WITH TRACE GRAVEL-SIZED ROCK FRAGMENTS

-L- EXISTING GROUND LINE TAKEN FROM ROADWAY DESIGN PLANS PROVIDED BY TGS ENGINEERS ON 11/5/21. INFERRED STRATIGRAPHY IS DRAWN THROUGH THE BORING OR SEISMIC REFRACTION LINE WITH BOTH PROJECTED ONTO THE CROSS SECTION



19-MAY-2022 17:42
 C:\Users\jbriver\OneDrive - Carolines Geotechnical Group, PLLC\Projects\0068 - A-0009CB - Future US 74_TGS\A-0009CB\CADD_GEO\TECH\Site\Sub\A-0009CB.GEO_RWAL29_XS1.dgn
 \$\$\$SUBSERIALNAME\$\$\$



GEOTECHNICAL BORING REPORT


BORE LOG

| WBS 32572.1.FS10 | | TIP A-0009CB | | COUNTY GRAHAM | | GEOLOGIST S. Braun | | | | | | | | | | |
|---|-----------------|---------------------|--------------------------|---------------------|-------|-------------------------|-----------------|----|----|-----|-----------|-----|---------------------------|------------|---------|------|
| SITE DESCRIPTION Upgrade NC 143 from SR 1223 (Beech Creek Road) to 0.5 Miles North of Appalachian Trail | | | | | | | GROUND WTR (ft) | | | | | | | | | |
| BORING NO. RWAL29_B-2 | | STATION 395+00 | | OFFSET 28 ft RT | | ALIGNMENT L | | | | | | | | | | |
| COLLAR ELEV. 3,077.4 ft | | TOTAL DEPTH 29.2 ft | | NORTHING 619,615 | | EASTING 594,443 | | | | | | | | | | |
| DRILL RIG/HAMMER EFF./DATE CG20446 Diedrich D50 83%/06/16/2020 | | | DRILL METHOD H.S. Augers | | | HAMMER TYPE Automatic | | | | | | | | | | |
| DRILLER J. Estep | | START DATE 05/06/21 | | COMP. DATE 05/06/21 | | SURFACE WATER DEPTH N/A | | | | | | | | | | |
| ELEV (ft) | DRIVE ELEV (ft) | DEPTH (ft) | BLOW COUNT | | | BLOWS PER FOOT | | | | | SAMP. NO. | LOG | SOIL AND ROCK DESCRIPTION | DEPTH (ft) | | |
| | | | 0.5ft | 0.5ft | 0.5ft | 0 | 25 | 50 | 75 | 100 | | | | | | |
| 3080 | | | | | | | | | | | | | | | | |
| | 3,076.4 | 1.0 | 9 | 8 | 9 | | | | | | | | | | 3,077.4 | 0.0 |
| 3075 | 3,073.9 | 3.5 | 10 | 8 | 8 | | | | | | | | | | | |
| | 3,071.4 | 6.0 | 9 | 6 | 7 | | | | | | | | | | | |
| 3070 | 3,068.9 | 8.5 | 5 | 7 | 5 | | | | | | | | | | | |
| | 3,063.9 | 13.5 | 7 | 3 | 4 | | | | | | | | | | 3,065.4 | 12.0 |
| 3065 | 3,058.9 | 18.5 | 9 | 5 | 5 | | | | | | | | | | | |
| 3060 | 3,053.9 | 23.5 | 1 | 2 | 1 | | | | | | | | | | | |
| | 3,049.4 | 28.0 | | | | | | | | | | | | | 3,049.4 | 28.0 |
| 3055 | 3,048.2 | 29.2 | 100/0.3 | | | | | | | | | | | | 3,048.2 | 29.2 |
| | | | 60/0.0 | | | | | | | | | | | | | |
| 3050 | | | | | | | | | | | | | | | | |

| WBS 32572.1.FS10 | | TIP A-0009CB | | COUNTY GRAHAM | | GEOLOGIST C. Piercy | | | | | | | | | | |
|---|-----------------|---------------------|--------------------------|---------------------|-------|-------------------------|-----------------|----|----|-----|-----------|-----|---------------------------|------------|---------|-----|
| SITE DESCRIPTION Upgrade NC 143 from SR 1223 (Beech Creek Road) to 0.5 Miles North of Appalachian Trail | | | | | | | GROUND WTR (ft) | | | | | | | | | |
| BORING NO. RWAL29_B-3 | | STATION 395+80 | | OFFSET 28 ft RT | | ALIGNMENT L | | | | | | | | | | |
| COLLAR ELEV. 3,072.1 ft | | TOTAL DEPTH 23.0 ft | | NORTHING 619,669 | | EASTING 594,501 | | | | | | | | | | |
| DRILL RIG/HAMMER EFF./DATE BRE9533 OME-550X 78%/03/12/2021 | | | DRILL METHOD H.S. Augers | | | HAMMER TYPE Automatic | | | | | | | | | | |
| DRILLER J. Phillips | | START DATE 05/06/21 | | COMP. DATE 05/06/21 | | SURFACE WATER DEPTH N/A | | | | | | | | | | |
| ELEV (ft) | DRIVE ELEV (ft) | DEPTH (ft) | BLOW COUNT | | | BLOWS PER FOOT | | | | | SAMP. NO. | LOG | SOIL AND ROCK DESCRIPTION | DEPTH (ft) | | |
| | | | 0.5ft | 0.5ft | 0.5ft | 0 | 25 | 50 | 75 | 100 | | | | | | |
| 3075 | | | | | | | | | | | | | | | | |
| | 3,071.1 | 1.0 | 6 | 5 | 5 | | | | | | | | | | 3,072.1 | 0.0 |
| 3070 | 3,068.6 | 3.5 | 5 | 12 | 11 | | | | | | | | | | 3,071.3 | 0.8 |
| | 3,066.1 | 6.0 | 71 | 29/0.3 | | | | | | | | | | | | |
| 3065 | 3,063.6 | 8.5 | 4 | 3 | 4 | | | | | | | | | | | |
| | 3,058.6 | 13.5 | 9 | 30 | 11 | | | | | | | | | | | |
| 3060 | 3,053.6 | 18.5 | 8 | 6 | 4 | | | | | | | | | | | |
| 3055 | 3,049.1 | 23.0 | | | | | | | | | | | | | | |
| | | | 60/0.0 | | | | | | | | | | | | | |
| 3050 | | | | | | | | | | | | | | | | |

NCDOT BORE DOUBLE A-0009CB_GEO_RDY_GTM.GPJ NC_DOT.GDT 5/17/22

GEOPHYSICAL TEST RESULTS – SEISMIC REFRACTION LINE 19.7




GEOPHYSICAL TESTING PERFORMED BY GEL SOLUTIONS. REFERENCE "SEISMIC REFRACTION SURVEY FOR EVALUATION OF ROCK" DATED 10/1/2021

CG2 ESTIMATED WAVE SPEED FOR WEATHERED ROCK: 4,500 FT/SEC

CG2 ESTIMATED WAVE SPEED FOR CRYSTALLINE ROCK: 7,500 FT/SEC

GEOPHYSICAL TEST RESULTS – SEISMIC REFRACTION LINE 19.8



GEOPHYSICAL TESTING PERFORMED BY GEL SOLUTIONS. REFERENCE "SEISMIC REFRACTION SURVEY FOR EVALUATION OF ROCK" DATED 10/01/2021

CG2 ESTIMATED WAVE SPEED FOR WEATHERED ROCK: 4,500 FT/SEC

CG2 ESTIMATED WAVE SPEED FOR CRYSTALLINE ROCK: 7,500 FT/SEC