

**TOTAL BILL OF MATERIAL**

BRIDGE NO.	GROOVING BRIDGE FLOORS	POLLUTION CONTROL	CLASS II SURFACE PREPARATION	CONCRETE REPAIRS	SHOTCRETE REPAIRS	EPOXY RESIN INJECTION	STRIP SEALS FOR PRESERVATION	PAINTING CONTAINMENT FOR BRIDGE #--	CLEANING AND REPAINTING OF BRIDGE #--	VOLUMETRIC MIXER	POURABLE SILICONE JOINT SEALANT	POLYESTER POLYMER CONCRETE MATERIALS	EPOXY POLYMER CONCRETE MATERIALS (ALTERNATE)	SLOPE PROTECTION VOID FILLING	CONCRETE WORK FOR JOINT REPLACEMENT	SCARIFYING BRIDGE DECK	SHOTBLASTING BRIDGE DECK	PLACING & FINISHING POLYMER CONCRETE OVERLAY	TYPE I BRIDGE JACKING BRIDGE NO. --
	SO. FT.	LUMP SUM	SO. YD.	CU. FT.	CU. FT.	LN. FT.	LN. FT.	LUMP SUM	LUMP SUM	LUMP SUM	LN. FT.	CU. YD.	CU. YD.	LBS	SO. FT.	SO. YD.	SO. YD.	SO. YD.	EA
500106	15,785	LUMP SUM	27.6	16.0	26.9	19.0	46.4	LUMP SUM	LUMP SUM	LUMP SUM	272.1	105.7	105.7	13,918.5	100.6	1,898	1,898	1,898	6
500107	15,785	LUMP SUM	26.7	4.6	22.2	28.7	46.4	LUMP SUM	LUMP SUM	LUMP SUM	266.1	105.7	105.7	13,918.5	100.6	1,898	1,898	1,898	1
<b>TOTAL</b>	<b>31,570</b>	<b>LUMP SUM</b>	<b>54.3</b>	<b>20.6</b>	<b>49.1</b>	<b>47.7</b>	<b>92.8</b>	<b>LUMP SUM</b>	<b>LUMP SUM</b>	<b>LUMP SUM</b>	<b>538.2</b>	<b>211.4</b>	<b>211.4</b>	<b>27,837</b>	<b>201.2</b>	<b>3,796</b>	<b>3,796</b>	<b>3,796</b>	<b>7</b>

AT THE TIME OF PREPARATION OF THESE PLANS, IT WAS NOT ANTICIPATED THAT CLASS III DECK SURFACE PREPARATION WOULD BE REQUIRED. HOWEVER, IT MAY BE DETERMINED IN THE FIELD THAT CLASS III DECK SURFACE PREPARATION, OR OTHER WORK WILL BE NECESSARY TO PROPERLY COMPLETE THE INTENDED BRIDGE PRESERVATION/ REHABILITATION WORK. THE CONTRACTOR SHALL BE PREPARED TO PERFORM SUCH WORK IN A TIMELY MANNER, AS DETERMINED IN THE FIELD. SUCH WORK SHALL BE CONSIDERED EXTRA WORK AND SHALL BE ADDRESSED AS PER ARTICLE 104-7 OF THE STANDARD SPECIFICATIONS, PROJECT SPECIAL PROVISIONS THAT OUTLINE REQUIREMENTS FOR THESE POTENTIAL ADDITIONAL WORK ITEMS HAVE BEEN PROVIDED IN PROJECT DOCUMENTS, BUT NO QUANTITIES HAVE BEEN LISTED. ACTUAL PAY ITEMS, QUANTITIES, AND COSTS WILL BE ESTABLISHED, AS REQUIRED, IF EXTRA WORK IS ENCOUNTERED.

PROJECT NO. HI-0008  
JOHNSTON COUNTY  
 BRIDGE NO. : 500106  
 & 500107



STATE OF NORTH CAROLINA  
 DEPARTMENT OF TRANSPORTATION  
 RALEIGH

**BILL OF MATERIAL**  
 FOR BRIDGES 106 & 107 ON  
 I-95 SBL AND NBL OVER  
 NORFOLK SOUTHERN RAILWAY,  
 SR 2305 AND SR 1927

DRAWN BY : G. AYES DATE : 05/2021  
 CHECKED BY : A. G. ABRAHA/S. WANCE DATE : 05/2021

DOCUMENT NOT CONSIDERED  
 FINAL UNLESS ALL  
 SIGNATURES COMPLETED

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			S-2
2			4			TOTAL SHEETS 48