

# UTILITY CONSTRUCTION

**NV5**  
 NV5 ENGINEERS & CONSULTANTS, INC.  
 7500 E. INDEPENDENCE BLVD, STE 100  
 CHARLOTTE, NC 28227  
 P: 704.537.7300 www.NV5.com  
 NC License # F-1333

**STV** 100 Years  
 STV Engineers, Inc.  
 1600 Perimeter Park Drive  
 Suite 225  
 Morrisville, NC 27560  
 NC License Number F-0991

PROJECT REFERENCE NO.	SHEET NO.
I-5987A	UC-3
DESIGNED BY: <b>ABN</b>	
DRAWN BY: <b>ABN</b>	
CHECKED BY: <b>ASV</b>	
APPROVED BY:	
REVISED:	
NORTH CAROLINA DEPARTMENT OF TRANSPORTATION	UTILITY CONSTRUCTION PLANS ONLY
UTILITIES ENGINEERING SEC. PHONE: (919) 707-6690 FAX: (919) 250-4151	

## GENERAL NOTES:

1. THE PROPOSED UTILITY CONSTRUCTION SHALL MEET THE APPLICABLE REQUIREMENTS OF THE NC DEPARTMENT OF TRANSPORTATION'S "STANDARD SPECIFICATIONS FOR ROADS AND STRUCTURES" DATED JANUARY 2018.
2. THE EXISTING UTILITIES BELONG TO THE CITY OF LUMBERTON AND ROBESON COUNTY.
3. ALL WATER LINES TO BE INSTALLED WITHIN COMPLIANCE OF THE RULES AND REGULATIONS OF THE NORTH CAROLINA DEPARTMENT OF ENVIRONMENTAL QUALITY, DIVISION OF WATER RESOURCES, PUBLIC WATER SUPPLY SECTION. ALL SEWER LINES TO BE INSTALLED WITHIN COMPLIANCE OF THE RULES AND REGULATIONS OF THE NORTH CAROLINA DEPARTMENT OF ENVIRONMENT QUALITY, DIVISION OF WATER RESOURCES, WATER QUALITY SECTION. PERFORM ALL WORK IN ACCORDANCE WITH THE APPLICABLE PLUMBING CODES.
4. THE UTILITY OWNER OWNS THE EXISTING UTILITY FACILITIES AND WILL OWN THE NEW UTILITY FACILITIES AFTER ACCEPTANCE BY THE DEPARTMENT. THE DEPARTMENT OWNS THE CONSTRUCTION CONTRACT AND HAS ADMINISTRATIVE AUTHORITY. COMMUNICATIONS AND DECISIONS BETWEEN THE CONTRACTOR AND UTILITY OWNER ARE NOT BINDING UPON THE DEPARTMENT OR THIS CONTRACT UNLESS AUTHORIZED BY THE ENGINEER. AGREEMENTS BETWEEN THE UTILITY OWNER AND CONTRACTOR FOR THE WORK THAT IS NOT PART OF THIS CONTRACT OR IS SECONDARY TO THIS CONTRACT ARE ALLOWED, BUT ARE NOT BINDING UPON THE DEPARTMENT.
5. PROVIDE ACCESS FOR THE DEPARTMENT PERSONNEL AND THE OWNER'S REPRESENTATIVES TO ALL PHASES OF CONSTRUCTION. NOTIFY DEPARTMENT PERSONNEL AND THE UTILITY OWNER TWO WEEKS PRIOR TO COMMENCEMENT OF ANY WORK AND ONE WEEK PRIOR TO SERVICE INTERRUPTION. KEEP UTILITY OWNERS' REPRESENTATIVES INFORMED OF WORK PROGRESS AND PROVIDE OPPORTUNITY FOR INSPECTION OF CONSTRUCTION AND TESTING.

6. THE PLANS DEPICT THE BEST AVAILABLE INFORMATION FOR THE LOCATION, SIZE, AND TYPE OF MATERIAL FOR ALL EXISTING UTILITIES. MAKE INVESTIGATIONS FOR DETERMINING THE EXACT LOCATION, SIZE, AND TYPE MATERIAL OF THE EXISTING FACILITIES AS NECESSARY FOR THE CONSTRUCTION OF THE PROPOSED UTILITIES AND FOR AVOIDING DAMAGE TO EXISTING FACILITIES. REPAIR ANY DAMAGE INCURRED TO EXISTING FACILITIES TO THE ORIGINAL OR BETTER CONDITION AT NO ADDITIONAL COST TO THE DEPARTMENT.
7. MAKE FINAL CONNECTIONS OF THE NEW WORK TO THE EXISTING SYSTEM WHERE INDICATED ON THE PLANS, AS REQUIRED TO FIT THE ACTUAL CONDITIONS, OR AS DIRECTED.
8. MAKE CONNECTIONS BETWEEN EXISTING AND PROPOSED UTILITIES AT TIMES MOST CONVENIENT TO THE PUBLIC, WITHOUT ENDANGERING THE UTILITY SERVICE, AND IN ACCORDANCE WITH THE UTILITY OWNER'S REQUIREMENTS. MAKE CONNECTIONS ON WEEKENDS, AT NIGHT, AND ON HOLIDAYS IF NECESSARY.
9. ALL UTILITY MATERIALS SHALL BE APPROVED PRIOR TO DELIVERY TO THE PROJECT. SEE 1500-7, " SUBMITTALS AND RECORDS" IN SECTION 1500 OF THE STANDARD SPECIFICATIONS.

## PROJECT SPECIFIC NOTES:

1. PROPOSED WATER LINES SHALL BE PVC SDR21 UNLESS INDICATED OTHERWISE. PROPOSED FORCE MAIN SHALL BE C900 PVC DR18 UNLESS INDICATED OTHERWISE.
2. PIPE INSTALLED BY DIRECTIONAL DRILL SHALL BE HDPE DR9 OR C900 FPVC DR18, AS SHOWN ON THE PLANS.
3. CONTRACTOR'S ATTENTION IS DIRECTED TO SECTIONS 102, 107, AND 1550 OF THE STANDARD SPECIFICATIONS CONCERNING TRENCHLESS INSTALLATION. IT IS CONTRACTOR'S RESPONSIBILITY TO HAVE BORE DESIGNED AND SEALED BY A LICENSED NORTH CAROLINA PROFESSIONAL ENGINEER. NO DAMAGE IS ALLOWED TO RIVER, WETLANDS, OR BUFFER ZONES.
4. IF HDPE PIPE IS INSTALLED BY DIRECTIONAL DRILL, IT SHALL BE FILLED WITH WATER AND NOT BE CONNECTED TO ANY OTHER PIPE OR FITTINGS FOR ONE WEEK FROM THE TIME OF INSTALLATION. ENDS OF HDPE PIPE SHALL BE SEALED AFTER INSTALLATION AND PRIOR TO BEING CONNECTED TO OTHER PIPE OR FITTINGS.
5. THERE IS AN ABANDONED 3" FORCE MAIN ALONG DAWN DRIVE IN THE VICINITY OF THE EXISTING 6" FORCE MAIN THAT IS TO BE RELOCATED. CONTRACTOR SHALL PERFORM TEST HOLES AT PROPOSED 6" FORCE MAIN TIE-IN LOCATIONS ALONG DAWN DRIVE PRIOR TO INSTALLING 6" RELOCATION PIPING AND APPURTENANCES.
6. CONTRACTOR TO BACKFILL TO 30" MIN COVER OVER PROPOSED WATER LINES AND FORCE MAINS, WHERE APPLICABLE, PRIOR TO TESTING AND PLACING INTO SERVICE.
7. ROBESON COUNTY WILL COLLECT ALL BACTERIOLOGICAL SAMPLES FOR RELOCATION PROJECTS. A ROBESON COUNTY REPRESENTATIVE SHALL BE PRESENT FOR THE PRESSURE TEST, CHLORINATION, AND FLUSHING OF ALL NEW WATER LINES AND SERVICES.
8. NO CONNECTION SHALL BE MADE BY THE CONTRACTOR TO ANY SECTION OF ROBESON COUNTY'S EXISTING WATER SYSTEM UNLESS THE RESIDENT INSPECTOR, FIELD ENGINEER, OR WATER PLANT SUPERINTENDENT IS PRESENT AT THE SITE. NO VALVE OR HYDRANT SHALL BE OPENED OR CLOSED UNLESS ONE OF THE ABOVE-LISTED PERSONS IS PRESENT AT THE SITE.

## UTILITY CONSTRUCTION

**DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED**