

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS

PROJ. REFERENCE NO.	SHEET NO.
I-5987A	X0-N

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

PHASE 3 CONT'D			474+00.00	9	96	19+50.00	596	0
Station	Uncl. Exc.	Embt	474+50.00	13	96	20+00.00	656	0
L LT CONT'D	(cu. yd.)	(cu. yd.)	475+00.00	20	81	20+50.00	605	0
465+50.00	36	56	475+50.00	29	73	21+00.00	469	0
466+00.00	44	58	476+00.00	37	70	21+12.72	101	0
466+50.00	43	68	476+50.00	40	69			
467+00.00	40	74	477+00.00	41	70			
467+50.00	36	76	477+50.00	37	83			
468+00.00	33	83	478+00.00	31	101			
468+50.00	31	96	478+50.00	23	111			
469+00.00	33	115	479+00.00	13	121			
			479+50.00	13	119			
			480+00.00	12	115			
			480+50.00	9	119			
Station	Uncl. Exc.	Embt	481+00.00	12	108			
Y1ARPADET	(cu. yd.)	(cu. yd.)	481+50.00	15	87			
10+00.00	0	0	482+00.00	16	79			
10+50.00	144	38	482+50.00	34	81			
11+00.00	156	38	483+00.00	94	81			
11+50.00	165	37	483+50.00	186	79			
12+00.00	173	36	483+80.00	140	50			
12+50.00	179	35						
13+00.00	186	34						
13+50.00	209	33	DETOUR REMOVAL					
14+00.00	242	20	SR2DET & Y1ADET REMOVED BETWEEN PHASE 2A AND 2B					
14+50.00	252	6	Station	Uncl. Exc.	Embt			
15+00.00	226	11	SR2DET	(cu. yd.)	(cu. yd.)			
15+50.00	205	40	12+08.72	0	0			
16+00.00	239	85	12+50.00	2050	0			
16+50.00	218	79	13+00.00	2597	0			
17+00.00	134	76	13+50.00	2740	0			
17+50.00	73	111	14+00.00	3026	0			
18+00.00	32	106	14+50.00	3124	0			
18+50.00	24	71	15+00.00	3163	0			
19+00.00	22	48	15+50.00	3508	0			
19+50.00	26	46						
20+00.00	35	26	Station	Uncl. Exc.	Embt			
20+50.00	49	4	Y1ADET	(cu. yd.)	(cu. yd.)			
21+00.00	59	0	13+27.00	0	0			
21+49.65	61	0	13+50.00	0	0			
PHASE 4 -L-			14+00.00	0	0			
Station	Uncl. Exc.	Embt	14+50.00	358	0			
L LT	(cu. yd.)	(cu. yd.)	15+00.00	358	0			
469+00.00	0	0	15+50.00	38	0			
469+50.00	42	127	16+00.00	955	0			
470+00.00	39	121	16+50.00	1746	0			
470+50.00	33	116	17+00.00	1648	0			
471+00.00	38	124	17+50.00	1453	0			
471+50.00	39	129	18+00.00	1136	0			
472+00.00	30	126	18+50.00	884	0			
472+50.00	18	119	19+00.00	663	0			
473+00.00	11	106						
473+50.00	8	96						