



CONCRETE SILL DETAILS



SECTION THROUGH SILL
DOWELS MAY BE PUSHED INTO GREEN CONCRETE AFTER SLAB HAS BEEN FLOAT FINISHED.




INLET ELEVATION
(LOOKING DOWNSTREAM)

THE CONTRACTOR'S ATTENTION IS CALLED TO THE FACT THAT THE NATIVE MATERIAL BACKFILL SHALL BE PLACED PRIOR TO THE CASTING OF THE ROOF SLAB.

NOTES:

- CULVERT FLOOR SLAB IS BURIED 1 FOOT BELOW EXISTING STREAM BED. BACKFILL WITH NATIVE MATERIAL TO SILL HEIGHT IN ALL BARRELS.
- NATIVE MATERIAL BETWEEN SILLS IN THE CULVERT SHALL PROVIDE A CONTINUOUS FLOW CHANNEL.
- NATIVE MATERIAL CONSISTS OF MATERIAL THAT IS EXCAVATED FROM THE STREAM OR FLOODPLAIN AT THE PROJECT SITE DURING CONSTRUCTION. ONLY MATERIAL THAT IS EXCAVATED FROM THE STREAM BED MAY BE USED TO LINE CULVERT BARRELS. RIP RAP MAY BE USED TO SUPPLEMENT THE NATIVE MATERIAL IN THE FLOW BARRELS.
- IF RIP RAP IS USED TO LINE THE FLOW CULVERT BARRELS, NATIVE MATERIAL SHOULD BE PLACED ON TOP TO FILL VOIDS AND PROVIDE A FLAT SURFACE FOR ANIMAL PASSAGE.
- NATIVE MATERIAL IS SUBJECT TO APPROVAL BY THE ENGINEER AND MAY BE SUBJECT TO PERMIT CONDITIONS.
- SILLS ARE TO BE 1 FOOT, CAST SEPARATELY AND ATTACHED BY DOWELS.
- TOP OF SILLS SHOULD MATCH STREAM BED ELEVATION.
- THE ENTIRE COST OF WORK REQUIRED TO PLACE EXCAVATED OR SUPPLEMENTAL MATERIAL AS SHOWN ON THE PLANS SHALL BE INCLUDED IN THE LUMP SUM PRICE FOR CULVERT EXCAVATION.



PLAN

PROJECT NO. I-5987A
ROBESON COUNTY
 STATION: 366+29.00 -L-
 SHEET 6 OF 8

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

**DETAILS OF SILLS
 FOR
 CONCRETE BOX CULVERT**

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	C12-6
1			3			TOTAL SHEETS
2			4			8

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

CDM Smith
 CDM SMITH
 5400 Glenwood Avenue, Suite 400
 Raleigh, NC 27612-3228
 NC COA No. F-1255

DRAWN BY: JJR DATE: 9/21
 CHECKED BY: THF DATE: 12/21
 DESIGN ENGINEER: VDK DATE: 12/21

DWG. No.

