

| DESIGN DISCHARGE | = |
|-----------------------------|---|
| FREQUENCY OF DESIGN FLOOD | = |
| DESIGN HIGH WATER ELEVATION | = |
| DRAINAGE AREA | = |
| BASE DISCHARGE (Q100) | = |
| BASE HIGH WATER ELEVATION | = |
| | |

| OVERTOPPING DISCHARGE | = 330± CFS |
|--------------------------------|------------|
| FREQUENCY OF OVERTOPPING FLOOD | = 10 YRS. |
| OVERTOPPING FLOOD ELEVATION | = 162.9′ * |
| | |

| TOTAL STRUCTURE QUA | NTITIES |
|---------------------------|-------------|
| CULVERT EXCAVATION | LUMP SUM |
| FOUNDATION COND. MATERIAL | |
| STAGE I | 116 TONS |
| STAGE II | 113 TONS |
| STAGE III | 147 TONS |
| TOTAL | 376 TONS |
| CLASS A CONCRETE | |
| STAGE I | 148.1 C.Y. |
| STAGE II | 123.7 C.Y. |
| STAGE III | 181.1 C.Y. |
| TOTAL | 452.9 C.Y. |
| REINFORCING STEEL | |
| STAGE I | 21,805 LBS. |
| STAGE II | 19,756 LBS. |
| STAGE III | 26,878 LBS. |
| TOTAL | 68,439 LBS. |

STAGES I - CONSTRUCT RCBC SECTION AT OUTLET END. STAGES III - CONSTRUCT RCBC SECTION AT INLET END. 1. WING FOOTINGS AND FLOOR SLAB INCLUDING 4" OF ALL VERTICAL WALLS. 2. SILLS WITH NATIVE MATERIAL BACKFILL IN BOTH BARRELS. 3. FOLLOWED BY THE WING WALLS FULL HEIGHT. ROOF SLAB AND HEADWALL. STAGE II - CONSTRUCT RCBC INTERMEDIATE SECTION. 1. FLOOR SLAB INCLUDING 4" OF ALL VERTICAL WALLS. 2. FOLLOWED BY NATIVE MATERIAL BACKFILL AND ROOF SLAB. PROJECT NO. <u>I-5987</u>A ROBESON _COUNTY STATION: 454+90.00 -L-SHEET 1 OF 8 STRUCTURE NO. E2 STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH BARREL STANDARD DOUBLE 8 FT.X 7 FT. (CAR/ CONCRETE BOX CULVERT

ASSUMED LIVE LOAD ----- HL-93 OR ALTERNATE LOADING, FOR CULVERT DIVERSION DETAILS AND PAY ITEM, SEE EROSION CONTROL PLANS. FOR CONSTRUCTION SEQUENCE, EROSION CONTROL AND MEASURES. SEE EROSION CONTROL PLANS. DESIGN FILL----- 6.28' FOR OTHER DESIGN DATA AND NOTES SEE STANDARD NOTE SHEET. 3"Ø WEEP HOLES INDICATED TO BE IN ACCORDANCE WITH THE SPECIFICATIONS. CONCRETE IN CULVERTS TO BE POURED IN THE FOLLOWING ORDER: THE CONTRACTOR SHALL CHECK THE LENGTH OF CULVERT BEFORE STAKING IT OUT TO MAKE CERTAIN THAT IT WILL PROPERLY TAKE CARE OF THE FILL. DIMENSIONS FOR WING LAYOUT AS WELL AS ADDITIONAL REINFORCING STEEL EMBEDDED IN BARRELS ARE SHOWN ON WING SHEET. TRANSVERSE CONSTRUCTION JOINTS SHALL BE USED IN THE BARRELS, SPACED TO LIMIT THE POURS TO A MAXIMUM OF 70 FEET.LOCATION OF JOINTS SHALL BE SUBJECT TO APPROVAL OF THE ENGINEER. STEEL IN THE BOTTOM SLAB MAY BE SPLICED AT THE PERMITTED CONSTRUCTION JOINT AT THE CONTRACTOR'S OPTION. EXTRA WEIGHT OF STEEL DUE TO THE SPLICES SHALL BE PAID FOR BY CONTRACTOR. AT THE CONTRACTOR'S OPTION, HE MAY SPLICE THE VERTICAL REINFORCING STEEL IN THE INTERIOR FACE OF EXTERIOR WALL ABOVE LOWER WALL CONSTRUCTION JOINT. THE SPLICE LENGTH SHALL BE AS PROVIDED IN THE SPLICE LENGTH CHART SHOWN ON THE PLANS. EXTRA WEIGHT OF STEEL DUE TO THE SPLICES SHALL BE PAID FOR BY THE CONTRACTOR. A 3 FOOT STRIP OF FILTER FABRIC SHALL BE ATTACHED TO THE FILL FACE OF THE WING COVERING THE ENTIRE LENGTH OF THE EXPANSION JOINT. NO PRECAST REINFORCED BOX CULVERT OPTION WILL BE ALLOWED. FOR SUBMITTAL OF WORKING DRAWINGS. SEE SPECIAL PROVISIONS. FOR FALSEWORK AND FORMWORK, SEE SPECIAL PROVISIONS. FOR CRANE SAFETY, SEE SPECIAL PROVISIONS. FOR GROUT FOR STRUCTURES, SEE SPECIAL PROVISIONS. FOR TRAFFIC PHASING, LIMITS OF TEMPORARY SHORING, SEE TRAFFIC CONTROL PLANS. FOR PAY ITEM FOR TEMPORARY SHORING, SEE ROADWAY PLANS.

DOCUMENT NOT CONSIDEREE FINAL UNLESS ALL

DWG.No.



SHEET NO.

C1<u>3-1</u>

TOTAL SHEETS

DATE:

130° SKEW

NO. BY:

REVISIONS

DATE:

BY: