PROJECT NO.	SHEET NO.	TOTAL NO.
2023CPT.05.03.20921.1, 2023CPT.05.03.20922.1	35	

SUMMARY OF QUANTITIES

											0264000000-E	1220000000-E	1260000000-E	1297000000-E		1308000000-E			1330000000-E	1503000000-E	1519000000-E	1575000000-E	1704000000-E	2549000000-E	2591000000-E	2613000000-N	2738000000-E	2759000000-N		2830000000-N	2845000000-N	4072000000-E	4102000000-N	7444000000-E
PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	SHOULDER GRADING	INCIDENTAL STONE BASE	AGGREGATE SHOULDER BORROW	2½" MILLING	1½" MILLING	0" TO 1.5" MILLING	0" TO 1.25" MILLING	0" TO 1" MILLING	INCIDENTAL MILLING	INTERMEDIATE COURSE, I19.0C	SURFACE COURSE, S9.5B	ASPHALT BINDER FOR PLANT MIX	PATCHING EXISTING PAVEMENT	2'-6" CURB & GUTTER	4" CONCRETE SIDEWALK	REMOVE AND REPLACE CURB RAMPS	GENERIC PAVING ITEM REMOVE SIDEWALK	GENERIC PAVING ITEM, RETROFIT CURB RAMP DETECTABLE WARNINGS	GENERIC PAVING ITEM, REMOVE CURB RAMP	ADJUST MANHOLES	ADJUST METER OR VALVE BOX	SUPPORTS, 3-LB STEEL U-CHANNEL	SIGN ERECTION, TYPE E	INDUCTIVE LOOP SAWCUT
									MI	FT	SMI	TONS	TON	SY	SY	SY	SY	SY	SY	TONS	TONS	TON	TONS	LF	SY	EA	SY		EA	EA	EA	LF	EA	LF
2023CPT05.03.20921.1	Wake	1	PINEY GROVE WILBON RD. SR 1101	PVMT JOINT TO NC 42	1	2	NO	NO	4.051	30	8.10	203	749			570			1,890		5,907	398	34					2						445
2023CPT05.03.20921.1	Wake	2	PINEY GROVE WILBON RD. SR 1101	NC 42 TO HARNETT CO LINE	2	2	NO	NO	1.459	27	2.92	73	270	23,660		130			900	3,319	2,011	294												
2023CPT05.03.20921.1	Wake	3	DICKENS RD SR 1398	SR 1399 (JAMES SLAUGHTER RD.) TO NC 55	1	2	NO	NO	0.735	20	1.47	37	136			485			340		818	58	57	33	20		13	4	2					
2023CPT05.03.20921.1	Wake	4	TECHNOLOGY PARK LN SR 3969	SR 1398 (DICKENS RD.) TO PVMT JOINT	1	2	NO	NO	0.212	22									65		257	18	12											
2023CPT05.03.20921.1	Wake	5	E VANCE ST SR 2770	US 401 TO SPRING ST.	4	2	NO	NO	0.195	32	0.39	10	36		4,155						351	24	10		2			6		4	2			
2023CPT05.03.20921.1	Wake	6	MASON RD. SR 1150	SR 1011 (OLD US 1 HWY) TO EOM	3	2	NO	NO	0.453	20	0.91	65	84						140		411	38	245											
2023CPT05.03.20921.1	Wake	7	JAMES REST HOME RD SR 1182	SR 1127 (NEW HILL HOLLEMAND RD.) TO DEAD END	3	2	NO	NO	0.405	20									65		361	29	100											
2023CPT05.03.20921.1	Wake	8	TECHNOLOGY DR SR 1191	NC 55 BYP TO EOM	1	2	NO	NO	0.465	24						110			160		785	65	301											
2023CPT05.03.20921.1	Wake	9	THIRD ST SR 1202	NC 55 TO DEAD END	1	2	NO	NO	0.143	27						260			105		191	15	35											
2023CPT05.03.20921.1	Wake	10	OLD MILLS RD SR 1421	SR 1393 (HILLTOP NEEDMORE RD.) TO SR 1404 (JOHNSON POND RD.)	1	2	NO	NO	0.938	20	1.88	47	173						445		1,005	74	173											
2023CPT05.03.20921.1	Wake	11	SOUTH RIDGE DR SR 1507	US 401 TO CUL-DE-SAC	1	2	NO	NO	0.535	20									60		573	42	85											
2023CPT05.03.20921.1	Wake	12	WESTWOOD LN SR 1553	SR 1386 (BELLS LAKE RD.) TO CUL-DE-SAC	3	2	NO	NO	0.171	20									100		183	13	24											
2023CPT05.03.20921.1	Wake	13	SALEM DR SR 1554	SR 1553 (WESTWOOD LN.) TO CUL-DE-SAC	3	2	NO	NO	0.087	20											71	5	10											
2023CPT05.03.20921.1	Wake	14	OLD STURBRIDGE DR SR 4766	SR 1386 (BELLS LAKE RD.) TO CUL-DE-SAC	3	2	NO	NO	0.177	20									95		184	13	21											
2023CPT05.03.20921.1	Wake	15	DURNFORD DR SR 3943	SR 1386 (LAKE BELLS RD.) TO SR 3943 (WANSTRAW WAY)	3	2	NO	NO	0.169	20									150		158	12	25											
2023CPT05.03.20921.1	Wake	16	WANSTRAW WAY SR 3942	SR 1390 (OPTIMIST FARM RD.) TO CUL-DE-SAC	1	2	NO	NO	0.554	20									80		621	46	90											
2023CPT05.03.20921.1	Wake	17	W ALLEN ST SR 1467	US 401 TO EOM	3	2	NO	NO	0.268	18									125		244	17	25											
2023CPT05.03.20921.1	Wake	18	MARIGOLD ST SR 1468	SR 1467 (W. ALLEN ST.) TO DEAD END	3	2	NO	NO	0.091	20									125		91	7	27											
2023CPT05.03.20921.1	Wake	19	LOBELLA ST SR 1469	SR 1467 (W. ALLEN ST. TO DEAD END	3	2	NO	NO	0.119	20									100		214	15	20											
2023CPT05.03.20921.1	Wake	20	CAMELLIA ST SR 2840	SR 2841 (RED BUD ST.) TO SR 2839 (E. ALLEN ST.)	3	2	NO	NO	0.125	18									60		100	10	60											
2023CPT05.03.20921.1	Wake	21	RED BUD ST SR 2841	US 401 TO SR 2840 (CAMELLIA ST)		2	NO	NO	0.5	18									60		64	4												
2023CPT05.03.20921.1	Wake	22	HICKORY DR SR 1447	CUL-DE-SAC TO EOM	3	2	NO	NO	0.295	20											293	28	162											
2023CPT05.03.20921.1	Wake	23	MANOR RIDGE DR SR 1446	SR 1375 (LAKE WHEELER RD.) TO US 401	1	2	NO	NO	0.572	20									125		613	41	10											
2023CPT05.03.20921.1	Wake	24	PURLAND DR SR 1470	SR 1375 (LAKE WHEELER RD.) TO SR 1446 (MANOR RIDGE RD.)	1	2	NO	NO	0.416	20									115		462	31	10											
2023CPT05.03.20921.1	Wake	25	STONEYFORD CT SR 1522	SR 1375 (LAKE WHEELER RD. TO CUL-DE-SAC	3	2	NO	NO	0.182	20									60		185	20	190											
2023CPT05.03.20921.1	Wake	26	REGAL DR SR 3729	SR 3728 (OAKCLIFF LN) TO EOM	3	2	NO	NO	0.152	18											157	11	10								2			
2023CPT05.03.20921.1	Wake	27	OAKCLIFF LN SR 3728	SR 2791 (KENNEBEC CH. RD.) TO CUL-DE-SAC	3	2	NO	NO	0.343	18									160		305	21	18								1			
2023CPT05.03.20921.1	Wake	28	TRAM RD SR 3723	SR 2763 (MAUDE STEWART RD.) TO SR 2763 (MAUDE STEWART RD.)	1	2	NO	NO	0.617	20									305		678	50	108								2			
2023CPT05.03.20921.1	Wake	29	TRESTLE CT SR 3704	SR 2763 (MAUDE STEWART RD.) TO CUL-DE-SAC	3	2	NO	NO	0.137	20									160		149	11	15											
2023CPT05.03.20921.1	Wake	30	MARY MARVIN TRL. SR 3743	SR 2763 (MAUDE STEWART RD.) TO SR 3743 (MARY MARVIN TRL)	1	2	NO	NO	0.956	20						280			95		1,045	74	90											