THE CONTRACTOR'S ATTENTION IS CALLED TO THE FACT THAT DUE TO THE NATURE OF PRESERVATION PROJECTS, THE EXTENT OF WORK CANNOT ALWAYS BE ACCURATELY DETERMINED PRIOR TO COMMENCEMENT OF WORK. REPAIR LOCATIONS AND ESTIMATES OF QUANTITIES ARE GIVEN WITH THE BEST INFORMATION AVAILABLE. IF ADDITIONAL REPAIRS NOT SHOWN ON THE DRAWINGS ARE DEEMED NECESSARY BY THE ENGINEER, THE ENGINEER SHALL NOTE ON THE DRAWINGS THE APPROXIMATE LOCATION AND DESCRIPTION OF THE REPAIRS.

EXISTING DIMENSIONS AND BRIDGE CONDITION ARE FROM THE BEST INFORMATION AVAILABLE. THE CONTRACTOR SHALL FIELD VERIFY THE INFORMATION SHOWN ON THE PLANS AND NOTIFY THE ENGINEER IF ACTUAL DIMENSIONS AND CONDITIONS DIFFER.

THE CONTRACTOR SHALL HAVE NO CLAIM WHATSOEVER AGAINST THE DEPARTMENT FOR ANY DELAYS OF ADDITIONAL COST INCURRED BASED ON DIFFERENCES BETWEEN WHAT IS SHOWN ON THE PLANS AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.

IT IS THE CONTRACTOR'S RESPONSIBILITY TO FOLLOW ALL STATE AND FEDERAL SAFETY REQUIREMENTS.

WORK ON THE BRIDGE(S) SHALL BE PERFORMED SO AS NOT TO ALLOW DEBRIS TO FALL BELOW, EXCEPT WHERE THE CONTRACTOR PLANS TO USE PLATFORMS, NETS, SCREENS OR OTHER PROTECTIVE DEVICES TO CATCH THE MATERIAL. THE CONTRACTOR SHALL SUBMIT PLANS FOR CONSTRUCTION IN ACCORDANCE WITH ARTICLE 402-2 OF THE STANDARD SPECIFICATIONS AND THE PROIECT SPECIAL PROVISIONS.

THE CONTRACTOR SHALL PERFORM ALL WORK WITH CARE SO THAT THE EXISTING STRUCTURE WHICH IS TO REMAIN IN PLACE WILL NOT BE DAMAGED. IF THE CONTRACTOR DAMAGES ANY PART OF THE EXISTING STRUCTURE WHICH IS TO REMAIN IN PLACE, THE DAMAGED AREA SHALL BE REPAIRED OR REPLACED IN A MANNER SATISFACTORY TO THE ENGINEER AT NO ADDITIONAL COST TO THE DEPARTMENT.

ANY DAMAGE TO EXISTING REINFORCING STEEL, DURING CONTRACTOR'S OPERATIONS, SHALL BE REPAIRED AS DIRECTED BY THE ENGINEER AND PERFORMED AT NO ADDITIONAL COST TO THE DEPARTMENT.

FOR CONTROL OF TRAFFIC AND LIMITS ON PHASING OF CONSTRUCTION, SEE TRANSPORTATION MANAGEMENT PLANS.

PRIOR TO BEGINNING WORK, THE CONTRACTOR SHALL SUBMIT FOR REVIEW AND APPROVAL A COMPLETE SEQUENCE OF TASKS FOR EACH OPERATION AFFECTING THE BRIDGE SURFACE AND/OR TRAFFIC.

FOR OTHER DESIGN DATA AND GENERAL NOTES, SEE SHEET SN.

FOR SUBMITTAL OF WORKING DRAWINGS, SEE SPECIAL PROVISIONS.

FOR FALSEWORK AND FORMWORK, SEE SPECIAL PROVISIONS.

FOR CRANE SAFETY, SEE SPECIAL PROVISIONS.

FOR GROUT FOR STRUCTURES, SEE SPECIAL PROVISIONS.

ALL PAVEMENT MARKINGS WILL BE IN ACCORDANCE WITH THE TRAFFIC CONTROL PLANS.

EXISTING JOINTS AND DECK DRAINS SHALL BE SEALED PRIOR TO BEGINNING SURFACE PREPARATIONS OF THE BRIDGE DECK. THE CONTRACTOR SHALL TAKE CARE THAT ANY CONSTRUCTION DEBRIS THAT COLLECTS IN THE DRAINS IS CONTAINED. DRAINS IN SHOULDERS OF ADJACENT TRAVEL LANE(S) SHALL BE KEPT FREE AND CLEAR OF DEBRIS.

FOR BRIDGE JOINT DEMOLITION, SEE SPECIAL PROVISIONS.

FOR POURABLE SILICONE JOINT SEALANT, SEE SPECIAL PROVISIONS.

FOR ELASTOMERIC CONCRETE FOR PRESERVATION, SEE SPECIAL PROVISIONS.

FOR SHOTCRETE REPAIRS, SEE SPECIAL PROVISIONS.

FOR CONCRETE REPAIRS, SEE SPECIAL PROVISIONS.

FOR VOLUMETRIC MIXER, SEE SPECIAL PROVISIONS.

FOR SHOTBLASTING BRIDGE DECK AND SILANE DECK TREATMENT. SEE SPECIAL PROVISIONS.

FOR CONCRETE DECK REPAIR FOR SILANE DECK TREATMENT, SEE SPECIAL PROVISIONS.

FOR REPAIRS TO PRESTRESSED CONCRETE GIRDERS. SEE SPECIAL PROVISIONS.

AT THE TIME OF PREPARATION OF THESE PLANS, IT WAS NOT ANTICIPATED THAT THE FOLLOWING ITEM(S) LISTED WOULD BE REQUIRED. HOWEVER, IT MAY BE DETERMINED IN THE FIELD THAT THE FOLLOWING ITEM(S) LISTED, OR OTHER WORK WILL BE NECESSARY TO PROPERLY COMPLETE THE INTENDED BRIDGE PRESERVATION/REHABILITATION WORK. THE CONTRACTOR SHALL BE PREPARED TO PERFORM SUCH WORK IN A TIMELY MANNER, AS DETERMINED IN THE FIELD. SUCH WORK SHALL BE CONSIDERED EXTRA WORK AND SHALL BE ADDRESSED AS PER ARTICLE 104-7 OF THE STANDARD SPECIFICATIONS. PROJECT SPECIAL PROVISIONS THAT OUTLINE REQUIREMENTS FOR THESE POTENTIAL ADDITIONAL WORK ITEMS HAVE BEEN PROVIDED IN THE PROJECT DOCUMENTS, BUT NO QUANTITIES HAVE BEEN LISTED. ACTUAL PAY ITEMS, QUANTITIES, AND COSTS WILL BE ESTABLISHED, AS REQUIRED, IF EXTRA WORK IS ENCOUNTERED. UNANTICIPATED ITEMS:

| ITEM | DESCRIPTION | UNIT |
|------|---------------------------------|---------|
| 1 | CONCRETE REPAIRS | CU. FT. |
| 2 | SPLICING OF PRESTRESSING STRAND | EA. |

| TOTAL BILL OF MATERIAL | | | | | | | | | | | |
|------------------------|----------------------|---------------------|------------------------------------------|------------------------------------------------|-------------------------------------------------|-------------------------------|------------------------------------------------------------|--------------------------------|-----------------------------|--|--|
| BRIDGE NO. | SHOTCRETE REPAIRS | VOLUMETRIC MIXER | POURABLE SILICONE JOINT SEALANT | ELASTOMERIC CONCRETE FOR PRESERVATION | REPAIRS TO PRESTRESSED CONCRETE GIRDER | BRIDGE JOINT DEMOLITION | CONCRETE DECK REPAIR FOR SILANE DECK TREATMENT | SHOTBLASTING BRIDGE DECK | SILANE DECK TREATMENT | | |
| | CU. FT. | LUMP SUM | LN. FT. | CU. FT. | CU. FT. | SQ. FT. | SQ. FT. | SQ. YD. | SQ. YD. | | |
| 970246 | | LUMP SUM | 74.9 | 12.9 | | 68.6 0.0 869.6 | | 869.6 | | | |
| 970247 | | LUMP SUM | 90.6 | 15.6 | 83.1 0.0 1052.7 | | 1052.7 | | | | |
| 970248 | | LUMP SUM | 104.9 | 18.0 | 96.2 1.0 899.8 | | 899.8 | 899.8 | | | |
| 970249 | | LUMP SUM | 108.1 | 18.6 | 99.1 0.0 913.3 | | 913.3 | 913.3 | | | |
| 970250 | | LUMP SUM | 77.2 | 13.3 | 70.8 0.0 993.6 | | 993.6 | 993.6 | | | |
| 970251 | | LUMP SUM | 77.2 | 13.3 | 70.8 0.0 995.9 | | 995.9 | 995.9 | | | |
| 970252 | | LUMP SUM | 104.5 | 18.0 | 95.8 0.0 2166.4 | | 2166.4 | 2166.4 | | | |
| 970253 | | LUMP SUM | 86.4 | 14.9 | 79.2 0.0 1790.6 | | 1790.6 | 1790.6 | | | |
| 970254 | 4.6 | LUMP SUM | 95.6 | 16.4 | 0.3 | 0.3 87.6 0.0 1075.5 | | 1075.5 | 1075.5 | | |
| 970255 | | LUMP SUM | 69.8 | 12.0 | | 64.0 0.0 791.0 | | 791.0 | | | |
| 970256 | | LUMP SUM | 80.9 | 13.9 | 74.1 0.0 741.4 | | 741.4 | 741.4 | | | |
| 970257 | | LUMP SUM | 80.6 | 13.9 | | 72.0 | | 753.7 | 753.7 | | |
| 970258 | 14.7 | LUMP SUM | 75.2 | 18.8 | 0.3 75.1 0.0 879.8 | | 879.8 | 879.8 | | | |
| 970259 | | LUMP SUM | 75.2 | 12.9 | 68.9 0.0 872.2 | | 872.2 | 872.2 | | | |
| 970260 | | LUMP SUM | 74.8 | 12.9 | 68.6 0.0 923.6 | | 923.6 | 923.6 | | | |
| 970261 | | LUMP SUM | 74.8 | 12.9 | 68.6 0.0 923.6 | | 923.6 | 923.6 | | | |
| TOTAL | 19.3 | LUMP SUM | 1,350.7 | 238.3 | 0.6 | 1,244.4 | 1.0 | 16,642.7 | 16,642.7 | | |

PROJECT NO.HI-0006WILSONCOUNTIESBRIDGE NO.: 970246, 970247, 970248, 970249, 970250, 970251, 970252, 970253, 970254, 970255, 970256, 970257, 970258, 970259, 970260, & 970261

SEAL 030024

OSESSOL

SEAL 030024

Document of the company of the

DEPARTMENT OF TRANSPORTATION
RALEIGH

BILL OF MATERIAL AND GENERAL NOTES

| | REVISIONS | | | | SHEET NO. | | |
|-------------------------|-----------|-----|-------|-----|-----------|-------|-----------------|
| DOCUMENT NOT CONSIDERED | NO. | BY: | DATE: | NO. | BY: | DATE: | S-3 |
| FINAL UNLESS ALL | 1 | | | 3 | | | TOTAL SHEETS |
| SIGNATURES COMPLETED | 2 | | | 4 | | | |

DRAWN BY: G. AYES DATE: 06/2022 CHECKED BY: A. G. ABRAHA DATE: 06/2022