



- NOTES**
1. BOND 0.5 INCH DIAMETER, 28 STRAND (MINIMUM) CLASS II COPPER CONDUCTOR TO THE MAIN GROUND ROD BY AN IRREVERSIBLE MECHANICAL CRIMP METHOD.
  2. ALL CONNECTIONS TO GROUND RODS SHOULD BE MADE WITH AN IRREVERSIBLE MECHANICAL CRIMP METHOD.
  3. BOND #4 AWG SOLID BARE COPPER WIRE TO REBAR CAGE AND THE MAIN GROUND ROD BY AN IRREVERSIBLE MECHANICAL CRIMP.
  4. ENSURE CAMERA HOUSING, CAMERA, AND PAN -TILT UNIT ARE BONDED TO POLE.
  5. REMOVE BONDING JUMPER BETWEEN EQUIPMENT CABINET GROUND BUSS AND NEUTRAL BUSS.
  6. REFER TO STANDARD DRAWING 1700-2 FOR ALTERNATE GROUND ROD INSTALLATION METHOD AS APPROVED BY THE ENGINEER.
  7. INSTALL MARKER TAPE DIRECTLY ABOVE ALL GROUNDING ELECTRODES AND CONDUCTORS AT A DEPTH OF 12 INCHES.

**DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED**

	<b>CCTV CAMERA INSTALLATION FOR METAL POLE WITH UNDERGROUND ELECTRICAL SERVICE TYPICAL DETAIL</b> FORSYTH CO.		SEAL NORTH CAROLINA PROFESSIONAL ENGINEER ANDREW J. SKUCE 05/31/2022
	DIVISION 09 PLAN DATE: FEBRUARY 2022 PREPARED BY: J. WALDEN	REVIEWED BY: A. J. SKUCE, PE REVIEWED BY:	
REVISIONS			DATE

Prepared in the Offices of:  
 750 N. Greenfield Pkwy., Garner, NC 27529