

PROJECT NO.	SHEET NO.	TOTAL NO.
2023CPT.05.05.20731.1	5	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	0264000000-E	1220000000-E	1260000000-E	1297000000-E	1330000000-E	1491000000-E	1503000000-E	1519000000-E	1575000000-E	1704000000-E	2738000000-E	4116100000-N
											SHOULDER GRADING	INCIDENTAL STONE BASE	AGGREGATE SHOULDER BORROW	2½" MILLING	INCIDENTAL MILLING	BASE COURSE, B25.0C	INTERMEDIATE COURSE, I19.0C	SURFACE COURSE, S9.5B	ASPHALT BINDER FOR PLANT MIX	PATCHING EXISTING PAVEMENT	GENERIC PAVING ITEM REMOVE AND REPLACE 5" MONOLITHIC CONCRETE ISLAND (KEYED IN)	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)
									MI	FT	SMI	TONS	TON	SY	SY	TONS	TONS	TONS	TON	TONS	SY	EA
2023CPT.05.05.20731.1	Person	1	SR 1326 - WOODSDALE RD	VIRGINIA STATE LINE TO RR BRIDGE	1	2	NO	NO	1.45	20	2.90	73	714		306		2,572	1,483	224	31		
2023CPT.05.05.20731.1	Person	2	SR 1326 - WOODSDALE RD	RR BRIDGE TO SR 1605 - BOSTON RD	2	2	NO	NO	5.86	23	11.72	293	1,083	79,852	1,000	43	12,205	7,041	1,060		25	2
TOTAL FOR PROJ NO. 2023CPT.05.05.20731.1									7.31		14.62	366	1,797	79,852	1,306	43	14,777	8,524	1,284	31	25	2
GRAND TOTAL									7.31		14.62	366	1,797	79,852	1,306	43	14,777	8,524	1,284	31	25	2

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LENGTH	WIDTH	413000000	57000000	4685000000-E		4709000000-E	4725000000-E		4810000000-E		4850000000-E	4890000000-E		
									WORK ZONE ADVANCE /GENERAL WARNING SIGNING	TEMPORARY TRAFFIC CONTROL	4" X 90 M WHITE THERMO	4" X 90 M YELLOW THERMO	24" X 90 M WHITE THERMO	THERMO LT ARROW 90 M	THERMO RT ARROW 90 M	4" WHITE PAINT	4" YELLOW PAINT	4" LINE REMOVAL	GENERIC MARKING ITEM HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINES, 4", 55 MIL		
									MI	FT	SF	LS	LF	LF	LF	EA	EA	LF	LF	LF	LF
2023CPT.05.05.20731.1	Person	1	SR 1326 - WOODSDALE RD	VIRGINIA STATE LINE TO RR BRIDGE	1	2	1.45	20	163	0.21	15,602	15,312				15,602	15,312	500	500		
2023CPT.05.05.20731.1	Person	2	SR 1326 - WOODSDALE RD	RR BRIDGE TO SR 1605 - BOSTON RD	2	2	5.86	23	657	0.79	63,054	60,699	67	1	1	63,054	60,699				
TOTAL FOR PROJ NO. 2023CPT.05.05.20731.1									7.31		820	1.00	78,656	76,011	67	1	1	78,656	76,011	500	500
GRAND TOTAL									7.31		820	1.00	78,656	76,011	67	1	1	78,656	76,011	500	500