

## STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

J. ERIC BOYETTE
SECRETARY

November 08, 2022

#### Addendum No. 1

RE: Contract # C204802

WBS # 2023CPT.03.03.10101, 2023CPT.03.03.20101, 2023CPT.03.03.20102

STATE FUNDED

**Brunswick County** 

2 SECTIONS OF US-17, 1 SECTION OF NC-904, AND 4 SECTIONS OF

SECONDARY ROADS.

November 15, 2022 Letting

To Whom It May Concern:

Reference is made to the proposal form furnished to you on this project.

The following revisions have been made to the proposal.

Page No.	Revision
Proposal Cover	Note added that reads "Includes Addendum No. 1 Dated 11-
	08-2022".
R-25	Project Special Provision entitled ADJUSTMENT OF
	CATCH BASINS, MANHOLES, DROP INLETS, METER
	BOXES AND VALVE BOXES added.

Please void the above listed Pages in your proposal and staple the revised Pages thereto.

The contract will be prepared accordingly.

Sincerely,

—pocusigned by: Konald Elton Davenport, Jr.

F81B6038A47A442...

Ronald E. Davenport, Jr., PE State Contract Officer RED/cms

Website: www.ncdot.gov

#### Attachments

cc: Mr. Boyd Tharrington, PE Mr. Forrest Dungan, PE

Mr. D. Chad Kimes, PE
Mr. Jon Weathersbee, PE
Mr. Ken Kennedy, PE
Mr. Ken Kennedy, PE
Mr. Mike Gwyn
Mr. Mike Gwyn

# STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH. N.C.

#### **PROPOSAL**

#### **INCLUDES ADDENDUM No.1 DATED 11-08-2022**

DATE AND TIME OF BID OPENING: Nov 15, 2022 AT 02:00 PM

CONTRACT ID C204802

WBS 2023CPT.03.03.10101, 2023CPT.03.03.20101, 2023CPT.03.03.20102

FEDERAL-AID NO. STATE FUNDED

COUNTY BRUNSWICK

T.I.P NO.

MILES 20.900

ROUTE NO.

LOCATION 2 SECTIONS OF US-17, 1 SECTION OF NC-904, AND 4 SECTIONS OF

SECONDARY ROADS.

TYPE OF WORK WIDENING, MILLING, RESURFACING, AND SHOULDER

RECONSTRUCTION.

#### NOTICE:

ALL BIDDERS SHALL COMPLY WITH ALL APPLICABLE LAWS REGULATING THE PRACTICE OF GENERAL CONTRACTING AS CONTAINED IN CHAPTER 87 OF THE GENERAL STATUTES OF NORTH CAROLINA WHICH REQUIRES THE BIDDER TO BE LICENSED BY THE N.C. LICENSING BOARD FOR CONTRACTORS WHEN BIDDING ON ANY NON-FEDERAL AID PROJECT WHERE THE BID IS \$30,000 OR MORE, EXCEPT FOR CERTAIN SPECIALTY WORK AS DETERMINED BY THE LICENSING BOARD. BIDDERS SHALL ALSO COMPLY WITH ALL OTHER APPLICABLE LAWS REGULATING THE PRACTICES OF ELECTRICAL, PLUMBING, HEATING AND AIR CONDITIONING AND REFRIGERATION CONTRACTING AS CONTAINED IN CHAPTER 87 OF THE GENERAL STATUTES OF NORTH CAROLINA. NOTWITHSTANDING THESE LIMITATIONS ON BIDDING, THE BIDDER WHO IS AWARDED ANY FEDERAL - AID FUNDED PROJECT SHALL COMPLY WITH CHAPTER 87 OF THE GENERAL STATUTES OF NORTH CAROLINA FOR LICENSING REQUIREMENTS WITHIN 60 CALENDAR DAYS OF BID OPENING.

BIDS WILL BE RECEIVED AS SHOWN BELOW:

THIS IS A ROADWAY PROPOSAL

5% BID BOND OR BID DEPOSIT REQUIRED

In areas where shoulder construction/reconstruction includes disturbance or grading on the front slope or to the toe of fill, relocating ditch line or backslope, or removing vegetation from the ditch line or swale, NPDES inspection and monitoring are required every 7 days or within 24 hours of a rainfall event of greater than 1.0 inch. Maintain daily rainfall records. Install erosion control measures per detail.

In areas where the vegetated buffer is less than 10 feet between the disturbed area and waters of the State classified as High Quality Water (HQW), Outstanding Resource Water (ORW), Critical Areas, or Unique Wetlands, NPDES inspection and monitoring are required every 7 days or within 24 hours of a rainfall event of greater than 1.0 inch. The Engineer may reduce the vegetated buffer threshold for this requirement to a value between 5 and 10 feet. The plans or provisions will indicate the presence of these water classifications. Maintain daily rainfall records. Install erosion control measures per detail.

Land disturbances hardened with aggregate materials receiving sheet flow are considered non-erodible.

Sites that require lengthy sections of silt fence may substitute with rapid permanent seeding and mulching as directed by the Engineer.

NPDES documentation shall be performed by a Level II Erosion and Sediment Control/Stormwater certificate holder.

Materials used for erosion control will be measured and paid as stated in the contract.

### ADJUSTMENT OF CATCH BASINS, MANHOLES, DROP INLETS, METER BOXES AND VALVE BOXES:

(11-15-22) 858 SP8 R98R

Revise the 2018 Standard Specifications as follows:

Page 8-38, Article 858-4 MEASUREMENT AND PAYMENT, lines 10-11, delete and replace the fifth paragraph with the following:

Where any catch basin, drop inlet, manhole, meter box or valve box is adjusted more than once because of milling operations, each adjustment will be measured and paid.