PROJECT NO.	SHEET NO.	TOTAL NO.
2023CPT.07.11.20011	10	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	0106000000-E BORROW EXCAVATION	1220000000-E INCIDENTAL STONE	1245000000-E SHOULDER RECONSTRUCTION	1297000000-E MILLING ASPHALT PAVEMENT, ****DEPTH (1 1/2")	1330000000-E INCIDENTAL MILLING	1491000000-E ASPHALT CONC BASE COURSE, TYPE B25.0C	1519000000-E ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1575000000-E ASPHALT BINDER FOR PLANT MIX	1704000000-E PATCHING EXISTING PAVEMENT	1775000000-E ASPHALT SURFACE TREATMENT, MAT COAT, #78M STONE	1838000000-E EMULSION FOR ASPHALT SURFACE TREATMENT	2830000000-N ADJ. OF MANHOLES	2845000000-N ADJUSTMENT OF METER BOXES OR VALVE BOXES	6084000000-E SEEDING & MULCHING	6110000000-E RESIDENTIAL SEEDING	7444000000-E INDUCTIVE LOOP SAW CUT	4413000000-E WORK ZONE ADVANCE/GENERAL WARNING SIGNING	4457000000-N TEMPORARY TRAFFIC CONTROL	4720000000-E THERMO MSG STOP 90 M	THERMO MSG AHEAD 90 M	4890000000-E GENERIC MARKING, 4" 50 MILS HOT SPRAY THERMO (WHITE)	GENERIC MARKING, 4" 50 MILS HOT SPRAY THERMO (YELLOW)	GENERIC MARKING, 6" 50 MILS HOT SPRAY THERMO (WHITE)	4709000000-E 24" X 90 M WHITE THERMO
										MI	FT	CY	TONS	SMI	SY	SY	TON	TONS	TON	TONS	SY	GAL	EA	EA	AC	AC	LF	SF	LS	EA	EA	LF	LF	LF	LF
2023CPT.07.11.20011	Alamance	1	SR 1642 - MACARTHUR LN	FROM SR 1529 - DURHAM ST EXT TO SR 1648 - MACARTHUR LN	1	2	2WU	NO	NO	0.833	21		54			175		969	75	215	10,614	3,503	1	4				95				8,585	8,585	48	
		1A	SR 1648 - MACARTHUR LN	FROM SR 1642 - MACARTHUR LN (STA 44+00) TO NC 87	1	2	2WU	NO	NO	0.137	21		9			188		160	12	35	1,749	577						16				1,415	1,415		
TOTAL FOR MAP NO. 1										**0.97**			**63**			**363**		**1,129**	**87**	**250**	**12,363**	**4,080**	**1**	**4**				**111**				**10,000**	**10,000**	**48**	
2023CPT.07.11.20011	Alamance	2	SR 2135 - S JIM MINOR RD	FROM NC 54 TO SR 2142 - MT WILLEN RD	1,3	2	2WU	NO	NO	6.35	21		375		317	875		7,794	585	1,300	85,086	28,078		4			800	724				70,000	64,500	252	35
TOTAL FOR MAP NO. 2										**6.35**			**375**		**317**	**875**		**7,794**	**585**	**1,300**	**85,086**	**28,078**		**4**			**800**	**724**				**70,000**	**64,500**	**252**	**35**
2023CPT.07.11.20011	Alamance	3	SR 1917 - WHITE LEVEL RD	FROM SR 1915 - MILES CHAPEL RD TO NC 119	1	2	2WU	NO	NO	2.063	19		80			775		2,272	174	450	24,876	8,209						234	*			22,500	20,500	46	
TOTAL FOR MAP NO. 3										**2.063**			**80**			**775**		**2,272**	**174**	**450**	**24,876**	**8,209**						**234**				**22,500**	**20,500**	**46**	
2023CPT.07.11.20011	Alamance	4	SR 1005 - W GREENSBORO CHAPEL HILL RD	FROM NC 49 TO SR 1115 - KIMESVILLE RD	2	2	2WU	NO	NO	3.634	21	182	175	7.27		363	4,537	5,066	565	450	49,145	16,218			1.50	1.20		419		4	5	40,000	30,000	150	
TOTAL FOR MAP NO. 4										**3.634**		**182**	**175**	**7.27**		**363**	**4,537**	**5,066**	**565**	**450**	**49,145**	**16,218**			**1.50**	**1.20**		**419**		**4**	**5**	**40,000**	**30,000**	**150**	
2023CPT.07.11.20011	Alamance	5	SR 2327 - BASS MOUNTAIN RD	FROM SR 2326 - MT HERMON ROCK CREEK RD TO SR 1005 - W GREENSBORO CHAPEL HILL RD	1,3	2	2WU	NO	NO	7.58	21		388		264	1,117		9,125	794	3,800	99,714	32,906						860				81,500	68,000	178	
TOTAL FOR MAP NO. 5										**7.58**			**388**		**264**	**1,117**		**9,125**	**794**	**3,800**	**99,714**	**32,906**						**860**				**81,500**	**68,000**	**178**	
TOTAL FOR PROJ NO. 2023CPT.07.11.20011										**20.597**		**182**	**1,081**	**7.27**	**581**	**3,493**	**4,537**	**25,386**	**2,205**	**6,250**	**271,184**	**89,491**	**1**	**8**	**1.50**	**1.20**	**800**	**2,348**	**1**	**9**		**417,000**			**35**
GRAND TOTAL										**20.597**		**182**	**1,081**	**7.27**	**581**	**3,493**	**4,537**	**25,386**	**2,205**	**6,250**	**271,184**	**89,491**	**1**	**8**	**1.50**	**1.20**	**800**	**2,348**	**1**	**9**		**417,000**			**35**
																														4	**5**	**224,000**	**193,000**	**674**	