PROJ. REFERENCE NO.	SHEET NO.
Y-4810K	X-1B

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

Station Y10B	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
10+50.00	0	0	0
11+00.00	3	2	0
11+50.00	8	5	0
11+99.93	15	6	0

Station Y2C	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
14+60.00	0	0	0
15+00.00	1	39	0
15+50.00	27	33	41
16+00.00	85	11	113
16+50.00	100	14	206
17+00.00	128	13	242
17+50.00	183	9	209
18+00.00	170	48	178
18+50.00	142	99	146
19+00.00	151	131	135
19+50.00	190	140	153
20+00.00	130	256	114
20+50.00	51	306	81
21+00.00	174	118	190
21+50.00	345	0	272
22+00.00	490	6	301
22+50.00	351	7	214
22+68.33	44	1	0

Station Y11A	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
12+00.00	0	0	0
12+50.00	23	50	0
13+00.00	35	197	0
13+25.08	52	150	0

Station Y11B	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
11+63.31	0	0	0
12+00.00	31	91	0
12+50.00	42	62	0
12+75.00	10	29	0