




 Map 2 Wallburg Rd SR2691 From
 Business Park Dr to beginning of
 curb and gutter
 Mill 4' in width and 5 1/2" in depth to add
 Approximately 2' additional width, keying
 into existing roadway approximately 2'
 for a total of 28' in width
 Mill 0-1 1/2" incidental mill beginning, end
 and at all SR intersections
 Pave 5 1/2" B25.0C in widening
 Pave 1 1/2" S9.5B