

PROJECT NO.	SHEET NO.	TOTAL NO.
2023CPT.08.05.10531	18	
2023CPT.08.05.20531		

SUMMARY OF QUANTITIES

PROJECT NO	COUNT	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGT H		1297000000-E	1330000000-E	1519000000-E	1523000000-E	1575000000-E	1704000000-E	1840000000-E	2830000000-N	2845000000-N	5255000000-N		
										MI	FT	1.5" MILLING SY	INCIDENTAL MILLING SY	SURFACE COURSE, S9.5B TONS	SURFACE COURSE, S9.5C TONS	ASPHALT BINDER FOR PLANT MIX TONS	PATCHING EXISTING PAVEMENT TONS	MILLED RUMBLE STRIPS LF	ADJUST MANHOLES EA	ADJUST METER OR VALVE BOX EA	PORTABLE LIGHTING LS		
2023CPT.08.05.10531	Lee	1	US 1 SBL	FROM BUS 421 (HORNER BLVD) TO END OF TAPER OF ON RAMP FROM SPRING LN	1	2	MD	NO	NO	1.03	48	23,534			2,174	130		10,877					
TOTAL FOR MAP NO. 1											1.03		23,534		2,174	130		10,877					
2023CPT.08.05.10531	Lee	2	US 1 BUS NBL	FROM SR 1420 (AMOS BRIDGES RD) TO US 1 BYPASS SBL	2,3	2	MU	NO	NO	0.16	35	970	3,030		370	22			1				
TOTAL FOR MAP NO. 2											0.16		970	3,030		370	22		1				
2023CPT.08.05.10531	Lee	3	US 15-501 NBL	FROM US 1 BYPASS SBL TO SR 1467 PERKINSON RD	2,3	2	MU	NO	NO	0.28	37	2,825	2,276		471	28							
TOTAL FOR MAP NO. 3											0.28		2,825	2,276		471	28						
2023CPT.08.05.10531	Lee	4	US 15-501 SBL	FROM SR 1467 (PERKINSON RD) TO US 1 BYPASS SBL	2,3	2	MU	NO	NO	0.28	36	3,280	6,520		905	54					*		
TOTAL FOR MAP NO. 4											0.28		3,280	6,520		905	54						
2023CPT.08.05.10531	Lee	5	US 1 BYPASS EXIT 71 SB ON RAMP	FROM US 15-501 TO US 1 BYPASS	2	1		NO	NO	0.2	24	3,145			265	16							
TOTAL FOR MAP NO. 5											0.2		3,145			265	16						
2023CPT.08.05.10531	Lee	6	US 1 BUS SBL	FROM US 1 BYPASS SBL TO SR 1420 (AMOS BRIDGES RD)	2,3	2	MU	NO	NO	0.14	36	965	965		244	15							
TOTAL FOR MAP NO. 6											0.14		965	965		244	15						
TOTAL FOR PROJ NO. 2023CPT.08.05.10531											2.09		34,719	12,791		4,429	265		10,877	1		1	
2023CPT.08.05.20531	Lee	7	SR 1007 (N PLANK RD)	FROM CHATHAM CO TO NC 42	5	2	2WU	NO	NO	3.46	22		245	5,403		376	300						
TOTAL FOR MAP NO. 7											3.46			245	5,403		376	300					
2023CPT.08.05.20531	Lee	8	SR 1464 (WOMACK RD)	FROM SR 1466 (DEEP RIVER RD) TO SR 1475 (OAK PARK RD)	4	2	2WU	NO	NO	0.93	24		265	1,584		112	125		1	1			
TOTAL FOR MAP NO. 8											0.93			265	1,584		112	125		1	1		
2023CPT.08.05.20531	Lee	9	SR 1479 (ELWIN BUCHANAN)	FROM SR 1466 (DEEP RIVER RD) TO SR 1476 (CLYDE RHYNE)	4	2	2WU	NO	NO	0.41	24		265	699		49	50						
TOTAL FOR MAP NO. 9											0.41			265	699		49	50					
2023CPT.08.05.20531	Lee	10	SR 1475 (OAK PARK RD)	FROM SR 1464 (WOMACK RD) TO RR TRACKS	4	2	2WU	NO	NO	0.28	24		275	383		28	50		1				
TOTAL FOR MAP NO. 10											0.28			275	383		28	50		1			
2023CPT.08.05.20531	Lee	11	SR 1476 (CLYDE RHYNE DR)	FROM SR 1464 (WOMACK RD) TO END OF STATE MAINT.	4	2	2WU	NO	NO	0.45	24		265	581		39			1	2			
TOTAL FOR MAP NO. 11											0.45			265	581		39			1	2		
2023CPT.08.05.20531	Lee	12	SR 1477 (REX MCLEOD DR)	FROM SR 1476 (CLYDE RHYNE DR) TO DEAD END	4	2	2WU	NO	NO	0.23	24		275	301		21	20						
TOTAL FOR MAP NO. 12											0.23			275	301		21	20					
TOTAL FOR PROJ NO. 2023CPT.08.05.20531											5.76			1,590	8,951		625	545		3	3		
GRAND TOTAL											7.85			34,719	14,381		8,951	4,429		10,877	4	3	1