

REFERENCE: BR-0029

PROJECT: 67029

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT

STRUCTURE
SUBSURFACE INVESTIGATION

COUNTY MACON
PROJECT DESCRIPTION REPLACE BRDG #0026 ON
NC-106 (DILLARD RD) over MIDDLE CREEK

CONTENTS

SHEET NO.	DESCRIPTION
1	TITLE SHEET
2-2A	LEGEND (SOIL & ROCK)
3	SITE PLAN
4	PROFILE
5-7	CROSS SECTIONS
8-11	BORE & CORE LOGS
12-14	CORE PHOTOGRAPHS

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	BR-0029	1	14

CAUTION NOTICE

THE SUBSURFACE INFORMATION AND THE SUBSURFACE INVESTIGATION ON WHICH IT IS BASED WERE MADE FOR THE PURPOSE OF STUDY, PLANNING AND DESIGN, AND NOT FOR CONSTRUCTION OR PAY PURPOSES. THE VARIOUS FIELD BORING LOGS, ROCK CORES AND SOIL TEST DATA AVAILABLE MAY BE REVIEWED OR INSPECTED IN RALEIGH BY CONTACTING THE N. C. DEPARTMENT OF TRANSPORTATION, GEOTECHNICAL ENGINEERING UNIT AT (919) 707-6850. THE SUBSURFACE PLANS AND REPORTS, FIELD BORING LOGS, ROCK CORES AND SOIL TEST DATA ARE NOT PART OF THE CONTRACT.

GENERAL SOIL AND ROCK STRATA DESCRIPTIONS AND INDICATED BOUNDARIES ARE BASED ON A GEOTECHNICAL INTERPRETATION OF ALL AVAILABLE SUBSURFACE DATA AND MAY NOT NECESSARILY REFLECT THE ACTUAL SUBSURFACE CONDITIONS BETWEEN BORINGS OR BETWEEN SAMPLED STRATA WITHIN THE BOREHOLE. THE LABORATORY SAMPLE DATA AND THE IN SITU (IN-PLACE) TEST DATA CAN BE RELIED ON ONLY TO THE DEGREE OF RELIABILITY INHERENT IN THE STANDARD TEST METHOD. THE OBSERVED WATER LEVELS OR SOIL MOISTURE CONDITIONS INDICATED IN THE SUBSURFACE INVESTIGATIONS ARE AS RECORDED AT THE TIME OF THE INVESTIGATION. THESE WATER LEVELS OR SOIL MOISTURE CONDITIONS MAY VARY CONSIDERABLY WITH TIME ACCORDING TO CLIMATIC CONDITIONS INCLUDING TEMPERATURES, PRECIPITATION AND WIND, AS WELL AS OTHER NON-CLIMATIC FACTORS.

THE BIDDER OR CONTRACTOR IS CAUTIONED THAT DETAILS SHOWN ON THE SUBSURFACE PLANS ARE PRELIMINARY ONLY AND IN MANY CASES THE FINAL DESIGN DETAILS ARE DIFFERENT. FOR BIDDING AND CONSTRUCTION PURPOSES, REFER TO THE CONSTRUCTION PLANS AND DOCUMENTS FOR FINAL DESIGN INFORMATION ON THIS PROJECT. THE DEPARTMENT DOES NOT WARRANT OR GUARANTEE THE SUFFICIENCY OR ACCURACY OF THE INVESTIGATION MADE, NOR THE INTERPRETATIONS MADE, OR OPINION OF THE DEPARTMENT AS TO THE TYPE OF MATERIALS AND CONDITIONS TO BE ENCOUNTERED. THE BIDDER OR CONTRACTOR IS CAUTIONED TO MAKE SUCH INDEPENDENT SUBSURFACE INVESTIGATIONS AS HE DEEMS NECESSARY TO SATISFY HIMSELF AS TO CONDITIONS TO BE ENCOUNTERED ON THE PROJECT. THE CONTRACTOR SHALL HAVE NO CLAIM FOR ADDITIONAL COMPENSATION OR FOR AN EXTENSION OF TIME FOR ANY REASON RESULTING FROM THE ACTUAL CONDITIONS ENCOUNTERED AT THE SITE DIFFERING FROM THOSE INDICATED IN THE SUBSURFACE INFORMATION.

- NOTES:
- THE INFORMATION CONTAINED HEREIN IS NOT IMPLIED OR GUARANTEED BY THE N. C. DEPARTMENT OF TRANSPORTATION AS ACCURATE NOR IS IT CONSIDERED PART OF THE PLANS, SPECIFICATIONS OR CONTRACT FOR THE PROJECT.
 - BY HAVING REQUESTED THIS INFORMATION, THE CONTRACTOR SPECIFICALLY WAIVES ANY CLAIMS FOR INCREASED COMPENSATION OR EXTENSION OF TIME BASED ON DIFFERENCES BETWEEN THE CONDITIONS INDICATED HEREIN AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.

PERSONNEL

-NCDOT-

DC CHEEK

CJ COFFEY

DC ELLIOTT


INVESTIGATED BY NCDOT GEU

DRAWN BY DC ELLIOTT

CHECKED BY JC KUHNE

SUBMITTED BY JC KUHNE

DATE _____



DocuSigned by:
D. Clayton Elliott 7/19/2019
FD421F60CB08 SIGNATURE DATE

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT
SUBSURFACE INVESTIGATION
SOIL AND ROCK LEGEND, TERMS, SYMBOLS, AND ABBREVIATIONS

SOIL DESCRIPTION										GRADATION										ROCK DESCRIPTION										TERMS AND DEFINITIONS																																																																																																																																																																																																											
SOIL IS CONSIDERED UNCONSOLIDATED, SEMI-CONSOLIDATED, OR WEATHERED EARTH MATERIALS THAT CAN BE PENETRATED WITH A CONTINUOUS FLIGHT POWER AUGER AND YIELD LESS THAN 100 BLOWS PER FOOT ACCORDING TO THE STANDARD PENETRATION TEST (AASHTO T 206, ASTM D1586). SOIL CLASSIFICATION IS BASED ON THE AASHTO SYSTEM. BASIC DESCRIPTIONS GENERALLY INCLUDE THE FOLLOWING: CONSISTENCY, COLOR, TEXTURE, MOISTURE, AASHTO CLASSIFICATION, AND OTHER PERTINENT FACTORS SUCH AS MINERALOGICAL COMPOSITION, ANGULARITY, STRUCTURE, PLASTICITY, ETC. FOR EXAMPLE, <i>VERY STIFF, GRAY, SILTY CLAY, MOIST WITH INTERBEDDED FINE SAND LAYERS, HIGHLY PLASTIC, A-7-6</i>										WELL GRADED - INDICATES A GOOD REPRESENTATION OF PARTICLE SIZES FROM FINE TO COARSE. UNIFORMLY GRADED - INDICATES THAT SOIL PARTICLES ARE ALL APPROXIMATELY THE SAME SIZE. GAP-GRADED - INDICATES A MIXTURE OF UNIFORM PARTICLE SIZES OF TWO OR MORE SIZES.										HARD ROCK IS NON-COASTAL PLAIN MATERIAL THAT WOULD YIELD SPT REFUSAL IF TESTED, AN INFERRED ROCK LINE INDICATES THE LEVEL AT WHICH NON-COASTAL PLAIN MATERIAL WOULD YIELD SPT REFUSAL. SPT REFUSAL IS PENETRATION BY A SPLIT SPOON SAMPLER EQUAL TO OR LESS THAN 0.1 FOOT PER 60 BLOWS IN NON-COASTAL PLAIN MATERIAL. THE TRANSITION BETWEEN SOIL AND ROCK IS OFTEN REPRESENTED BY A ZONE OF WEATHERED ROCK. ROCK MATERIALS ARE TYPICALLY DIVIDED AS FOLLOWS: WEATHERED ROCK (WR) NON-COASTAL PLAIN MATERIAL THAT WOULD YIELD SPT N VALUES > 100 BLOWS PER FOOT IF TESTED. CRYSTALLINE ROCK (CR) FINE TO COARSE GRAIN IGNEOUS AND METAMORPHIC ROCK THAT WOULD YIELD SPT REFUSAL IF TESTED. ROCK TYPE INCLUDES GRANITE, GNEISS, GABBRO, SCHIST, ETC. NON-CRYSTALLINE ROCK (NCR) FINE TO COARSE GRAIN METAMORPHIC AND NON-COASTAL PLAIN SEDIMENTARY ROCK THAT WOULD YIELD SPT REFUSAL IF TESTED. ROCK TYPE INCLUDES PHYLLITE, SLATE, SANDSTONE, ETC. COASTAL PLAIN SEDIMENTARY ROCK (CPS) COASTAL PLAIN SEDIMENTS CEMENTED INTO ROCK, BUT MAY NOT YIELD SPT REFUSAL. ROCK TYPE INCLUDES LIMESTONE, SANDSTONE, CEMENTED SHELL BEDS, ETC.										ALLUVIUM (ALLUV.) - SOILS THAT HAVE BEEN TRANSPORTED BY WATER. AQUIFER - A WATER BEARING FORMATION OR STRATA. ARENACEOUS - APPLIED TO ROCKS THAT HAVE BEEN DERIVED FROM SAND OR THAT CONTAIN SAND. ARGILLACEOUS - APPLIED TO ALL ROCKS OR SUBSTANCES COMPOSED OF CLAY MINERALS, OR HAVING A NOTABLE PROPORTION OF CLAY IN THEIR COMPOSITION, SUCH AS SHALE, SLATE, ETC. ARTESIAN - GROUND WATER THAT IS UNDER SUFFICIENT PRESSURE TO RISE ABOVE THE LEVEL AT WHICH IT IS ENCOUNTERED, BUT WHICH DOES NOT NECESSARILY RISE TO OR ABOVE THE GROUND SURFACE. CALCAREOUS (CALC.) - SOILS THAT CONTAIN APPRECIABLE AMOUNTS OF CALCIUM CARBONATE. COLLUVIUM - ROCK FRAGMENTS MIXED WITH SOIL DEPOSITED BY GRAVITY ON SLOPE OR AT BOTTOM OF SLOPE. CORE RECOVERY (REC.) - TOTAL LENGTH OF ALL MATERIAL RECOVERED IN THE CORE BARREL DIVIDED BY TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE. DIKE - A TABULAR BODY OF IGNEOUS ROCK THAT CUTS ACROSS THE STRUCTURE OF ADJACENT ROCKS OR CUTS MASSIVE ROCK. DIP - THE ANGLE AT WHICH A STRATUM OR ANY PLANAR FEATURE IS INCLINED FROM THE HORIZONTAL. DIP DIRECTION (DIP AZIMUTH) - THE DIRECTION OR BEARING OF THE HORIZONTAL TRACE OF THE LINE OF DIP, MEASURED CLOCKWISE FROM NORTH. FAULT - A FRACTURE OR FRACTURE ZONE ALONG WHICH THERE HAS BEEN DISPLACEMENT OF THE SIDES RELATIVE TO ONE ANOTHER PARALLEL TO THE FRACTURE. FISSILE - A PROPERTY OF SPLITTING ALONG CLOSELY SPACED PARALLEL PLANES. FLOAT - ROCK FRAGMENTS ON SURFACE NEAR THEIR ORIGINAL POSITION AND DISLODGED FROM PARENT MATERIAL. FLOOD PLAIN (FP) - LAND BORDERING A STREAM, BUILT OF SEDIMENTS DEPOSITED BY THE STREAM. FORMATION (FM) - A MAPPABLE GEOLOGIC UNIT THAT CAN BE RECOGNIZED AND TRACED IN THE FIELD. JOINT - FRACTURE IN ROCK ALONG WHICH NO APPRECIABLE MOVEMENT HAS OCCURRED. LEDGE - A SHELF-LIKE RIDGE OR PROJECTION OF ROCK WHOSE THICKNESS IS SMALL COMPARED TO ITS LATERAL EXTENT. LENS - A BODY OF SOIL OR ROCK THAT THINS OUT IN ONE OR MORE DIRECTIONS. MOTTLED (MOT.) - IRREGULARLY MARKED WITH SPOTS OF DIFFERENT COLORS. MOTTLING IN SOILS USUALLY INDICATES POOR AERATION AND LACK OF GOOD DRAINAGE. PERCHED WATER - WATER MAINTAINED ABOVE THE NORMAL GROUND WATER LEVEL BY THE PRESENCE OF AN INTERVENING IMPERVIOUS STRATUM. RESIDUAL (RES.) SOIL - SOIL FORMED IN PLACE BY THE WEATHERING OF ROCK. ROCK QUALITY DESIGNATION (ROD) - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE. SAPROLITE (SAP.) - RESIDUAL SOIL THAT RETAINS THE RELIC STRUCTURE OR FABRIC OF THE PARENT ROCK. SILL - AN INTRUSIVE BODY OF IGNEOUS ROCK OF APPROXIMATELY UNIFORM THICKNESS AND RELATIVELY THIN COMPARED WITH ITS LATERAL EXTENT, THAT HAS BEEN EMPLACED PARALLEL TO THE BEDDING OR SCHISTOSITY OF THE INTRUDED ROCKS. SLICKENSIDE - POLISHED AND STRIATED SURFACE THAT RESULTS FROM FRICTION ALONG A FAULT OR SLIP PLANE. STANDARD PENETRATION TEST (PENETRATION RESISTANCE) (SPT) - NUMBER OF BLOWS (N OR BPF) OF A 140 LB. HAMMER FALLING 30 INCHES REQUIRED TO PRODUCE A PENETRATION OF 1 FOOT INTO SOIL WITH A 2 INCH OUTSIDE DIAMETER SPLIT SPOON SAMPLER. SPT REFUSAL IS PENETRATION EQUAL TO OR LESS THAN 0.1 FOOT PER 60 BLOWS. STRATA CORE RECOVERY (SREC.) - TOTAL LENGTH OF STRATA MATERIAL RECOVERED DIVIDED BY TOTAL LENGTH OF STRATUM AND EXPRESSED AS A PERCENTAGE. STRATA ROCK QUALITY DESIGNATION (SROD) - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS WITHIN A STRATUM EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF STRATA AND EXPRESSED AS A PERCENTAGE. TOPSOIL (TS.) - SURFACE SOILS USUALLY CONTAINING ORGANIC MATTER.																																																																																																																																																																																																											
<p style="text-align: center;">SOIL LEGEND AND AASHTO CLASSIFICATION</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th rowspan="2">GENERAL CLASS.</th> <th colspan="5">GRANULAR MATERIALS (≤ 35% PASSING #200)</th> <th colspan="5">SILT-CLAY MATERIALS (> 35% PASSING #200)</th> <th colspan="5">ORGANIC MATERIALS</th> </tr> <tr> <th>A-1</th> <th>A-1-b</th> <th>A-2</th> <th>A-2-4</th> <th>A-2-5</th> <th>A-2-6</th> <th>A-2-7</th> <th>A-4</th> <th>A-5</th> <th>A-6</th> <th>A-7</th> <th>A-1, A-2</th> <th>A-3</th> <th>A-4, A-5</th> <th>A-6, A-7</th> </tr> </thead> <tbody> <tr> <td>GROUP CLASS.</td> <td>A-1-a</td> <td>A-1-b</td> <td>A-2-4</td> <td>A-2-5</td> <td>A-2-6</td> <td>A-2-7</td> <td>A-4</td> <td>A-5</td> <td>A-6</td> <td>A-7</td> <td>A-1, A-2</td> <td>A-3</td> <td>A-4, A-5</td> <td>A-6, A-7</td> </tr> <tr> <td>SYMBOL</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>% PASSING #10 #40 #200</td> <td>50 MX 30 MX 15 MX</td> <td>50 MX 25 MX</td> <td>10 MN 35 MX</td> <td>10 MN 35 MX</td> <td>10 MN 35 MX</td> <td>10 MN 35 MX</td> <td>36 MN 36 MN</td> <td>36 MN 36 MN</td> <td>36 MN 36 MN</td> <td>36 MN 36 MN</td> <td>GRANULAR SOILS</td> <td>SILT-CLAY SOILS</td> <td>MUCK, PEAT</td> </tr> <tr> <td>MATERIAL PASSING #40 LL PI</td> <td>-</td> <td>-</td> <td>40 MX 10 MN</td> <td>41 MN 10 MN</td> <td>40 MX 11 MN</td> <td>41 MN 11 MN</td> <td>40 MX 10 MN</td> <td>41 MN 10 MN</td> <td>40 MX 11 MN</td> <td>41 MN 11 MN</td> <td>SOILS WITH LITTLE OR MODERATE AMOUNTS OF ORGANIC MATTER</td> <td>HIGHLY ORGANIC SOILS</td> </tr> <tr> <td>GROUP INDEX</td> <td>0</td> <td>0</td> <td>0</td> <td>0</td> <td>4 MX</td> <td>8 MX</td> <td>12 MX</td> <td>16 MX</td> <td>NO MX</td> <td></td> <td></td> <td></td> </tr> <tr> <td>USUAL TYPES OF MAJOR MATERIALS</td> <td>STONE GRAVEL, SAND</td> <td>FINE SAND</td> <td>SILTY OR CLAYEY GRAVEL AND SAND</td> <td>SILTY SOILS</td> <td>CLAYEY SOILS</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>GEN. RATING AS SUBGRADE</td> <td colspan="5">EXCELLENT TO GOOD</td> <td colspan="5">FAIR TO POOR</td> <td>FAIR TO POOR</td> <td>POOR</td> <td>UNSATURABLE</td> </tr> <tr> <td colspan="10">PI OF A-7-5 SUBGROUP IS ≤ LL - 30 ; PI OF A-7-6 SUBGROUP IS > LL - 30</td> </tr> </tbody> </table>										GENERAL CLASS.	GRANULAR MATERIALS (≤ 35% PASSING #200)					SILT-CLAY MATERIALS (> 35% PASSING #200)					ORGANIC MATERIALS					A-1	A-1-b	A-2	A-2-4	A-2-5	A-2-6	A-2-7	A-4	A-5	A-6	A-7	A-1, A-2	A-3	A-4, A-5	A-6, A-7	GROUP CLASS.	A-1-a	A-1-b	A-2-4	A-2-5	A-2-6	A-2-7	A-4	A-5	A-6	A-7	A-1, A-2	A-3	A-4, A-5	A-6, A-7	SYMBOL															% PASSING #10 #40 #200	50 MX 30 MX 15 MX	50 MX 25 MX	10 MN 35 MX	10 MN 35 MX	10 MN 35 MX	10 MN 35 MX	36 MN 36 MN	36 MN 36 MN	36 MN 36 MN	36 MN 36 MN	GRANULAR SOILS	SILT-CLAY SOILS	MUCK, PEAT	MATERIAL PASSING #40 LL PI	-	-	40 MX 10 MN	41 MN 10 MN	40 MX 11 MN	41 MN 11 MN	40 MX 10 MN	41 MN 10 MN	40 MX 11 MN	41 MN 11 MN	SOILS WITH LITTLE OR MODERATE AMOUNTS OF ORGANIC MATTER	HIGHLY ORGANIC SOILS	GROUP INDEX	0	0	0	0	4 MX	8 MX	12 MX	16 MX	NO MX				USUAL TYPES OF MAJOR MATERIALS	STONE GRAVEL, SAND	FINE SAND	SILTY OR CLAYEY GRAVEL AND SAND	SILTY SOILS	CLAYEY SOILS								GEN. RATING AS SUBGRADE	EXCELLENT TO GOOD					FAIR TO POOR					FAIR TO POOR	POOR	UNSATURABLE	PI OF A-7-5 SUBGROUP IS ≤ LL - 30 ; PI OF A-7-6 SUBGROUP IS > LL - 30										<p style="text-align: center;">MINERALOGICAL COMPOSITION</p> <p>MINERAL NAMES SUCH AS QUARTZ, FELDSPAR, MICA, TALC, KAOLIN, ETC. ARE USED IN DESCRIPTIONS WHEN THEY ARE CONSIDERED OF SIGNIFICANCE.</p> <p style="text-align: center;">COMPRESSIBILITY</p> <p>SLIGHTLY COMPRESSIBLE LL < 31 MODERATELY COMPRESSIBLE LL = 31 - 50 HIGHLY COMPRESSIBLE LL > 50</p> <p style="text-align: center;">PERCENTAGE OF MATERIAL</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th></th> <th>GRANULAR SOILS</th> <th>SILT - CLAY SOILS</th> <th>OTHER MATERIAL</th> </tr> </thead> <tbody> <tr> <td>TRACE OF ORGANIC MATTER</td> <td>2 - 3%</td> <td>3 - 5%</td> <td>TRACE 1 - 10%</td> </tr> <tr> <td>LITTLE ORGANIC MATTER</td> <td>3 - 5%</td> <td>5 - 12%</td> <td>LITTLE 10 - 20%</td> </tr> <tr> <td>MODERATELY ORGANIC</td> <td>5 - 10%</td> <td>12 - 20%</td> <td>SOME 20 - 35%</td> </tr> <tr> <td>HIGHLY ORGANIC</td> <td>> 10%</td> <td>> 20%</td> <td>HIGHLY 35% AND ABOVE</td> </tr> </tbody> </table> <p style="text-align: center;">GROUND WATER</p> <p> WATER LEVEL IN BORE HOLE IMMEDIATELY AFTER DRILLING STATIC WATER LEVEL AFTER 24 HOURS PERCHED WATER, SATURATED ZONE, OR WATER BEARING STRATA SPRING OR SEEP</p> <p style="text-align: center;">MISCELLANEOUS SYMBOLS</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <tbody> <tr> <td> ROADWAY EMBANKMENT (RE) WITH SOIL DESCRIPTION</td> <td> DIP & DIP DIRECTION OF ROCK STRUCTURES</td> <td> SLOPE INDICATOR INSTALLATION</td> </tr> <tr> <td> SOIL SYMBOL</td> <td> TEST BORING</td> <td> CONE PENETROMETER TEST</td> </tr> <tr> <td> ARTIFICIAL FILL (AF) OTHER THAN ROADWAY EMBANKMENT</td> <td> AUGER BORING</td> <td> SOUNDING ROD</td> </tr> <tr> <td> INFERRED SOIL BOUNDARY</td> <td> CORE BORING</td> <td> TEST BORING WITH CORE</td> </tr> <tr> <td> INFERRED ROCK LINE</td> <td> MONITORING WELL</td> <td> SPT N-VALUE</td> </tr> <tr> <td> ALLUVIAL SOIL BOUNDARY</td> <td> PIEZOMETER INSTALLATION</td> <td></td> </tr> </tbody> </table>											GRANULAR SOILS	SILT - CLAY SOILS	OTHER MATERIAL	TRACE OF ORGANIC MATTER	2 - 3%	3 - 5%	TRACE 1 - 10%	LITTLE ORGANIC MATTER	3 - 5%	5 - 12%	LITTLE 10 - 20%	MODERATELY ORGANIC	5 - 10%	12 - 20%	SOME 20 - 35%	HIGHLY ORGANIC	> 10%	> 20%	HIGHLY 35% AND ABOVE	ROADWAY EMBANKMENT (RE) WITH SOIL DESCRIPTION	DIP & DIP DIRECTION OF ROCK STRUCTURES	SLOPE INDICATOR INSTALLATION	SOIL SYMBOL	TEST BORING	CONE PENETROMETER TEST	ARTIFICIAL FILL (AF) OTHER THAN ROADWAY EMBANKMENT	AUGER BORING	SOUNDING ROD	INFERRED SOIL BOUNDARY	CORE BORING	TEST BORING WITH CORE	INFERRED ROCK LINE	MONITORING WELL	SPT N-VALUE	ALLUVIAL SOIL BOUNDARY	PIEZOMETER INSTALLATION		<p style="text-align: center;">TEXTURE OR GRAIN SIZE</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>U.S. STD. SIEVE SIZE OPENING (MM)</th> <th>4</th> <th>10</th> <th>40</th> <th>60</th> <th>200</th> <th>270</th> </tr> </thead> <tbody> <tr> <td></td> <td>4.76</td> <td>2.00</td> <td>0.42</td> <td>0.25</td> <td>0.075</td> <td>0.053</td> </tr> </tbody> </table> <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>BOULDER (BLDR.)</th> <th>COBBLE (COB.)</th> <th>GRAVEL (GR.)</th> <th>COARSE SAND (CSE. SD.)</th> <th>FINE SAND (F SD.)</th> <th>SILT (SL.)</th> <th>CLAY (CL.)</th> </tr> </thead> <tbody> <tr> <td>GRAIN SIZE MM IN.</td> <td>305 12</td> <td>75 3</td> <td>2.0</td> <td>0.25</td> <td>0.05</td> <td>0.005</td> </tr> </tbody> </table>										U.S. STD. SIEVE SIZE OPENING (MM)	4	10	40	60	200	270		4.76	2.00	0.42	0.25	0.075	0.053	BOULDER (BLDR.)	COBBLE (COB.)	GRAVEL (GR.)	COARSE SAND (CSE. SD.)	FINE SAND (F SD.)	SILT (SL.)	CLAY (CL.)	GRAIN SIZE MM IN.	305 12	75 3	2.0	0.25	0.05	0.005
GENERAL CLASS.	GRANULAR MATERIALS (≤ 35% PASSING #200)					SILT-CLAY MATERIALS (> 35% PASSING #200)					ORGANIC MATERIALS																																																																																																																																																																																																																														
	A-1	A-1-b	A-2	A-2-4	A-2-5	A-2-6	A-2-7	A-4	A-5	A-6	A-7	A-1, A-2	A-3	A-4, A-5	A-6, A-7																																																																																																																																																																																																																										
GROUP CLASS.	A-1-a	A-1-b	A-2-4	A-2-5	A-2-6	A-2-7	A-4	A-5	A-6	A-7	A-1, A-2	A-3	A-4, A-5	A-6, A-7																																																																																																																																																																																																																											
SYMBOL																																																																																																																																																																																																																																									
% PASSING #10 #40 #200	50 MX 30 MX 15 MX	50 MX 25 MX	10 MN 35 MX	10 MN 35 MX	10 MN 35 MX	10 MN 35 MX	36 MN 36 MN	36 MN 36 MN	36 MN 36 MN	36 MN 36 MN	GRANULAR SOILS	SILT-CLAY SOILS	MUCK, PEAT																																																																																																																																																																																																																												
MATERIAL PASSING #40 LL PI	-	-	40 MX 10 MN	41 MN 10 MN	40 MX 11 MN	41 MN 11 MN	40 MX 10 MN	41 MN 10 MN	40 MX 11 MN	41 MN 11 MN	SOILS WITH LITTLE OR MODERATE AMOUNTS OF ORGANIC MATTER	HIGHLY ORGANIC SOILS																																																																																																																																																																																																																													
GROUP INDEX	0	0	0	0	4 MX	8 MX	12 MX	16 MX	NO MX																																																																																																																																																																																																																																
USUAL TYPES OF MAJOR MATERIALS	STONE GRAVEL, SAND	FINE SAND	SILTY OR CLAYEY GRAVEL AND SAND	SILTY SOILS	CLAYEY SOILS																																																																																																																																																																																																																																				
GEN. RATING AS SUBGRADE	EXCELLENT TO GOOD					FAIR TO POOR					FAIR TO POOR	POOR	UNSATURABLE																																																																																																																																																																																																																												
PI OF A-7-5 SUBGROUP IS ≤ LL - 30 ; PI OF A-7-6 SUBGROUP IS > LL - 30																																																																																																																																																																																																																																									
	GRANULAR SOILS	SILT - CLAY SOILS	OTHER MATERIAL																																																																																																																																																																																																																																						
TRACE OF ORGANIC MATTER	2 - 3%	3 - 5%	TRACE 1 - 10%																																																																																																																																																																																																																																						
LITTLE ORGANIC MATTER	3 - 5%	5 - 12%	LITTLE 10 - 20%																																																																																																																																																																																																																																						
MODERATELY ORGANIC	5 - 10%	12 - 20%	SOME 20 - 35%																																																																																																																																																																																																																																						
HIGHLY ORGANIC	> 10%	> 20%	HIGHLY 35% AND ABOVE																																																																																																																																																																																																																																						
ROADWAY EMBANKMENT (RE) WITH SOIL DESCRIPTION	DIP & DIP DIRECTION OF ROCK STRUCTURES	SLOPE INDICATOR INSTALLATION																																																																																																																																																																																																																																							
SOIL SYMBOL	TEST BORING	CONE PENETROMETER TEST																																																																																																																																																																																																																																							
ARTIFICIAL FILL (AF) OTHER THAN ROADWAY EMBANKMENT	AUGER BORING	SOUNDING ROD																																																																																																																																																																																																																																							
INFERRED SOIL BOUNDARY	CORE BORING	TEST BORING WITH CORE																																																																																																																																																																																																																																							
INFERRED ROCK LINE	MONITORING WELL	SPT N-VALUE																																																																																																																																																																																																																																							
ALLUVIAL SOIL BOUNDARY	PIEZOMETER INSTALLATION																																																																																																																																																																																																																																								
U.S. STD. SIEVE SIZE OPENING (MM)	4	10	40	60	200	270																																																																																																																																																																																																																																			
	4.76	2.00	0.42	0.25	0.075	0.053																																																																																																																																																																																																																																			
BOULDER (BLDR.)	COBBLE (COB.)	GRAVEL (GR.)	COARSE SAND (CSE. SD.)	FINE SAND (F SD.)	SILT (SL.)	CLAY (CL.)																																																																																																																																																																																																																																			
GRAIN SIZE MM IN.	305 12	75 3	2.0	0.25	0.05	0.005																																																																																																																																																																																																																																			
<p style="text-align: center;">SOIL MOISTURE - CORRELATION OF TERMS</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>SOIL MOISTURE SCALE (ATTERBERG LIMITS)</th> <th>FIELD MOISTURE DESCRIPTION</th> <th>GUIDE FOR FIELD MOISTURE DESCRIPTION</th> </tr> </thead> <tbody> <tr> <td>LL - LIQUID LIMIT</td> <td>- SATURATED - (SAT.)</td> <td>USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE</td> </tr> <tr> <td>PLASTIC RANGE (PI)</td> <td>- WET - (W)</td> <td>SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE</td> </tr> <tr> <td>OM - OPTIMUM MOISTURE</td> <td>- MOIST - (M)</td> <td>SOLID; AT OR NEAR OPTIMUM MOISTURE</td> </tr> <tr> <td>SL - SHRINKAGE LIMIT</td> <td>- DRY - (D)</td> <td>REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE</td> </tr> </tbody> </table>										SOIL MOISTURE SCALE (ATTERBERG LIMITS)	FIELD MOISTURE DESCRIPTION	GUIDE FOR FIELD MOISTURE DESCRIPTION	LL - LIQUID LIMIT	- SATURATED - (SAT.)	USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE	PLASTIC RANGE (PI)	- WET - (W)	SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE	OM - OPTIMUM MOISTURE	- MOIST - (M)	SOLID; AT OR NEAR OPTIMUM MOISTURE	SL - SHRINKAGE LIMIT	- DRY - (D)	REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE	<p style="text-align: center;">RECOMMENDATION SYMBOLS</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <tbody> <tr> <td> UNDERCUT</td> <td> UNCLASSIFIED EXCAVATION - UNSUITABLE WASTE</td> <td> UNCLASSIFIED EXCAVATION - ACCEPTABLE, BUT NOT TO BE USED IN THE TOP 3 FEET OF EMBANKMENT OR BACKFILL</td> </tr> <tr> <td> SHALLOW UNDERCUT</td> <td> UNCLASSIFIED EXCAVATION - ACCEPTABLE DEGRADABLE ROCK</td> <td></td> </tr> </tbody> </table> <p style="text-align: center;">ABBREVIATIONS</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <tbody> <tr> <td>AR - AUGER REFUSAL</td> <td>MED. - MEDIUM</td> <td>VST - VANE SHEAR TEST</td> </tr> <tr> <td>BT - BORING TERMINATED</td> <td>MICA - MICACEOUS</td> <td>WEA. - WEATHERED</td> </tr> <tr> <td>CL - CLAY</td> <td>MOD. - MODERATELY</td> <td>UW - UNIT WEIGHT</td> </tr> <tr> <td>CPT - CONE PENETRATION TEST</td> <td>NP - NON PLASTIC</td> <td>UDW - DRY UNIT WEIGHT</td> </tr> <tr> <td>CSE - COARSE</td> <td>ORG. - ORGANIC</td> <td></td> </tr> <tr> <td>DMT - DILATOMETER TEST</td> <td>PMT - PRESSUREMETER TEST</td> <td></td> </tr> <tr> <td>DPT - DYNAMIC PENETRATION TEST</td> <td>SAP. - SAPROLITIC</td> <td></td> </tr> <tr> <td>e - VOID RATIO</td> <td>SD. - SAND, SANDY</td> <td></td> </tr> <tr> <td>F - FINE</td> <td>SL. - SILTY, SILTY</td> <td></td> </tr> <tr> <td>FOSS. - FOSSILIFEROUS</td> <td>SLI. - SLIGHTLY</td> <td></td> </tr> <tr> <td>FRAC. - FRACTURED, FRACTURES</td> <td>TCR - TRICONE REFUSAL</td> <td></td> </tr> <tr> <td>FRAG. - FRAGMENTS</td> <td>w - MOISTURE CONTENT</td> <td></td> </tr> <tr> <td>HL - HIGHLY</td> <td>V - VERY</td> <td></td> </tr> </tbody> </table>										UNDERCUT	UNCLASSIFIED EXCAVATION - UNSUITABLE WASTE	UNCLASSIFIED EXCAVATION - ACCEPTABLE, BUT NOT TO BE USED IN THE TOP 3 FEET OF EMBANKMENT OR BACKFILL	SHALLOW UNDERCUT	UNCLASSIFIED EXCAVATION - ACCEPTABLE DEGRADABLE ROCK		AR - AUGER REFUSAL	MED. - MEDIUM	VST - VANE SHEAR TEST	BT - BORING TERMINATED	MICA - MICACEOUS	WEA. - WEATHERED	CL - CLAY	MOD. - MODERATELY	UW - UNIT WEIGHT	CPT - CONE PENETRATION TEST	NP - NON PLASTIC	UDW - DRY UNIT WEIGHT	CSE - COARSE	ORG. - ORGANIC		DMT - DILATOMETER TEST	PMT - PRESSUREMETER TEST		DPT - DYNAMIC PENETRATION TEST	SAP. - SAPROLITIC		e - VOID RATIO	SD. - SAND, SANDY		F - FINE	SL. - SILTY, SILTY		FOSS. - FOSSILIFEROUS	SLI. - SLIGHTLY		FRAC. - FRACTURED, FRACTURES	TCR - TRICONE REFUSAL		FRAG. - FRAGMENTS	w - MOISTURE CONTENT		HL - HIGHLY	V - VERY																																																																																																																																																											
SOIL MOISTURE SCALE (ATTERBERG LIMITS)	FIELD MOISTURE DESCRIPTION	GUIDE FOR FIELD MOISTURE DESCRIPTION																																																																																																																																																																																																																																							
LL - LIQUID LIMIT	- SATURATED - (SAT.)	USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE																																																																																																																																																																																																																																							
PLASTIC RANGE (PI)	- WET - (W)	SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE																																																																																																																																																																																																																																							
OM - OPTIMUM MOISTURE	- MOIST - (M)	SOLID; AT OR NEAR OPTIMUM MOISTURE																																																																																																																																																																																																																																							
SL - SHRINKAGE LIMIT	- DRY - (D)	REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE																																																																																																																																																																																																																																							
UNDERCUT	UNCLASSIFIED EXCAVATION - UNSUITABLE WASTE	UNCLASSIFIED EXCAVATION - ACCEPTABLE, BUT NOT TO BE USED IN THE TOP 3 FEET OF EMBANKMENT OR BACKFILL																																																																																																																																																																																																																																							
SHALLOW UNDERCUT	UNCLASSIFIED EXCAVATION - ACCEPTABLE DEGRADABLE ROCK																																																																																																																																																																																																																																								
AR - AUGER REFUSAL	MED. - MEDIUM	VST - VANE SHEAR TEST																																																																																																																																																																																																																																							
BT - BORING TERMINATED	MICA - MICACEOUS	WEA. - WEATHERED																																																																																																																																																																																																																																							
CL - CLAY	MOD. - MODERATELY	UW - UNIT WEIGHT																																																																																																																																																																																																																																							
CPT - CONE PENETRATION TEST	NP - NON PLASTIC	UDW - DRY UNIT WEIGHT																																																																																																																																																																																																																																							
CSE - COARSE	ORG. - ORGANIC																																																																																																																																																																																																																																								
DMT - DILATOMETER TEST	PMT - PRESSUREMETER TEST																																																																																																																																																																																																																																								
DPT - DYNAMIC PENETRATION TEST	SAP. - SAPROLITIC																																																																																																																																																																																																																																								
e - VOID RATIO	SD. - SAND, SANDY																																																																																																																																																																																																																																								
F - FINE	SL. - SILTY, SILTY																																																																																																																																																																																																																																								
FOSS. - FOSSILIFEROUS	SLI. - SLIGHTLY																																																																																																																																																																																																																																								
FRAC. - FRACTURED, FRACTURES	TCR - TRICONE REFUSAL																																																																																																																																																																																																																																								
FRAG. - FRAGMENTS	w - MOISTURE CONTENT																																																																																																																																																																																																																																								
HL - HIGHLY	V - VERY																																																																																																																																																																																																																																								
<p style="text-align: center;">PLASTICITY</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>NON PLASTIC</th> <th>PLASTICITY INDEX (PI)</th> <th>DRY STRENGTH</th> </tr> </thead> <tbody> <tr> <td>SLIGHTLY PLASTIC</td> <td>0-5</td> <td>VERY LOW</td> </tr> <tr> <td>MODERATELY PLASTIC</td> <td>6-15</td> <td>SLIGHT</td> </tr> <tr> <td>HIGHLY PLASTIC</td> <td>16-25</td> <td>MEDIUM</td> </tr> <tr> <td></td> <td>26 OR MORE</td> <td>HIGH</td> </tr> </tbody> </table> <p style="text-align: center;">COLOR</p> <p>DESCRIPTIONS MAY INCLUDE COLOR OR COLOR COMBINATIONS (TAN, RED, YELLOW-BROWN, BLUE-GRAY). MODIFIERS SUCH AS LIGHT, DARK, STREAKED, ETC. ARE USED TO DESCRIBE APPEARANCE.</p>										NON PLASTIC	PLASTICITY INDEX (PI)	DRY STRENGTH	SLIGHTLY PLASTIC	0-5	VERY LOW	MODERATELY PLASTIC	6-15	SLIGHT	HIGHLY PLASTIC	16-25	MEDIUM		26 OR MORE	HIGH	<p style="text-align: center;">EQUIPMENT USED ON SUBJECT PROJECT</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <tbody> <tr> <td>DRILL UNITS:</td> <td>ADVANCING TOOLS:</td> <td>HAMMER TYPE:</td> </tr> <tr> <td><input checked="" type="checkbox"/> CME-45C</td> <td><input type="checkbox"/> CLAY BITS</td> <td><input checked="" type="checkbox"/> AUTOMATIC <input type="checkbox"/> MANUAL</td> </tr> <tr> <td><input type="checkbox"/> CME-55</td> <td><input type="checkbox"/> 6" CONTINUOUS FLIGHT AUGER</td> <td></td> </tr> <tr> <td><input type="checkbox"/> CME-550</td> <td><input type="checkbox"/> 8" HOLLOW AUGERS</td> <td></td> </tr> <tr> <td><input type="checkbox"/> VANE SHEAR TEST</td> <td><input type="checkbox"/> HARD FACED FINGER BITS</td> <td></td> </tr> <tr> <td><input type="checkbox"/> PORTABLE HOIST</td> <td><input type="checkbox"/> TUNG-CARBIDE INSERTS</td> <td></td> </tr> <tr> <td></td> <td><input checked="" type="checkbox"/> CASING <input checked="" type="checkbox"/> W/ ADVANCER</td> <td></td> </tr> <tr> <td></td> <td><input type="checkbox"/> TRICONE _____ *STEEL TEETH</td> <td></td> </tr> <tr> <td></td> <td><input type="checkbox"/> TRICONE _____ *TUNG-CARB.</td> <td></td> </tr> <tr> <td></td> <td><input type="checkbox"/> CORE BIT</td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> </tr> </tbody> </table>										DRILL UNITS:	ADVANCING TOOLS:	HAMMER TYPE:	<input checked="" type="checkbox"/> CME-45C	<input type="checkbox"/> CLAY BITS	<input checked="" type="checkbox"/> AUTOMATIC <input type="checkbox"/> MANUAL	<input type="checkbox"/> CME-55	<input type="checkbox"/> 6" CONTINUOUS FLIGHT AUGER		<input type="checkbox"/> CME-550	<input type="checkbox"/> 8" HOLLOW AUGERS		<input type="checkbox"/> VANE SHEAR TEST	<input type="checkbox"/> HARD FACED FINGER BITS		<input type="checkbox"/> PORTABLE HOIST	<input type="checkbox"/> TUNG-CARBIDE INSERTS			<input checked="" type="checkbox"/> CASING <input checked="" type="checkbox"/> W/ ADVANCER			<input type="checkbox"/> TRICONE _____ *STEEL TEETH			<input type="checkbox"/> TRICONE _____ *TUNG-CARB.			<input type="checkbox"/> CORE BIT																																																																																																																																																																										
NON PLASTIC	PLASTICITY INDEX (PI)	DRY STRENGTH																																																																																																																																																																																																																																							
SLIGHTLY PLASTIC	0-5	VERY LOW																																																																																																																																																																																																																																							
MODERATELY PLASTIC	6-15	SLIGHT																																																																																																																																																																																																																																							
HIGHLY PLASTIC	16-25	MEDIUM																																																																																																																																																																																																																																							
	26 OR MORE	HIGH																																																																																																																																																																																																																																							
DRILL UNITS:	ADVANCING TOOLS:	HAMMER TYPE:																																																																																																																																																																																																																																							
<input checked="" type="checkbox"/> CME-45C	<input type="checkbox"/> CLAY BITS	<input checked="" type="checkbox"/> AUTOMATIC <input type="checkbox"/> MANUAL																																																																																																																																																																																																																																							
<input type="checkbox"/> CME-55	<input type="checkbox"/> 6" CONTINUOUS FLIGHT AUGER																																																																																																																																																																																																																																								
<input type="checkbox"/> CME-550	<input type="checkbox"/> 8" HOLLOW AUGERS																																																																																																																																																																																																																																								
<input type="checkbox"/> VANE SHEAR TEST	<input type="checkbox"/> HARD FACED FINGER BITS																																																																																																																																																																																																																																								
<input type="checkbox"/> PORTABLE HOIST	<input type="checkbox"/> TUNG-CARBIDE INSERTS																																																																																																																																																																																																																																								
	<input checked="" type="checkbox"/> CASING <input checked="" type="checkbox"/> W/ ADVANCER																																																																																																																																																																																																																																								
	<input type="checkbox"/> TRICONE _____ *STEEL TEETH																																																																																																																																																																																																																																								
	<input type="checkbox"/> TRICONE _____ *TUNG-CARB.																																																																																																																																																																																																																																								
	<input type="checkbox"/> CORE BIT																																																																																																																																																																																																																																								
<p style="text-align: center;">FRACATURE SPACING</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>TERM</th> <th>SPACING</th> </tr> </thead> <tbody> <tr> <td>VERY WIDE</td> <td>MORE THAN 10 FEET</td> </tr> <tr> <td>WIDE</td> <td>3 TO 10 FEET</td> </tr> <tr> <td>MODERATELY CLOSE</td> <td>1 TO 3 FEET</td> </tr> <tr> <td>CLOSE</td> <td>0.16 TO 1 FOOT</td> </tr> <tr> <td>VERY CLOSE</td> <td>LESS THAN 0.16 FEET</td> </tr> </tbody> </table> <p style="text-align: center;">BEDDING</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>TERM</th> <th>THICKNESS</th> </tr> </thead> <tbody> <tr> <td>VERY THICKLY BEDDED</td> <td>4 FEET</td> </tr> <tr> <td>THICKLY BEDDED</td> <td>1.5 - 4 FEET</td> </tr> <tr> <td>THINLY BEDDED</td> <td>0.16 - 1.5 FEET</td> </tr> <tr> <td>VERY THINLY BEDDED</td> <td>0.03 - 0.16 FEET</td> </tr> <tr> <td>THICKLY LAMINATED</td> <td>0.008 - 0.03 FEET</td> </tr> <tr> <td>THINLY LAMINATED</td> <td>< 0.008 FEET</td> </tr> </tbody> </table>										TERM	SPACING	VERY WIDE	MORE THAN 10 FEET	WIDE	3 TO 10 FEET	MODERATELY CLOSE	1 TO 3 FEET	CLOSE	0.16 TO 1 FOOT	VERY CLOSE	LESS THAN 0.16 FEET	TERM	THICKNESS	VERY THICKLY BEDDED	4 FEET	THICKLY BEDDED	1.5 - 4 FEET	THINLY BEDDED	0.16 - 1.5 FEET	VERY THINLY BEDDED	0.03 - 0.16 FEET	THICKLY LAMINATED	0.008 - 0.03 FEET	THINLY LAMINATED	< 0.008 FEET	<p style="text-align: center;">INDURATION</p> <p>FOR SEDIMENTARY ROCKS, INDURATION IS THE HARDENING OF MATERIAL BY CEMENTING, HEAT, PRESSURE, ETC.</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <tbody> <tr> <td>FRIABLE</td> <td>RUBBING WITH FINGER FREES NUMEROUS GRAINS; GENTLE BLOW BY HAMMER DISINTEGRATES SAMPLE.</td> </tr> <tr> <td>MODERATELY INDURATED</td> <td>GRAINS CAN BE SEPARATED FROM SAMPLE WITH STEEL PROBE; BREAKS EASILY WHEN HIT WITH HAMMER.</td> </tr> <tr> <td>INDURATED</td> <td>GRAINS ARE DIFFICULT TO SEPARATE WITH STEEL PROBE; DIFFICULT TO BREAK WITH HAMMER.</td> </tr> <tr> <td>EXTREMELY INDURATED</td> <td>SHARP HAMMER BLOWS REQUIRED TO BREAK SAMPLE; SAMPLE BREAKS ACROSS GRAINS.</td> </tr> </tbody> </table>										FRIABLE	RUBBING WITH FINGER FREES NUMEROUS GRAINS; GENTLE BLOW BY HAMMER DISINTEGRATES SAMPLE.	MODERATELY INDURATED	GRAINS CAN BE SEPARATED FROM SAMPLE WITH STEEL PROBE; BREAKS EASILY WHEN HIT WITH HAMMER.	INDURATED	GRAINS ARE DIFFICULT TO SEPARATE WITH STEEL PROBE; DIFFICULT TO BREAK WITH HAMMER.	EXTREMELY INDURATED	SHARP HAMMER BLOWS REQUIRED TO BREAK SAMPLE; SAMPLE BREAKS ACROSS GRAINS.																																																																																																																																																																																				
TERM	SPACING																																																																																																																																																																																																																																								
VERY WIDE	MORE THAN 10 FEET																																																																																																																																																																																																																																								
WIDE	3 TO 10 FEET																																																																																																																																																																																																																																								
MODERATELY CLOSE	1 TO 3 FEET																																																																																																																																																																																																																																								
CLOSE	0.16 TO 1 FOOT																																																																																																																																																																																																																																								
VERY CLOSE	LESS THAN 0.16 FEET																																																																																																																																																																																																																																								
TERM	THICKNESS																																																																																																																																																																																																																																								
VERY THICKLY BEDDED	4 FEET																																																																																																																																																																																																																																								
THICKLY BEDDED	1.5 - 4 FEET																																																																																																																																																																																																																																								
THINLY BEDDED	0.16 - 1.5 FEET																																																																																																																																																																																																																																								
VERY THINLY BEDDED	0.03 - 0.16 FEET																																																																																																																																																																																																																																								
THICKLY LAMINATED	0.008 - 0.03 FEET																																																																																																																																																																																																																																								
THINLY LAMINATED	< 0.008 FEET																																																																																																																																																																																																																																								
FRIABLE	RUBBING WITH FINGER FREES NUMEROUS GRAINS; GENTLE BLOW BY HAMMER DISINTEGRATES SAMPLE.																																																																																																																																																																																																																																								
MODERATELY INDURATED	GRAINS CAN BE SEPARATED FROM SAMPLE WITH STEEL PROBE; BREAKS EASILY WHEN HIT WITH HAMMER.																																																																																																																																																																																																																																								
INDURATED	GRAINS ARE DIFFICULT TO SEPARATE WITH STEEL PROBE; DIFFICULT TO BREAK WITH HAMMER.																																																																																																																																																																																																																																								
EXTREMELY INDURATED	SHARP HAMMER BLOWS REQUIRED TO BREAK SAMPLE; SAMPLE BREAKS ACROSS GRAINS.																																																																																																																																																																																																																																								
<p style="text-align: center;">BENCH MARK: BM8 : SPIKE NAIL IN BASE OF 18' TULIP POPLAR @ APPROX -L- STA 18+10, ~45' RT : N: 486136 E : 705720 ELEVATION: 3413.09 FEET</p> <p style="text-align: center;">NOTES:</p> <p>FIAD - FILLED IMMEDIATELY AFTER DRILLING</p>																																																																																																																																																																																																																																									















NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT

SUBSURFACE INVESTIGATION

SUPPLEMENTAL LEGEND, GEOLOGICAL STRENGTH INDEX (GSI) TABLES
FROM AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS


AASHTO LRFD Figure 10.4.6.4-1 — Determination of GSI for Jointed Rock Mass (Marinos and Hoek, 2000)

AASHTO LRFD Figure 10.4.6.4-2 — Determination of GSI for Tectonically Deformed Heterogeneous Rock Masses (Marinos and Hoek, 2000)


GEOLOGICAL STRENGTH INDEX (GSI) FOR JOINTED ROCKS (Hoek and Marinos, 2000)		SURFACE CONDITIONS					GSI FOR HETEROGENEOUS ROCK MASSES SUCH AS FLYSCH (Marinos, P and Hoek E., 2000)		SURFACE CONDITIONS OF DISCONTINUITIES (Predominantly bedding planes)				
From the lithology, structure and surface conditions of the discontinuities, estimate the average value of GSI. Do not try to be too precise. Quoting a range from 33 to 37 is more realistic than stating that GSI = 35. Note that the table does not apply to structurally controlled failures. Where weak planar structural planes are present in an unfavorable orientation with respect to the excavation face, these will dominate the rock mass behaviour. The shear strength of surfaces in rocks that are prone to deterioration as a result of changes in moisture content will be reduced if water is present. When working with rocks in the fair to very poor categories, a shift to the right may be made for wet conditions. Water pressure is dealt with by effective stress analysis.		VERY GOOD Very rough, fresh unweathered surfaces	GOOD Rough, slightly weathered, iron stained surfaces	FAIR Smooth, moderately weathered and altered surfaces	POOR Slickensided, highly weathered surfaces with compact coatings or fillings or angular fragments	VERY POOR Slickensided, highly weathered surfaces with soft clay coatings or fillings	From a description of the lithology, structure and surface conditions (particularly of the bedding planes), choose a box in the chart. Locate the position in the box that corresponds to the condition of the discontinuities and estimate the average value of GSI from the contours. Do not attempt to be too precise. Quoting a range from 33 to 37 is more realistic than giving GSI = 35. Note that the Hoek-Brown criterion does not apply to structurally controlled failures. Where unfavourably oriented continuous weak planar discontinuities are present, these will dominate the behaviour of the rock mass. The strength of some rock masses is reduced by the presence of groundwater and this can be allowed for by a slight shift to the right in the columns for fair, poor and very poor conditions. Water pressure does not change the value of GSI and it is dealt with by using effective stress analysis.		VERY GOOD - Very Rough, fresh unweathered surfaces	GOOD - Rough, slightly weathered surfaces	FAIR - Smooth, moderately weathered and altered surfaces	POOR - Very smooth, occasionally slickensided surfaces with compact coatings or fillings with angular fragments	VERY POOR - Very smooth, slickensided or highly weathered surfaces with soft clay coatings or fillings
STRUCTURE		DECREASING SURFACE QUALITY →					COMPOSITION AND STRUCTURE						
 INTACT OR MASSIVE - intact rock specimens or massive in situ rock with few widely spaced discontinuities		90			N/A	N/A	 A. Thick bedded, very blocky sandstone. The effect of pelitic coatings on the bedding planes is minimized by the confinement of the rock mass. In shallow tunnels or slopes these bedding planes may cause structurally controlled instability.	70					
 BLOCKY - well interlocked undisturbed rock mass consisting of cubical blocks formed by three intersecting discontinuity sets		80					 B. Sandstone with thin inter-layers of siltstone	60					
 VERY BLOCKY - interlocked, partially disturbed mass with multi-faceted angular blocks formed by 4 or more joint sets			70				 C. Sandstone and siltstone in similar amounts	50					
 BLOCKY/DISTURBED/SEAMY - folded with angular blocks formed by many intersecting discontinuity sets. Persistence of bedding planes or schistosity			60				 D. Siltstone or silty shale with sandstone layers	40					
 DISINTEGRATED - poorly interlocked, heavily broken rock mass with mixture of angular and rounded rock pieces			50				 E. Weak siltstone or clayey shale with sandstone layers	30					
 LAMINATED/SHEARED - Lack of blockiness due to close spacing of weak schistosity or shear planes			40				 F. Tectonically deformed, intensively folded/faulted, sheared clayey shale or siltstone with broken and deformed sandstone layers forming an almost chaotic structure	20					
			30				 G. Undisturbed silty or clayey shale with or without a few very thin sandstone layers	10					
			20				 H. Tectonically deformed silty or clayey shale forming a chaotic structure with pockets of clay. Thin layers of sandstone are transformed into small rock pieces.						
			10										
		N/A	N/A										

→ Means deformation after tectonic disturbance

PROJECT REFERENCE NO.	SHEET NO.
BR-0029	3
SITE PLAN	
 0 20 40 FEET	



17



-L- STA. 14+55.25 =
-DRWI- STA. 10+00.00

GR

15

SAND & COBBLES

RK

EB1-A

RK

EB2-A



-L-

EB1-B

MIDDLE CREEK

EB2-B

-DRWI-

BST

TEMP BENCH MARK


RK

SAND & COBBLES


RK

GR

*BM8 ~200' EAST
FROM EB2-B;
SPIKE IN POPLAR
RT OF ROAD




PROJECT REFERENCE NO.	SHEET NO.
BR-0029	4
REPLACE BRDG #550026 ON NC-106 OVER MIDDLE CREEK	



PROFILE ALONG -L-

19-JUL-2019 09:48
C:\PROJECTS\STRUCTURES\BR0029_GEO.BRDC0026_MACON\CADD_GEO\TECH\XSC\BR-0029_Geo_xp1.BRDC0026_MACON.dgn
\$\$\$\$\$USERNAME\$\$\$\$\$



A

ROADWAY EMBANKMENT: DARK GRAY/BLACK/WHITE, HARD,
SILTY-SANDY-GRAVEL w/ BOULDERS THROUGHOUT (AI)

EB1-A
14+95.5
5' LT

EB1-B
14+95.5
17' RT

EXISTING GROUND

60/0.1

C.R.: GNEISS

CRYSTALLINE ROCK: GRANITIC
to QUARTZ MONZOITIC GNEISS


13.7'
FIAD

13.3'
FIAD

B.T. @
15.5'
IN
CRYSTALLINE
ROCK


B.T. @
15.8'
IN
CRYSTALLINE
ROCK

15+00.00
-L-




CRYSTALLINE ROCK: GRANITIC
to QUARTZ MONZOITIC GNEISS

15 + 50.00



19-JUL-2018 09:51 C:\PROJECTS\STRUCTURES\BR0029_GEO\BRDC0026\MACON\CADD_GEO\TECH\ssc\BR-0029_Geo_xp1_BRDC0026_MACON.dgn \$\$\$USERNAME\$\$\$



- (A) ROADWAY EMBANKMENT: DARK GRAY/BLACK/WHITE, HARD, SILTY-SANDY-GRAVEL w/ BOULDERS THROUGHOUT (AI)
- (B) SAPROLITE: GRAY/ORANGE/BLACK, MED DENSE to DENSE, SILTY FINE to COURSE SAND, w/ trace MICA

EB2-A
16+21
12' LT

EB2-B
16+10
15' RT

EXISTING GROUND

ALLUVIAL (AI)

CRYSTALLINE ROCK: GNEISS


WEATHERED ROCK: GNEISS

CRYSTALLINE ROCK: GRANITIC to QUARTZ MONZOITIC GNEISS

B.T. @ 19.7' IN CRYSTALLINE ROCK

B.T. @ 40.5' IN CRYSTALLINE ROCK

16+00.00



GEOTECHNICAL BORING REPORT BORE LOG

GEOTECHNICAL BORING REPORT CORE LOG

WBS 67029.1.1		TIP BR-0029		COUNTY MACON		GEOLOGIST Elliott, D. C.									
SITE DESCRIPTION Replace Bridge #550026 on NC 106 (Dillard Rd) over Middle Creek							GROUND WTR (ft)								
BORING NO. EB1-A		STATION 14+96		OFFSET 5 ft LT		ALIGNMENT -L-									
COLLAR ELEV. 3,402.2 ft		TOTAL DEPTH 15.5 ft		NORTHING 486,202		EASTING 705,408									
DRILL RIG/HAMMER EFF./DATE AFO6744 CME - 45C 92% 07/31/2017			DRILL METHOD Core Boring			HAMMER TYPE Automatic									
DRILLER Cheek, D. O.		START DATE 06/26/19		COMP. DATE 06/26/19		SURFACE WATER DEPTH N/A									
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
3405															
3400														GROUND SURFACE	0.0
														ROADWAY EMBANKMENT SILTY-SANDY, GRAVELLY w/ BOULDERS THROUGHOUT	
3395														CRYSTALLINE ROCK GRANITIC to QUARTZ MONZONITIC (RABUN GNEISS)	6.0
3390															15.5
Boring Terminated at Elevation 3,386.7 ft IN CRYSTALLINE ROCK															
**NOTE: Due to medium-to-large boulders encountered in the embankment, this boring was completed using only NXWL (Wire-Line Core Barrel), thus no SPT Drives, to progress thru the embankment.															

NCDOT BORE DOUBLE BR0029 GEO_BRDG0026 MACON_BOREHOLES.GPJ NC_DOT.GDT 7/8/19

WBS 67029.1.1		TIP BR-0029		COUNTY MACON		GEOLOGIST Elliott, D. C.				
SITE DESCRIPTION Replace Bridge #550026 on NC 106 (Dillard Rd) over Middle Creek							GROUND WTR (ft)			
BORING NO. EB1-A		STATION 14+96		OFFSET 5 ft LT		ALIGNMENT -L-				
COLLAR ELEV. 3,402.2 ft		TOTAL DEPTH 15.5 ft		NORTHING 486,202		EASTING 705,408				
DRILL RIG/HAMMER EFF./DATE AFO6744 CME - 45C 92% 07/31/2017			DRILL METHOD Core Boring			HAMMER TYPE Automatic				
DRILLER Cheek, D. O.		START DATE 06/26/19		COMP. DATE 06/26/19		SURFACE WATER DEPTH N/A				
CORE SIZE NXWL		TOTAL RUN 15.5 ft		SAMP. NO.		STRATA		LOG	DESCRIPTION AND REMARKS	DEPTH (ft)
ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	REC. (ft) %	RQD (ft) %	REC. (ft) %			
3402.19	3,402.2	0.0	5.5	2:42/1.0 1:39/1.0 1:01/1.0 0:38/1.0 1:23/1.5	(0.0) 0%	(0.0) 0%			Ground Surface	
3400	3,396.7	5.5							ROADWAY EMBANKMENT	
3395	3,396.7	5.5	5.0	1:47/1.0 1:40/1.0 2:22/1.0 2:34/1.0 2:30/1.0	(4.2) 84%	(3.2) 64%			CRYSTALLINE ROCK	6.0
3390	3,391.7	10.5	5.0	2:20/1.0 2:31/1.0 2:14/1.0 2:18/1.0 2:27/1.0	(4.5) 90%	(3.6) 72%			GSI: 6.0' - 7.7' = 40-50 GSI: 7.7' - 15.5' = 55-65	
	3,386.7	15.5							Boring Terminated at Elevation 3,386.7 ft IN CRYSTALLINE ROCK	15.5
**NOTE: Due to medium-to-large boulders encountered in the embankment, this boring was completed using only NXWL (Wire-Line Core Barrel), thus no SPT Drives, to progress thru the embankment.										

NCDOT BORE DOUBLE BR0029 GEO_BRDG0026 MACON_BOREHOLES.GPJ NC_DOT.GDT 7/8/19

GEOTECHNICAL BORING REPORT BORE LOG

GEOTECHNICAL BORING REPORT CORE LOG

WBS 67029.1.1		TIP BR-0029		COUNTY MACON		GEOLOGIST Elliott, D. C.							
SITE DESCRIPTION Replace Bridge #550026 on NC 106 (Dillard Rd) over Middle Creek							GROUND WTR (ft)						
BORING NO. EB1-B		STATION 14+96		OFFSET 17 ft RT		ALIGNMENT -L-							
COLLAR ELEV. 3,403.1 ft		TOTAL DEPTH 15.8 ft		NORTHING 486,180		EASTING 705,406							
DRILL RIG/HAMMER EFF./DATE AFO6744 CME - 45C 92% 07/31/2017		DRILL METHOD NW Casing W/SPT & Core		HAMMER TYPE Automatic									
DRILLER Cheek, D. O.		START DATE 06/26/19		COMP. DATE 06/26/19		SURFACE WATER DEPTH N/A							
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100			
3405													
3400	3,398.1	5.0	60/0.0										3,403.1 GROUND SURFACE 3,402.7 ROADWAY EMBANKMENT ASPHALT into ABC below ROADWAY EMBANKMENT SANDY & GRAVELLY w/ BOULDERS THROUGHOUT 3,396.6 CRYSTALLINE ROCK GRANITIC to QUARTZ MONZONITIC (RABUN GNEISS) 3,387.3 Boring Terminated at Elevation 3,387.3 ft IN CRYSTALLINE ROCK **NOTE: V HARD BOULDER encountered @ 5.4'; begin CORING @ 5.4' to progress through embankment

WBS 67029.1.1		TIP BR-0029		COUNTY MACON		GEOLOGIST Elliott, D. C.					
SITE DESCRIPTION Replace Bridge #550026 on NC 106 (Dillard Rd) over Middle Creek							GROUND WTR (ft)				
BORING NO. EB1-B		STATION 14+96		OFFSET 17 ft RT		ALIGNMENT -L-					
COLLAR ELEV. 3,403.1 ft		TOTAL DEPTH 15.8 ft		NORTHING 486,180		EASTING 705,406					
DRILL RIG/HAMMER EFF./DATE AFO6744 CME - 45C 92% 07/31/2017		DRILL METHOD NW Casing W/SPT & Core		HAMMER TYPE Automatic							
DRILLER Cheek, D. O.		START DATE 06/26/19		COMP. DATE 06/26/19		SURFACE WATER DEPTH N/A					
CORE SIZE NXWL			TOTAL RUN 10.4 ft								
ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN REC. (ft) %	RQD (ft) %	SAMP. NO.	STRATA REC. (ft) %	RQD (ft) %	LOG	DESCRIPTION AND REMARKS
3397.65	3,397.7	5.4	5.4	2:52/1.0	(5.3) 98%	(4.8) 89%					Begin Coring @ 5.4 ft
3395				2:40/1.0							ROADWAY EMBANKMENT (continued)
	3,392.3	10.8		2:27/1.0							CRYSTALLINE ROCK
				2:31/1.0							GSI: 6.5' - 11.6' = 65-75
				2:12/1.4							GSI: 11.6' - 15.1' = 85-95
3390			5.0	1:01/0.4	(5.0) 100%	(4.7) 94%					
	3,387.3	15.8		2:21/1.0							Boring Terminated at Elevation 3,387.3 ft IN CRYSTALLINE ROCK
				2:17/1.0							**NOTE: V HARD BOULDER encountered @ 5.4'; begin CORING @ 5.4' to progress through embankment
				2:10/1.0							**Crystalline Rock @ 6.5' after encountering embnk boulders above
				2:12/1.0							
				2:24/1.0							

GEOTECHNICAL BORING REPORT

BORE LOG

WBS 67029.1.1		TIP BR-0029		COUNTY MACON		GEOLOGIST Elliott, D. C.										
SITE DESCRIPTION Replace Bridge #550026 on NC 106 (Dillard Rd) over Middle Creek							GROUND WTR (ft)									
BORING NO. EB2-A		STATION 16+21		OFFSET 12 ft LT		ALIGNMENT -L-										
COLLAR ELEV. 3,399.0 ft		TOTAL DEPTH 19.7 ft		NORTHING 486,197		EASTING 705,533										
DRILL RIG/HAMMER EFF./DATE AFO6744 CME - 45C 92% 07/31/2017				DRILL METHOD NW Casing W/SPT & Core		HAMMER TYPE Automatic										
DRILLER Cheek, D. O.		START DATE 06/26/19		COMP. DATE 06/26/19		SURFACE WATER DEPTH N/A										
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION			
			0.5ft	0.5ft	0.5ft	0	25	50	75	100			ELEV. (ft)	DEPTH (ft)		
3400														3,399.0	0.0	GROUND SURFACE
														3,397.0	2.0	ARTIFICIAL FILL BROWN, SANDY-SILT, PREVIOUSLY DISTURBED TOPSOIL
3395	3,394.3	4.7											M			SAPROLITE GRAY/ORANGE/TAN/BLACK, MED DENSE to DENSE, SILTY FINE-to-COURSE SAND, w/ trace MICA
3390	3,389.3	9.7	3	5	5								M			
3385	3,384.3	14.7	11	19	33									3,386.9	12.1	WEATHERED ROCK DARK GRAY/BLACK/WHITE w/ MICA
3380	3,379.3	19.7	60/0.0											3,384.9	14.1	CRYSTALLINE ROCK GRANITIC to QUARTZ MONZONITIC (RABUN GNEISS) *some W.R. seams this run
			60/0.1											3,379.3	19.7	Boring Terminated at Elevation 3,379.3 ft IN CRYSTALLINE ROCK

NCDOT BORE DOUBLE BR0029 GEO_BRD50026 MACON_BOREHOLES.GPJ NC_DOT.GDT 7/8/19

GEOTECHNICAL BORING REPORT CORE LOG

WBS 67029.1.1		TIP BR-0029		COUNTY MACON		GEOLOGIST Elliott, D. C.									
SITE DESCRIPTION Replace Bridge #550026 on NC 106 (Dillard Rd) over Middle Creek							GROUND WTR (ft)								
BORING NO. EB2-B		STATION 16+10		OFFSET 15 ft RT		ALIGNMENT -L-									
COLLAR ELEV. 3,406.5 ft		TOTAL DEPTH 40.5 ft		NORTHING 486,176		EASTING 705,521									
DRILL RIG/HAMMER EFF/DATE AFO6744 CME - 45C 92% 07/31/2017				DRILL METHOD Core Boring		HAMMER TYPE Automatic									
DRILLER Cheek, D. O.		START DATE 06/26/19		COMP. DATE 06/26/19		SURFACE WATER DEPTH N/A									
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
3410															
3405															GROUND SURFACE ROADWAY EMBANKMENT ASPHALT into ABC below ROADWAY EMBANKMENT SILTY-SANDY, GRAVELLY w/ BOULDERS THROUGHOUT
3400															
3395															
3390															
3385															
3380															WEATHERED ROCK GNEISS: heavily weathered & stained, joint in-fill throughout
3375															
3370															CRYSTALLINE ROCK GRANITIC to QUARTZ MONZONITIC (RABUN GNEISS)
															Boring Terminated at Elevation 3,366.0 ft IN CRYSTALLINE ROCK **NOTE: Due to medium-to-large boulders encountered in the embankment, this boring was completed using only NXWL (Wire-Line Core Barrel), thus no SPT Drives, to progress thru the embankment.


GEOTECHNICAL BORING REPORT CORE LOG

WBS 67029.1.1		TIP BR-0029		COUNTY MACON		GEOLOGIST Elliott, D. C.					
SITE DESCRIPTION Replace Bridge #550026 on NC 106 (Dillard Rd) over Middle Creek							GROUND WTR (ft)				
BORING NO. EB2-B		STATION 16+10		OFFSET 15 ft RT		ALIGNMENT -L-					
COLLAR ELEV. 3,406.5 ft		TOTAL DEPTH 40.5 ft		NORTHING 486,176		EASTING 705,521					
DRILL RIG/HAMMER EFF/DATE AFO6744 CME - 45C 92% 07/31/2017				DRILL METHOD Core Boring		HAMMER TYPE Automatic					
DRILLER Cheek, D. O.		START DATE 06/26/19		COMP. DATE 06/26/19		SURFACE WATER DEPTH N/A					
CORE SIZE NXWL		TOTAL RUN 40.5 ft		DESCRIPTION AND REMARKS							
ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN REC. (ft) %	RQD (ft) %	SAMP. NO.	STRATA REC. (ft) %	RQD (ft) %	LOG	
3406.47											Continued from previous page
3405	3,406.5	0.0	10.5	0:00/30.5	(1.8) 17%	(1.4) 13%					ROADWAY EMBANKMENT ROADWAY EMBANKMENT
3400											
3395	3,396.0	10.5	5.0		(0.0) 0%	(0.0) 0%					
3390	3,391.0	15.5	5.0		(0.0) 0%	(0.0) 0%					
3385	3,386.0	20.5	5.0		(1.0) 20%	(0.0) 0%					
3380	3,381.0	25.5	5.0		(1.1) 22%	@ 24.5' / (0.0) 0% W.R.					WEATHERED ROCK SEAMS OF WEATHERED AND FRESH ROCK GSI: 24.5 - 33.1' = 10-25
3375	3,376.0	30.5	5.0		1:19/1.0 (3.8) 76%	1:31/1.0 (1.3) 26%					
3370	3,371.0	35.5	5.0		1:44/1.0 @ 33.1'	2:19/1.0 @ 33.1'					CRYSTALLINE ROCK GSI: 33.1' - 35.5' : 40-50 GSI: 35.5 - 40.5' : 75-85
	3,366.0	40.5			2:28/1.0 (5.0) 100%	(4.2) 84%					Boring Terminated at Elevation 3,366.0 ft IN CRYSTALLINE ROCK **NOTE: Due to medium-to-large boulders encountered in the embankment, this boring was completed using only NXWL (Wire-Line Core Barrel), thus no SPT Drives, to progress thru the embankment.

CORE PHOTOGRAPHS

EB1-A

BOX 1 of 1 : 5.5 - 15.5 FEET




GEOLOGICAL STRENGTH INDEX: GSI

0.0' - 6.0' : N/A : no significant return; embnk materials, w/ boulders
 6.0' - 7.7' : 40-50
 7.7' - 15.5' : 55-65

EB1-B

BOX 1 of 2 : 5.4 - 15.1 FEET




GEOLOGICAL STRENGTH INDEX: GSI

5.4' - 6.5' : N/A : embnk materials, w/ boulders
 6.5' - 11.6' : 65-75
 11.6' - 15.1' : 85-95

CORE PHOTOGRAPHS

EB1-B

BOX 2 of 2 : 15.1 - 15.8 FEET




GEOLOGICAL STRENGTH INDEX: GSI
15.1' - 15.8' : 85-95

CORE PHOTOGRAPHS

EB2-B


BOX 1 of 2 : 0.0 - 35.5 FEET



GEOLOGICAL STRENGTH INDEX: GSI
0.0' - 24.5' : N/A : embnk materials, w/ boulders
24.5' - 33.1' : 10-25
33.1' - 35.5' : 40-50

EB2-B

BOX 2 of 2 : 35.5 - 40.5 FEET



GEOLOGICAL STRENGTH INDEX: GSI
35.5' - 40.5' : 75-85