PROJ. REFERENCE NO.	SHEET NO.
I-5973	X-1A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

Approximate quantities only. Clearing and grubbing, unclassified excavation,borrow excavation, fine grading, and removal of existing asphalt

CROSS-SECTION SUMMARY

Station	Uncl. Exc.	Embt	Station	Uncl. Exc.	Embt	Station	Uncl. Exc.	Embt	Station	Uncl. Exc.	Embt	Station	Uncl. Exc.	Embt	Station	Uncl. Exc.	Embt
L (LT)	(cu. yd.)	(cu. yd.)	L (LT)	(cu. yd.)	(cu. yd.)	L (RT)	(cu. yd.)	(cu. yd.)	LRPA	(cu. yd.)	(cu. yd.)	LRPB	(cu. yd.)	(cu. yd.)	LRPC	(cu. yd.)	(cu. yd.)
18+82.35	0	0	39+00	26	6	12+00	0	0	15+95	0	0	14+56	0	0	16+60	0	0
19+00	2	0	39+50	26	4	12+50	19	0	16+00	4	0	15+00	13	0	17+00	8	1
19+50	14	1	40+00	29	3	13+00	19	0	16+50	38	41	15+50	12	1	17+50	8	3
20+00	18	3	40+50	32	2	13+50	21	0	17+00	34	129	16+00	10	7	18+00	5	6
20+50	18	6	41+00	41	0	14+00	34	8	17+50	35	210	16+50	8	21	18+50	4	8
21+00	15	20	41+50	51	3	14+50	35	54	18+00	34	262	17+00	5	52	19+00	5	10
21+50	14	40	42+00	52	7	15+00	24	134	18+50	34	283	17+50	3	71	19+50	6	18
22+00	15	54	42+50	50	4	15+50	21	196	19+00	30	280	18+00	5	76	20+00	6	30
22+50	17	43	43+00	45	2	16+00	21	142	19+50	33	264	18+50	13	87	20+50	7	30
23+00	23	38	43+50	38	2	16+50	21	86	20+00	35	244	19+00	21	98	21+00	6	50
23+50	38	25	44+00	37	0	17+00	18	137	20+50	28	222	19+50	22	97	21+50	4	89
24+00	67	0	44+50	30	0	17+45	18	116	21+00	28	193	20+00	26	52	22+00	10	107
24+50	99	0	45+00	11	0	17+50	3	9	21+50	33	166	20+50	45	11	22+50	18	103
25+00	108	0				18+00	26	70	22+00	37	110	21+00	79	5	23+00	19	79
25+50	104	0				18+50	25	53	22+50	37	45	21+50	102	2	23+50	23	49
26+00	102	0				19+00	26	45	23+00	41	12	22+00	118	2	24+00	35	17
26+50	102	0				19+50	27	41	23+50	77	9	22+50	146	1	24+50	41	36
26+85	71	0				20+00	28	67	24+00	102	12	23+00	155	0	25+00	32	40
27+00	28	0				20+50	28	99	24+50	82	9	23+50	154	0	25+50	26	7
27+50	70	6				21+00	25	94	25+00	66	24	24+00	152	1	26+00	28	10
28+00	61	7				21+50	22	66	25+50	66	32	24+50	114	6	26+50	27	13
28+50	73	1				22+00	21	35	26+00	79	32	25+00	60	16	27+00	27	12
29+00	80	2				22+50	42	36	26+50	62	32	25+50	34	22	27+50	28	32
29+50	77	4				23+00	190	24	27+00	36	24	26+00	31	22	28+00	21	33
30+00	78	3				23+50	158	0	27+50	36	19	26+50	36	14	28+50	13	23
30+50	88	2				24+00	9	0	28+00	31	9	27+00	203	10	29+00	12	25
31+00	85	2				24+50	51	0	28+38.74	11	0	27+50	643	12	29+50	11	10
31+50	79	2				25+00	86	1				27+87.94	570	5	29+74.69	2	0
32+00	88	0				25+50	72	1									
32+50	78	0				26+00	43	1									
33+00	68	0				26+50	26	0									
33+50	78	0				26+85	8	0									
34+00	91	0															
34+50	113	0													LLPA	(cu. yd.)	(cu. yd.)
35+00	116	0													17+81.45	0	0
35+50	74	0													18+00	2	0
36+00	21	0													18+50	6	0
36+50	10	2													19+00	6	0
37+00	25	3													19+50	6	0
37+50	26	7													20+00	6	0
38+00	24	10													20+47.93	6	0
38+50	25	8															