PROJECT REFERENCE NO. U-5724 LEGEND X - FUSION SPLICE INDIVIDUAL FIBER EXISTING SPLICE EXPRESS ENTIRE BUFFER TUBE SPLICE ENTIRE BUFFER TUBE OR MAINTAIN IF EXISTING EXPRESSED CONTRACTOR IS RESPONSIBLE FOR FIELD VERIFYING EXISTING SPLICING. THE CONTRACTOR SHALL COORDINATE WITH THE ENGINEER WHERE EXISTING SPLICING IS NOT AS EXPECTED. DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED SEAL U-5724 SPLICE DETAIL 030472 WAYNE COUNTY REVIEWED BY:

NEW UNDERGROUND SPLICE ENCLOSURE COLOR CODE TIA/EIA 598–C AT US-13 (BERKELY BOULEVARD) AND ROYALL AVENUE /CENTRAL HEIGHTS ROAD SIGNAL ID # 04-0556 (2) ORANGE (8) BLACK (9) YELLOW (3) GREEN (4) BROWN (10) VIOLET NEW DROP CABLE TO CCTV-12 DROF ILE TO -0556 (11) ROSE (5) SLATE (6) WHITE (12) AQUA BLUE GREEN BROWN SLATE WHITE WHITE GREEN BROWN SLATE CAP AND SEAL CAP AND CAP AND  $\stackrel{ extstyle imes}{\sim}$  CAP AND BLUE ORANGE BLUE ORANGE GREEN GREEN BROWN BROWN SLATE WHITE RED WHITE RED BLACK YELLOW ROSE AQUA NEW NCDOT EXISTING NCDOT CAP AND — SEAL 24-SMFO CABLE TO 24–SMFO CABLE TO NEW SPLICE ENCLOSURE SPLICE ENCLOSURE AT SPLICE AT BERKELEY BLVD. AND 04–1173 SERVICE RD. 24 FIBERS IN 2 BUFFER TUBES 24 FIBERS IN 2 BUFFER TUBES SIGNAL CABINET 04–0556 **CCTV CABINET** SPLICE TRAY -DATA PORT **TRANSCEIVER** TRANSCEIVER -CAP AND -CAP AND SEAL SEAL **NOTES:** 1) NOTIFY THE CITY OF GOLDSBORO TRAFFIC ENGINEER, BOBBY CROOM, AT 919-580-4278 FIVE (5) DAYS PRIOR TO BEGINNING WORK ON SIGNAL SYSTEM COMMUNICATIONS CABLE. NOTIFY THE CITY TRAFFIC ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL FIBER CIRCUITS ARE FUNCTIONING PROPERLY. ALL WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS BACK UP AND OPERATIONAL. 2) CONTRACTOR TO RECORD EXISTING SPLICE ARRANGEMENT FOR COMPARISON TO THE SUPPLIED SPLICE DETAILS. IF DISCREPANCIES EXIST, CONTACT THE ENGINEER TO DETERMINE HOW TO PROCEED WITH RESPLICING. PROVIDE AS-BUILT PLANS TO THE ENGINEER IF FINAL SPLICE ARRANGEMENT DIFFERS FROM THE SUPPLIED SPLICE DETAILS.

3) TRANSCEIVER TERMINATION CONFIGURATIONS ARE GENERIC. CONTRACTOR IS RESPONSIBLE

PRIOR TO INSTALLING THE COVER ON THE SPLICE TRAY TAKE A DIGITAL PHOTOGRAPH

SHOWING THE SPLICE TRAY AND INFORMATION SHOWN ABOVE (1-4) AND SUBMIT PHOTOGRAPH ALONG WITH OTDR TEST RESULTS.

FOR DETERMINING \ ENSURING PROPER TERMINATIONS.

4) NAME OF INDIVIDUAL PERFORMING THE SPLICING

1) SPLICE LOCATION

3) COMPANY NAME

2) DATE

4) INCLUDE ON THE COVER OF EACH SPLICE TRAY THE FOLLOWING: REFERENCE SECTION 1731 "FIBER OPTIC SPLICE ENCLOSURE"

DIVISION 04 OCT 2019 PLAN DATE: J. CROSS REVIEWED BY: K. SMITH

kevin Smith 6/30/2020 CADD Filename:

Kimley» Horn

750 N. Greenfield Pkwy., Garner, NC 27529

NC License #F-0102 421 Fayetteville St., Suite 600

Raleigh, NC 27636 Tel: (919) 677-2000 Fax: (919) 677-2050

PREPARED BY: REVISIONS

INIT. DATE