PROJ. REFERENCE NO.	SHEET NO.
U-5724	X-1A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station	Uncl. Exc.	Embt
L (LT)	(cu. yd.)	(cu. yd.)
13+50.00	0	0
14+00.00	10	30
14+50.00	9	11
15+00.00	41	28
15+50.00	42	39
16+00.00	8	43
16+50.00	5	38
17+00.00	2	36
17+50.00	2	33
18+00.00	2	47
18+50.00	4	63
19+00.00	7	39
19+20.00	3	7
19+50.00	3	26
20+00.00	2	75
20+50.00	3	83
21+00.00	3	75
21+50.00	2	49
22+00.00	1	45
22+50.00	4	36
23+00.00	8	19
23+50.00	10	18
24+00.00	11	15
24+50.00	11	11
25+00.00	6	15
25+50.00	2	27
26+00.00	5	30
26+50.00	0	0
44+00.00	0	0
44+50.00	33	100
45+00.00	18	117
45+50.00	14	100
46+00.00	26	71
46+50.00	21	65
47+00.00	21	52
47+50.00	25	55
48+00.00	30	51
48+50.00	32	54
49+00.00	30	63
49+50.00	34	69
50+00.00	39	77
50+50.00	44	86
51+00.00	51	89
51+50.00	28	96
52+00.00	0	66
52+50.00	0	26
53+00.00	0	28
53+50.00	12	34
54+00.00	26	28
54+50.00	26	13
55+00.00	28	7

Station	Uncl. Exc.	Embt
L (LT)	(cu. yd.)	(cu. yd.)
55+00.00	30	4
56+00.00	25	3
56+50.00	22	2
57+00.00	21	1
57+50.00	13	0
58+00.00	4	0

Station	Uncl. Exc.	Embt
L (RT)	(cu. yd.)	(cu. yd.)
13+50.00	0	0
14+00.00	28	5
14+50.00	27	5
15+00.00	36	4
15+50.00	37	4
16+00.00	33	5
16+50.00	36	7
17+00.00	31	9
17+50.00	31	9
18+00.00	46	7
18+50.00	52	7
19+00.00	50	6
19+20.00	11	2
19+50.00	19	2
20+00.00	64	4
20+50.00	71	4
21+00.00	72	5
21+50.00	67	6
22+00.00	66	6
22+50.00	65	6
23+00.00	64	5
23+50.00	65	3
24+00.00	65	2
24+50.00	62	2
25+00.00	56	3
25+50.00	55	5
44+00.00	0	0
44+50.00	18	136
45+00.00	24	125
45+50.00	24	104
46+00.00	22	80
46+50.00	11	46
47+00.00	16	18
47+50.00	31	19
48+00.00	24	26
48+50.00	10	17
49+00.00	6	24
49+50.00	17	32
50+00.00	16	42
50+50.00	6	42
51+00.00	6	44

Station	Uncl. Exc.	Embt
L	(cu. yd.)	(cu. yd.)
51+50.00	3	46
52+00.00	0	32
53+00.00	0	91
53+50.00	11	50
54+00.00	31	20
54+50.00	32	1
55+00.00	22	2
55+50.00	25	1
56+00.00	21	0
56+50.00	13	0
57+00.00	11	0
57+50.00	11	0
58+00.00	6	1

Station	Uncl. Exc.	Embt
L	(cu. yd.)	(cu. yd.)
27+50.00	0	0
28+00.00	158	22
28+50.00	242	0
29+00.00	186	2
29+50.00	88	62
30+00.00	42	170
30+50.00	35	296
31+00.00	38	408
31+50.00	39	506
32+00.00	39	546
32+50.00	38	523
33+00.00	39	521
33+50.00	37	504
34+00.00	36	483
34+50.00	35	455
35+00.00	35	425
35+50.00	32	417
36+00.00	35	415
36+50.00	39	412
37+00.00	34	427
37+50.00	26	455
38+00.00	19	485
38+50.00	18	509
39+00.00	16	544
39+50.00	13	563
40+00.00	10	581
40+50.00	13	605
41+00.00	35	583
41+50.00	47	527
42+00.00	34	369
42+50.00	26	270
43+00.00	22	256
43+50.00	18	244

Station	Uncl. Exc.	Embt
Y1 (LT)	(cu. yd.)	(cu. yd.)
18+63.46	0	0
19+00.00	12	6
19+50.00	35	3
20+00.00	50	0
20+50.00	53	0
21+00.00	44	0
21+50.00	30	2
22+00.00	15	3
22+45.00	0	0

Station	Uncl. Exc.	Embt
Y1 (RT)	(cu. yd.)	(cu. yd.)
24+61.00	0	0
25+00.00	5	5
25+28.00	3	7
27+36.00	0	0
27+50.00	6	0
28+00.00	17	0
28+21.00	0	0

Station	Uncl. Exc.	Embt
Y2 (LT)	(cu. yd.)	(cu. yd.)
10+28.99	0	0
10+50.00	6	11
11+00.00	5	35
11+42.00	4	29
11+50.00	1	5
12+00.00	3	54
12+27.00	1	46
12+50.00	0	45
13+00.00	8	94
13+50.00	20	68
13+66.00	4	18
14+00.00	11	35
14+50.00	33	46
15+00.00	38	47
15+50.00	42	49
16+00.00	49	51
16+30.00	16	40
16+50.00	11	27
17+00.00	60	53
17+50.00	65	50
18+00.00	67	48
18+50.00	62	54
19+00.00	54	68
19+50.00	54	81
20+00.00	44	124
20+50.00	42	134
21+00.00	31	131

Station	Uncl. Exc.	Embt
Y2 (LT)	(cu. yd.)	(cu. yd.)
21+50.00	3	127
22+00.00	23	99
22+50.00	52	99
23+00.00	63	97
23+50.00	40	52
24+00.00	13	49
24+50.00	12	86
25+00.00	11	80
25+50.00	10	82
26+00.00	8	86
26+50.00	6	90
27+00.00	6	90
27+50.00	7	102
28+00.00	3	136
28+36.00	0	94
28+50.00	0	34
28+91.00	0	98

Station	Uncl. Exc.	Embt
Y2 (RT)	(cu. yd.)	(cu. yd.)
10+28.99	0	0
10+50.00	6	6
11+00.00	11	36
11+42.00	11	38
11+50.00	2	7
12+00.00	14	39
12+27.00	6	20
12+50.00	4	16
13+00.00	8	32
13+50.00	4	38
14+00.00	10	21
14+50.00	10	38
15+00.00	10	43
15+50.00	13	47
16+00.00	15	53
16+50.00	4	23
17+00.00	24	53
17+50.00	28	45
18+00.00	32	39
18+50.00	29	40
19+00.00	22	50
19+50.00	14	63
20+00.00	10	49
20+50.00	7	39
21+00.00	2	50
21+50.00	0	50
22+00.00	75	77
22+50.00	163	100
23+00.00	184	92
23+50.00	200	87
24+00.00	209	85

Station	Uncl. Exc.	Embt
Y2 (RT)	(cu. yd.)	(cu. yd.)
24+50.00	180	88
25+00.00	150	90
25+50.00	161	90
26+00.00	169	99
26+50.00	163	52
27+00.00	163	77
27+50.00	157	163
28+00.00	140	183
28+50.00	67	314
28+60.00	0	57
28+91.00	0	85

Station	Uncl. Exc.	Embt
Y2	(cu. yd.)	(cu. yd.)
28+91.00	0	0
29+00.00	3	54
29+50.00	16	498
30+00.00	30	553
30+50.00	54	443
31+00.00	36	368
31+50.00	23	279
32+00.00	17	210
32+50.00	17	138
33+00.00	23	86
33+50.00	21	78
34+00.00	10	114
34+50.00	7	170
35+00.00	5	187
35+50.00	45	206
36+00.00	99	169
36+50.00	115	78
37+00.00	140	44
37+50.00	160	39
38+00.00	167	49
38+50.00	168	53
38+70.00	33	21
39+00.00	51	30
39+50.00	170	44
40+00.00	189	36
40+50.00	217	27
41+00.00	234	20
41+50.00	242	19
41+90.00	114	24
42+00.00	29	8
42+50.00	232	68
43+00.00	230	125
43+50.00	252	178
44+00.00	250	267
44+50.00	188	349
45+00.00	119	366
45+50.00	49	401