PROJECT NO.	SHEET NO.	TOTAL NO.
2023CPT.12.03.10231, 2023CPT.12.03.20231	8	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	1260000000-E AGGREGATE SHOULDER BORROW	1220000000-E INCIDENTAL STONE BASE	1245000000-E SHOULDER RECONSTRUCTION	1297000000-E 1½" MILLING	1330000000-E INCIDENTAL MILLING	1523000000-E SURFACE COURSE, S9.5C	1524000000-E LEVELING COURSE, S9.5C	1575000000-E ASPHALT BINDER FOR PLANT MIX	1704000000-E PATCHING EXISTING PAVEMENT	1840000000-E MILLED RUMBLE STRIPS	2815000000-N ADJ. OF DROP INLET	2830000000-N ADJ. OF MANHOLES	2845000000-N ADJ. OF METER OR VALVE BOX	2374000000-N FRAME W/ GRATE 840.03	2920000000-N CONVERT EXISTING DROP INLET TO CATCH	4600000000-N SINGLE LANE CLOSURE	4600000000-N RAMP / LOOP CLOSURE	5255000000-N PORTABLE LIGHTING	7324000000-N JUNCTION BOX (STANDARD SIZE)	7444000000-E INDUCTIVE LOOP SAWCUT	7456000000-E LEAD-IN CABLE (14-2)
										MI	FT	TON	TONS	SMI	SY	SY	TONS	TONS	TONS	TONS	LF	EA	EA	EA	EA	EA	EA	EA	LS	EA	LF	LF
2023CPT.12.03.10231	Cleveland	1	US-74 (ANDREW JACKSON HWY.)	N. CANSLER ST. TO GASTON COUNTY LINE	10	2	MD	NO	NO	1.43	VAR. 56-78	1,001	125	5.72		2,489	5,687	380	420	1,136	30,200						8					
TOTAL FOR MAP NO. 1										**1.43**		**1,001**	**125**	**5.72**		**2,489**	**5,687**	**380**	**420**	**1,136**	**30,200**						**8**					
2023CPT.12.03.10231	Cleveland	2	US-74 (ASSOCIATED RAMPS)	US-74 (ASSOCIATED RAMPS)	1 4 9	1		NO	NO	1.84 0.03 0.02	VAR. 16-18 VAR. 16-72 VAR. 38-72	1,323	402	7.36	2,111	380	1,990	100	139	280								4				
TOTAL FOR MAP NO. 2										**1.89**		**1,323**	**402**	**7.36**	**2,111**	**380**	**1,990**	**100**	**139**	**280**								**4**				
2023CPT.12.03.10231	Cleveland	3	NC-150 (COLLEGE AVE.)	NC-18 TO SR-1003 (W. COLLEGE AVE.)	1 5 6 7	2 2 2 3	2WU	NO	NO	5.77 0.20 0.06 0.07	VAR. 25-39 VAR. 36-37 VAR. 36-37 VAR. 36-43	2,065	292	11.77	8,038	2,398	8,933	625	692	2,412		2	17	5	1.00	1			*	1	800	180
TOTAL FOR MAP NO. 3										**6.1**		**2,065**	**292**	**11.77**	**8,038**	**2,398**	**8,933**	**625**	**692**	**2,412**		**2**	**17**	**5**	**1.00**	**1**				**1**	**800**	**180**
2023CPT.12.03.10231	Cleveland	4	NC-226 (POLKVILLE RD)	US-74 TO NC-182 (EXCEPTING US-74 BYPASS PROJ LIMIT [0.62 MI], AND EXCEPTING FROM BEGIN SAFETY FRICTION COURSE TO SR-1809 DOUBLE SHOALS RD.[2.82 MI])	1 2 3 4 6 8	2 2 VAR. VAR. 3 VAR.	2WU	NO	NO	6.07 0.09 0.07 0.45 0.43 0.31	VAR. 23-37 VAR. 24-27 VAR. 26-37 VAR. 24-48 VAR. 40-41 VAR. 24-41	2,146	314	12.30	31,583	2,563	10,445	846	781	2,067										1	1,110	460
TOTAL FOR MAP NO. 4										**7.11**		**2,146**	**314**	**12.30**	**31,583**	**2,563**	**10,445**	**846**	**781**	**2,067**										**1**	**1,110**	**460**
TOTAL FOR PROJ NO. 2023CPT.12.03.10231										**16.53**		**6,535**	**1,133**	**37.15**	**41,732**	**7,830**	**27,055**	**1,951**	**2,032**	**5,895**	**30,200**	**2**	**17**	**5**	**1.00**	**1**	**8**	**4**	**1.00**	**2**	**1,910**	**640**
2023CPT.12.03.20231	Cleveland	5	SR-1001 (STONY POINT RD.)	370' N OF SR-2044 (NEW CAMP CREEK RD) TO SR-2033 (OAK GROVE RD)	1 3 2	2	2WU	NO	NO	1.42 0.11 0.01	VAR. 28-38 VAR. 28-29 VAR. 26-27	518	93	2.96	2,233	1,123	2,500	294	203	702											190	80
TOTAL FOR MAP NO. 5										**1.54**		**518**	**93**	**2.96**	**2,233**	**1,123**	**2,500**	**294**	**203**	**702**											**190**	**80**
TOTAL FOR PROJ NO. 2023CPT.12.03.20231										**1.54**		**518**	**93**	**2.96**	**2,233**	**1,123**	**2,500**	**294**	**203**	**702**											**190**	**80**
GRAND TOTAL										**18.07**		**7,053**	**1,226**	**40.11**	**43,965**	**8,953**	**29,555**	**2,245**	**2,235**	**6,597**	**30,200**	**2**	**17**	**5**	**1.00**	**1**	**8**	**4**	**1.00**	**2**	**2,100**	**720**