DocuSign Envelope ID: 85B90AE4-8378-45B8-8A10-64577ACC77C4

COMPUTED BY: SGM DATE: 7/8/2022 CHECKED BY: JLT DATE: 7/8/2022 PROJECT NO. SHEET NO.
A-0009CC 3B-1

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS

PAVEMENT REMOVAL SUMMARY

IN SQUARE YARDS

SURVEY LINE	Station	Station	LOCATION LT/RT/CL	ASPHALT REMOVAL	ASPHALT BREAKUP	CONCRETE REMOVAL	CONCRETE BREAKUP
-L-	414+50	455+73	RT	3,717.65			
-L-	456+92	464+09	LT	666.76			
-L-	466+27	471+30	RT	565.69			
-L-	471+91	474+10	LT	315.82			
-L-	472+90	474+17	RT	102.54			
-Y2-	13+98	19+12	RT	136.85			
-Y2-	23+94	27+40	RT	252.12			
-Y2-	29+10	47+10	LT	3,419.84			
-Y2-	49+45	57+75	RT	805.97			
-Y2-	58+22	65+11	RT	649.30			
-Y2-	66+31	66+98	LT	46.76			
-Y2-	67+52	72+85	LT	501.34			
-Y2-	75+08	84+60	RT	980.65			
-Y2-	86+67	88+55	LT	39.59			
		TOTAL:		12,200.88			
		SAY:		12,210			

SUMMARY OF EARTHWORK

IN CUBIC YARDS

Station	Station	Uncl. Excav.	Undercut	Embank. +%	Borrow	Waste
. 444.50.00	1 444.50.00	22.650		4.405		24 5 45
-L- 414+50.00 -L- 444+50.00		22,650	5.00	1,105		21,545
Retaining Wall # 27		4.055	560			560
-DR3- 10+20.00	-DR3- 11+72.03	4,055	560	4.405		4,055
3061	UTAL 1	26,705	560	1,105		26,160
-L- 444+50.00	-L- 474+19.52	13,476		2,208		11,268
	TOTAL 2	13,476		2,208		11,268
	O I A L L	13,470		2,200		11,200
-Y2-12+60.00	-Y2- 40+00.00	90,331		23,786		66,545
Retaining Wall # 30		55,532	2,850			2,850
SUBT	90,331	2,850	23,786		69,395	
			,	,		,
-Y2- 40+00.00	-Y2- 70+00.00	24,372		62,375	38,003	
Retainin	,-	8,150	- /		8,150	
-DR4- 10+12.13	DR4- 11+10.00	57		3,950	3,893	
SUBT	24,429	8,150	66,325	41,896	8,150	
-Y2- 70+00.00	-Y2- 90+00.00	11,189		5,920		5,269
SUBT	11,189		5,920		5,269	
TOTAL		166,130	11,560	99,344	41,896	120,242
JNSUITABLE WASTE (PER G	0				0	
OSS DUE TO CLEARING & C	-7,000				-7,000	
ADDITIONAL UNDERCUT (PI		2,300			2,300	
ADDITIONAL UNDERCUT (PI		3,150			3,150	
HARD ROCK WASTE TO REP				-3,290	-3,290	
ADJUST ROCK SWELL			-823	-823		
ELIMINATE EARTH SHRINKA			-5,465	-5,465		
EARTH WASTE TO REPLACE	BORROW				-32,318	-32,318
GRAND	TOTALS:	159,130	17,010	93,056	0	83,084
S	AY	161,000	17,010			

Note: Earthwork quantities are calculated by TGS Engineers. These earthwork quantities are based in part on subsurface data provided by the Geotechnical Engineering Unit.

EST. DDE = 1,870 CUBIC YARDS

SELECT GRANULAR MATERIAL, CLASS III = 6,670 CY

EST. SHALLOW UNDERCUT = 1,200 CY

PER GEOTECH RECOMMENDATION, ESTIMATED 22,600 CUBIC YARDS OF UNDERCUT FOR TOE SHEAR KEY.

PAVEMENT STRUCTURE VOLUME = 4,150 CY

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when

the project is staked out. These cross-section notes will be used in computing the final quantities

for which the contractor will be paid.