

PROJECT: 32572.1.FS10 REFERENCE: A-0009CC

CONTENTS

<u>SHEET NO.</u>	<u>DESCRIPTION</u>
1	TITLE SHEET
2	LEGEND (SOIL & ROCK)
3	SITE PLAN
4-5	WALL ENVELOPE
6-16	CROSS SECTIONS
17-19	BORE LOGS
20-23	GEOPHYSICAL TEST RESULTS

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT

STRUCTURE
SUBSURFACE INVESTIGATION

COUNTY GRAHAM
PROJECT DESCRIPTION UPGRADE NC 143 FROM 0.5
MILES NORTH OF APPALACHIAN TRAIL TO NC 28
AND UPGRADE NC 28 FROM 0.2 MILES WEST OF
NC 143 TO 0.3 MILES EAST OF SR 1235 (GUNTERS
GAP RD)
SITE DESCRIPTION RETAINING WALL #23:
SOIL NAIL WALL WITH ARCHITECTURAL FORM
LINER FINISH ON -L- FROM 448+40 TO 452+25,
LT & RETAINING WALL #24:
SOIL NAIL WALL WITH ARCHITECTURAL FORM
LINER FINISH ON -L- FROM 453+25 TO 456+25,
LT

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	A-0009CC	1	23

CAUTION NOTICE

THE SUBSURFACE INFORMATION AND THE SUBSURFACE INVESTIGATION ON WHICH IT IS BASED WERE MADE FOR THE PURPOSE OF STUDY, PLANNING AND DESIGN, AND NOT FOR CONSTRUCTION OR PAY PURPOSES. THE VARIOUS FIELD BORING LOGS, ROCK CORES AND SOIL TEST DATA AVAILABLE MAY BE REVIEWED OR INSPECTED IN RALEIGH BY CONTACTING THE N. C. DEPARTMENT OF TRANSPORTATION, GEOTECHNICAL ENGINEERING UNIT AT 1919 T07-6850. THE SUBSURFACE PLANS AND REPORTS, FIELD BORING LOGS, ROCK CORES AND SOIL TEST DATA ARE NOT PART OF THE CONTRACT.

GENERAL SOIL AND ROCK STRATA DESCRIPTIONS AND INDICATED BOUNDARIES ARE BASED ON A GEOTECHNICAL INTERPRETATION OF ALL AVAILABLE SUBSURFACE DATA AND MAY NOT NECESSARILY REFLECT THE ACTUAL SUBSURFACE CONDITIONS BETWEEN BORINGS OR BETWEEN SAMPLED STRATA WITHIN THE BOREHOLE. THE LABORATORY SAMPLE DATA AND THE IN SITU (IN-PLACE) TEST DATA CAN BE RELIED ON ONLY TO THE DEGREE OF RELIABILITY INHERENT IN THE STANDARD TEST METHOD. THE OBSERVED WATER LEVELS OR SOIL MOISTURE CONDITIONS INDICATED IN THE SUBSURFACE INVESTIGATIONS ARE AS RECORDED AT THE TIME OF THE INVESTIGATION. THESE WATER LEVELS OR SOIL MOISTURE CONDITIONS MAY VARY CONSIDERABLY WITH TIME ACCORDING TO CLIMATIC CONDITIONS INCLUDING TEMPERATURES, PRECIPITATION AND WIND, AS WELL AS OTHER NON-CLIMATIC FACTORS.

THE BIDDER OR CONTRACTOR IS CAUTIONED THAT DETAILS SHOWN ON THE SUBSURFACE PLANS ARE PRELIMINARY ONLY AND IN MANY CASES THE FINAL DESIGN DETAILS ARE DIFFERENT. FOR BIDDING AND CONSTRUCTION PURPOSES, REFER TO THE CONSTRUCTION PLANS AND DOCUMENTS FOR FINAL DESIGN INFORMATION ON THIS PROJECT. THE DEPARTMENT DOES NOT WARRANT OR GUARANTEE THE SUFFICIENCY OR ACCURACY OF THE INVESTIGATION MADE, NOR THE INTERPRETATIONS MADE, OR OPINION OF THE DEPARTMENT AS TO THE TYPE OF MATERIALS AND CONDITIONS TO BE ENCOUNTERED. THE BIDDER OR CONTRACTOR IS CAUTIONED TO MAKE SUCH INDEPENDENT SUBSURFACE INVESTIGATIONS AS HE DEEMS NECESSARY TO SATISFY HIMSELF AS TO CONDITIONS TO BE ENCOUNTERED ON THE PROJECT. THE CONTRACTOR SHALL HAVE NO CLAIM FOR ADDITIONAL COMPENSATION OR FOR AN EXTENSION OF TIME FOR ANY REASON RESULTING FROM THE ACTUAL CONDITIONS ENCOUNTERED AT THE SITE DIFFERING FROM THOSE INDICATED IN THE SUBSURFACE INFORMATION.

- NOTES:
- THE INFORMATION CONTAINED HEREIN IS NOT IMPLIED OR GUARANTEED BY THE N. C. DEPARTMENT OF TRANSPORTATION AS ACCURATE NOR IS IT CONSIDERED PART OF THE PLANS, SPECIFICATIONS OR CONTRACT FOR THE PROJECT.
 - BY HAVING REQUESTED THIS INFORMATION, THE CONTRACTOR SPECIFICALLY WAIVES ANY CLAIMS FOR INCREASED COMPENSATION OR EXTENSION OF TIME BASED ON DIFFERENCES BETWEEN THE CONDITIONS INDICATED HEREIN AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.

PERSONNEL

BRECCIA

CG2 EXPLORATION

M. BREWER

C. PIERCEY

N. MCLAREN

INVESTIGATED BY CG2

DRAWN BY M. BREWER, P.E.

CHECKED BY R. KRAL, P.E.

SUBMITTED BY M. BREWER, P.E.

DATE JULY 2022

Prepared in the Office of:
 **CAROLINAS GEOTECHNICAL GROUP**
2400 CROWNPOINT EXECUTIVE DRIVE
SUITE 800
CHARLOTTE, NC 28227
(980) 339-8684



DocuSigned by:



386129C0A4C1462
SIGNATURE DATE 7/9/2022

**DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED**

NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT
SUBSURFACE INVESTIGATION
SOIL AND ROCK LEGEND, TERMS, SYMBOLS, AND ABBREVIATIONS

SOIL DESCRIPTION										GRADATION										ROCK DESCRIPTION										TERMS AND DEFINITIONS																																																																																																																																																																																	
<p>SOIL IS CONSIDERED UNCONSOLIDATED, SEMI-CONSOLIDATED, OR WEATHERED EARTH MATERIALS THAT CAN BE PENETRATED WITH A CONTINUOUS FLIGHT POWER AUGER AND YIELD LESS THAN 100 BLOWS PER FOOT ACCORDING TO THE STANDARD PENETRATION TEST (AASHTO T 208, ASTM D1586). SOIL CLASSIFICATION IS BASED ON THE AASHTO SYSTEM. BASIC DESCRIPTIONS GENERALLY INCLUDE THE FOLLOWING: CONSISTENCY, COLOR, TEXTURE, MOISTURE, AASHTO CLASSIFICATION, AND OTHER PERTINENT FACTORS SUCH AS MINERALOGICAL COMPOSITION, ANGULARITY, STRUCTURE, PLASTICITY, ETC. FOR EXAMPLE, <i>VERY STIFF, GRAY, SILTY CLAY, MOIST WITH INTERBEDDED FINE SAND LAYERS, HIGHLY PLASTIC, A-7-6</i></p>										<p>WELL GRADED - INDICATES A GOOD REPRESENTATION OF PARTICLE SIZES FROM FINE TO COARSE. UNIFORMLY GRADED - INDICATES THAT SOIL PARTICLES ARE ALL APPROXIMATELY THE SAME SIZE. GAP-GRADED - INDICATES A MIXTURE OF UNIFORM PARTICLE SIZES OF TWO OR MORE SIZES.</p>										<p>HARD ROCK IS NON-COASTAL PLAIN MATERIAL THAT WOULD YIELD SPT REFUSAL IF TESTED, AN INFERRED ROCK LINE INDICATES THE LEVEL AT WHICH NON-COASTAL PLAIN MATERIAL WOULD YIELD SPT REFUSAL. SPT REFUSAL IS PENETRATION BY A SPLIT SPOON SAMPLER EQUAL TO OR LESS THAN 0.1 FOOT PER 60 BLOWS IN NON-COASTAL PLAIN MATERIAL. THE TRANSITION BETWEEN SOIL AND ROCK IS OFTEN REPRESENTED BY A ZONE OF WEATHERED ROCK. ROCK MATERIALS ARE TYPICALLY DIVIDED AS FOLLOWS:</p>										<p>ALLUVIUM (ALLUV.) - SOILS THAT HAVE BEEN TRANSPORTED BY WATER. AQUIFER - A WATER BEARING FORMATION OR STRATA. ARENACEOUS - APPLIED TO ROCKS THAT HAVE BEEN DERIVED FROM SAND OR THAT CONTAIN SAND. ARGILLACEOUS - APPLIED TO ALL ROCKS OR SUBSTANCES COMPOSED OF CLAY MINERALS, OR HAVING A NOTABLE PROPORTION OF CLAY IN THEIR COMPOSITION, SUCH AS SHALE, SLATE, ETC. ARTESIAN - GROUND WATER THAT IS UNDER SUFFICIENT PRESSURE TO RISE ABOVE THE LEVEL AT WHICH IT IS ENCOUNTERED, BUT WHICH DOES NOT NECESSARILY RISE TO OR ABOVE THE GROUND SURFACE. CALCAREOUS (CALC.) - SOILS THAT CONTAIN APPRECIABLE AMOUNTS OF CALCIUM CARBONATE. COLLUVIUM - ROCK FRAGMENTS MIXED WITH SOIL DEPOSITED BY GRAVITY ON SLOPE OR AT BOTTOM OF SLOPE. CORE RECOVERY (REC.) - TOTAL LENGTH OF ALL MATERIAL RECOVERED IN THE CORE BARREL DIVIDED BY TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE. DIKE - A TABULAR BODY OF IGNEOUS ROCK THAT CUTS ACROSS THE STRUCTURE OF ADJACENT ROCKS OR CUTS MASSIVE ROCK. DIP - THE ANGLE AT WHICH A STRATUM OR ANY PLANAR FEATURE IS INCLINED FROM THE HORIZONTAL. DIP DIRECTION (DIP AZIMUTH) - THE DIRECTION OR BEARING OF THE HORIZONTAL TRACE OF THE LINE OF DIP, MEASURED CLOCKWISE FROM NORTH. FAULT - A FRACTURE OR FRACTURE ZONE ALONG WHICH THERE HAS BEEN DISPLACEMENT OF THE SIDES RELATIVE TO ONE ANOTHER PARALLEL TO THE FRACTURE. FISSILE - A PROPERTY OF SPLITTING ALONG CLOSELY SPACED PARALLEL PLANES. FLOAT - ROCK FRAGMENTS ON SURFACE NEAR THEIR ORIGINAL POSITION AND DISLOGGED FROM PARENT MATERIAL. FLOOD PLAIN (FP) - LAND BORDERING A STREAM, BUILT OF SEDIMENTS DEPOSITED BY THE STREAM. FORMATION (FM) - A MAPPABLE GEOLOGIC UNIT THAT CAN BE RECOGNIZED AND TRACED IN THE FIELD. JOINT - FRACTURE IN ROCK ALONG WHICH NO APPRECIABLE MOVEMENT HAS OCCURRED. LEDGE - A SHELF-LIKE RIDGE OR PROJECTION OF ROCK WHOSE THICKNESS IS SMALL COMPARED TO ITS LATERAL EXTENT. LENS - A BODY OF SOIL OR ROCK THAT THINS OUT IN ONE OR MORE DIRECTIONS. MOTTLED (MOT.) - IRREGULARLY MARKED WITH SPOTS OF DIFFERENT COLORS. MOTTLING IN SOILS USUALLY INDICATES POOR AERATION AND LACK OF GOOD DRAINAGE. PERCHED WATER - WATER MAINTAINED ABOVE THE NORMAL GROUND WATER LEVEL BY THE PRESENCE OF AN INTERVENING IMPERVIOUS STRATUM. RESIDUAL (RES.) SOIL - SOIL FORMED IN PLACE BY THE WEATHERING OF ROCK. ROCK QUALITY DESIGNATION (ROQ) - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE. SAPROLITE (SAP.) - RESIDUAL SOIL THAT RETAINS THE RELIC STRUCTURE OR FABRIC OF THE PARENT ROCK. SILL - AN INTRUSIVE BODY OF IGNEOUS ROCK OF APPROXIMATELY UNIFORM THICKNESS AND RELATIVELY THIN COMPARED WITH ITS LATERAL EXTENT, THAT HAS BEEN EMPLACED PARALLEL TO THE BEDDING OR SCHISTOSITY OF THE INTRUDED ROCKS. SLICKENSIDE - POLISHED AND STRIATED SURFACE THAT RESULTS FROM FRICTION ALONG A FAULT OR SLIP PLANE. STANDARD PENETRATION TEST (PENETRATION RESISTANCE) (SPT) - NUMBER OF BLOWS (N OR BPF) OF A 140 LB. HAMMER FALLING 30 INCHES REQUIRED TO PRODUCE A PENETRATION OF 1 FOOT INTO SOIL WITH A 2 INCH OUTSIDE DIAMETER SPLIT SPOON SAMPLER. SPT REFUSAL IS PENETRATION EQUAL TO OR LESS THAN 0.1 FOOT PER 60 BLOWS. STRATA CORE RECOVERY (SREC.) - TOTAL LENGTH OF STRATA MATERIAL RECOVERED DIVIDED BY TOTAL LENGTH OF STRATUM AND EXPRESSED AS A PERCENTAGE. STRATA ROCK QUALITY DESIGNATION (SROQ) - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS WITHIN A STRATUM EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF STRATA AND EXPRESSED AS A PERCENTAGE. TOPSOIL (TS.) - SURFACE SOILS USUALLY CONTAINING ORGANIC MATTER.</p>																																																																																																																																																																																	
<p style="text-align: center;">SOIL LEGEND AND AASHTO CLASSIFICATION</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th rowspan="2">GENERAL CLASS.</th> <th colspan="5">GRANULAR MATERIALS (≤ 35% PASSING #200)</th> <th colspan="5">SILT-CLAY MATERIALS (> 35% PASSING #200)</th> <th colspan="5">ORGANIC MATERIALS</th> </tr> <tr> <th>A-1</th> <th>A-3</th> <th>A-2</th> <th>A-4</th> <th>A-5</th> <th>A-6</th> <th>A-7</th> <th>A-1, A-2</th> <th>A-3</th> <th>A-4, A-5</th> <th>A-6, A-7</th> <th></th> <th></th> <th></th> <th></th> </tr> <tr> <td>GROUP CLASS.</td> <td>A-1-a</td> <td>A-1-b</td> <td>A-2-4</td> <td>A-2-5</td> <td>A-2-6</td> <td>A-2-7</td> <td>A-4</td> <td>A-5</td> <td>A-6</td> <td>A-7</td> <td>A-1, A-2</td> <td>A-3</td> <td>A-4, A-5</td> <td>A-6, A-7</td> <td></td> </tr> <tr> <td>SYMBOL</td> <td colspan="5">[Pattern]</td> <td colspan="5">[Pattern]</td> <td colspan="5">[Pattern]</td> </tr> <tr> <td>% PASSING #10 #40 #200</td> <td>50 MX 30 MX 15 MX</td> <td>50 MX 25 MX</td> <td>51 MN 10 MX</td> <td>35 MX 35 MX</td> <td>35 MX 35 MX</td> <td>35 MX 35 MX</td> <td>36 MN 36 MN</td> <td>36 MN 36 MN</td> <td>36 MN 36 MN</td> <td>36 MN 36 MN</td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>MATERIAL PASSING #40 LL PI</td> <td colspan="5">-</td> <td>40 MX 41 MN</td> <td>40 MX 41 MN</td> <td>40 MX 41 MN</td> <td>40 MX 41 MN</td> <td>40 MX 41 MN</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>GROUP INDEX</td> <td colspan="5">0</td> <td>0</td> <td>4 MX</td> <td>8 MX</td> <td>12 MX</td> <td>16 MX</td> <td>NO MX</td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>USUAL TYPES OF MAJOR MATERIALS</td> <td colspan="2">STONE FRAGS. GRAVEL, AND SAND</td> <td colspan="2">FINE SAND</td> <td colspan="2">SILTY OR CLAYEY GRAVEL AND SAND</td> <td colspan="2">SILTY SOILS</td> <td colspan="2">CLAYEY SOILS</td> <td colspan="5">SOILS WITH LITTLE OR MODERATE AMOUNTS OF ORGANIC MATTER</td> </tr> <tr> <td>GEN. RATING AS SUBGRADE</td> <td colspan="5">EXCELLENT TO GOOD</td> <td colspan="5">FAIR TO POOR</td> <td>FAIR TO POOR</td> <td>POOR</td> <td>UNSATURABLE</td> <td colspan="5"></td> </tr> </table> <p style="text-align: center;">PI OF A-7-5 SUBGROUP IS ≤ LL - 30 ; PI OF A-7-6 SUBGROUP IS > LL - 30</p>										GENERAL CLASS.	GRANULAR MATERIALS (≤ 35% PASSING #200)					SILT-CLAY MATERIALS (> 35% PASSING #200)					ORGANIC MATERIALS					A-1	A-3	A-2	A-4	A-5	A-6	A-7	A-1, A-2	A-3	A-4, A-5	A-6, A-7					GROUP CLASS.	A-1-a	A-1-b	A-2-4	A-2-5	A-2-6	A-2-7	A-4	A-5	A-6	A-7	A-1, A-2	A-3	A-4, A-5	A-6, A-7		SYMBOL	[Pattern]					[Pattern]					[Pattern]					% PASSING #10 #40 #200	50 MX 30 MX 15 MX	50 MX 25 MX	51 MN 10 MX	35 MX 35 MX	35 MX 35 MX	35 MX 35 MX	36 MN 36 MN	36 MN 36 MN	36 MN 36 MN	36 MN 36 MN						MATERIAL PASSING #40 LL PI	-					40 MX 41 MN	40 MX 41 MN	40 MX 41 MN	40 MX 41 MN	40 MX 41 MN							GROUP INDEX	0					0	4 MX	8 MX	12 MX	16 MX	NO MX						USUAL TYPES OF MAJOR MATERIALS	STONE FRAGS. GRAVEL, AND SAND		FINE SAND		SILTY OR CLAYEY GRAVEL AND SAND		SILTY SOILS		CLAYEY SOILS		SOILS WITH LITTLE OR MODERATE AMOUNTS OF ORGANIC MATTER					GEN. RATING AS SUBGRADE	EXCELLENT TO GOOD					FAIR TO POOR					FAIR TO POOR	POOR	UNSATURABLE						<p style="text-align: center;">MINERALOGICAL COMPOSITION</p> <p>MINERAL NAMES SUCH AS QUARTZ, FELDSPAR, MICA, TALC, KAOLIN, ETC. ARE USED IN DESCRIPTIONS WHEN THEY ARE CONSIDERED OF SIGNIFICANCE.</p>										<p style="text-align: center;">WEATHERING</p> <p>FRESH: ROCK FRESH, CRYSTALS BRIGHT, FEW JOINTS MAY SHOW SLIGHT STAINING. ROCK RINGS UNDER HAMMER IF CRYSTALLINE.</p> <p>VERY SLIGHT (IV SLI.): ROCK GENERALLY FRESH, JOINTS STAINED, SOME JOINTS MAY SHOW THIN CLAY COATINGS IF OPEN. CRYSTALS ON A BROKEN SPECIMEN FACE SHINE BRIGHTLY. ROCK RINGS UNDER HAMMER BLOWS IF OF A CRYSTALLINE NATURE.</p> <p>SLIGHT (SLI.): ROCK GENERALLY FRESH, JOINTS STAINED AND DISCOLORATION EXTENDS INTO ROCK UP TO 1 INCH. OPEN JOINTS MAY CONTAIN CLAY. IN GRANITOID ROCKS SOME OCCASIONAL FELDSPAR CRYSTALS ARE DULL AND DISCOLORED. CRYSTALLINE ROCKS RING UNDER HAMMER BLOWS.</p> <p>MODERATE (MOD.): SIGNIFICANT PORTIONS OF ROCK SHOW DISCOLORATION AND WEATHERING EFFECTS. IN GRANITOID ROCKS, MOST FELDSPARS ARE DULL AND DISCOLORED, SOME SHOW CLAY. ROCK HAS DULL SOUND UNDER HAMMER BLOWS AND SHOWS SIGNIFICANT LOSS OF STRENGTH AS COMPARED WITH FRESH ROCK.</p> <p>MODERATELY SEVERE (MOD. SEV.): ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. IN GRANITOID ROCKS, ALL FELDSPARS DULL AND DISCOLORED AND A MAJORITY SHOW KAOLINIZATION. ROCK SHOWS SEVERE LOSS OF STRENGTH AND CAN BE EXCAVATED WITH A GEOLOGIST'S PICK. ROCK GIVES "CLUNK" SOUND WHEN STRUCK. <i>IF TESTED, WOULD YIELD SPT REFUSAL</i></p> <p>SEVERE (SEV.): ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. ROCK FABRIC CLEAR AND EVIDENT BUT REDUCED IN STRENGTH TO STRONG SOIL. IN GRANITOID ROCKS ALL FELDSPARS ARE KAOLINIZED TO SOME EXTENT. SOME FRAGMENTS OF STRONG ROCK USUALLY REMAIN. <i>IF TESTED, WOULD YIELD SPT N VALUES > 100 BPF</i></p> <p>VERY SEVERE (IV SEV.): ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. ROCK FABRIC ELEMENTS ARE DISCERNIBLE BUT MASS IS EFFECTIVELY REDUCED TO SOIL STATUS, WITH ONLY FRAGMENTS OF STRONG ROCK REMAINING. SAPROLITE IS AN EXAMPLE OF ROCK WEATHERED TO A DEGREE THAT ONLY MINOR VESTIGES OF ORIGINAL ROCK FABRIC REMAIN. <i>IF TESTED, WOULD YIELD SPT N VALUES < 100 BPF</i></p> <p>COMPLETE: ROCK REDUCED TO SOIL. ROCK FABRIC NOT DISCERNIBLE, OR DISCERNIBLE ONLY IN SMALL AND SCATTERED CONCENTRATIONS. QUARTZ MAY BE PRESENT AS DIKES OR STRINGERS. SAPROLITE IS ALSO AN EXAMPLE.</p>										<p style="text-align: center;">PERCENTAGE OF MATERIAL</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th>ORGANIC MATERIAL</th> <th>GRANULAR SOILS</th> <th>SILT - CLAY SOILS</th> <th>OTHER MATERIAL</th> </tr> <tr> <td>TRACE OF ORGANIC MATTER</td> <td>2 - 3%</td> <td>3 - 5%</td> <td>TRACE 1 - 10%</td> </tr> <tr> <td>LITTLE ORGANIC MATTER</td> <td>3 - 5%</td> <td>5 - 12%</td> <td>LITTLE 10 - 20%</td> </tr> <tr> <td>MODERATELY ORGANIC</td> <td>5 - 10%</td> <td>12 - 20%</td> <td>SOME 20 - 35%</td> </tr> <tr> <td>HIGHLY ORGANIC</td> <td>> 10%</td> <td>> 20%</td> <td>HIGHLY 35% AND ABOVE</td> </tr> </table>										ORGANIC MATERIAL	GRANULAR SOILS	SILT - CLAY SOILS	OTHER MATERIAL	TRACE OF ORGANIC MATTER	2 - 3%	3 - 5%	TRACE 1 - 10%	LITTLE ORGANIC MATTER	3 - 5%	5 - 12%	LITTLE 10 - 20%	MODERATELY ORGANIC	5 - 10%	12 - 20%	SOME 20 - 35%	HIGHLY ORGANIC	> 10%	> 20%	HIGHLY 35% AND ABOVE
GENERAL CLASS.	GRANULAR MATERIALS (≤ 35% PASSING #200)					SILT-CLAY MATERIALS (> 35% PASSING #200)					ORGANIC MATERIALS																																																																																																																																																																																																				
	A-1	A-3	A-2	A-4	A-5	A-6	A-7	A-1, A-2	A-3	A-4, A-5	A-6, A-7																																																																																																																																																																																																				
GROUP CLASS.	A-1-a	A-1-b	A-2-4	A-2-5	A-2-6	A-2-7	A-4	A-5	A-6	A-7	A-1, A-2	A-3	A-4, A-5	A-6, A-7																																																																																																																																																																																																	
SYMBOL	[Pattern]					[Pattern]					[Pattern]																																																																																																																																																																																																				
% PASSING #10 #40 #200	50 MX 30 MX 15 MX	50 MX 25 MX	51 MN 10 MX	35 MX 35 MX	35 MX 35 MX	35 MX 35 MX	36 MN 36 MN	36 MN 36 MN	36 MN 36 MN	36 MN 36 MN																																																																																																																																																																																																					
MATERIAL PASSING #40 LL PI	-					40 MX 41 MN	40 MX 41 MN	40 MX 41 MN	40 MX 41 MN	40 MX 41 MN																																																																																																																																																																																																					
GROUP INDEX	0					0	4 MX	8 MX	12 MX	16 MX	NO MX																																																																																																																																																																																																				
USUAL TYPES OF MAJOR MATERIALS	STONE FRAGS. GRAVEL, AND SAND		FINE SAND		SILTY OR CLAYEY GRAVEL AND SAND		SILTY SOILS		CLAYEY SOILS		SOILS WITH LITTLE OR MODERATE AMOUNTS OF ORGANIC MATTER																																																																																																																																																																																																				
GEN. RATING AS SUBGRADE	EXCELLENT TO GOOD					FAIR TO POOR					FAIR TO POOR	POOR	UNSATURABLE																																																																																																																																																																																																		
ORGANIC MATERIAL	GRANULAR SOILS	SILT - CLAY SOILS	OTHER MATERIAL																																																																																																																																																																																																												
TRACE OF ORGANIC MATTER	2 - 3%	3 - 5%	TRACE 1 - 10%																																																																																																																																																																																																												
LITTLE ORGANIC MATTER	3 - 5%	5 - 12%	LITTLE 10 - 20%																																																																																																																																																																																																												
MODERATELY ORGANIC	5 - 10%	12 - 20%	SOME 20 - 35%																																																																																																																																																																																																												
HIGHLY ORGANIC	> 10%	> 20%	HIGHLY 35% AND ABOVE																																																																																																																																																																																																												
<p style="text-align: center;">CONSISTENCY OR DENSENESS</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th>PRIMARY SOIL TYPE</th> <th>COMPACTNESS OR CONSISTENCY</th> <th>RANGE OF STANDARD PENETRATION RESISTANCE (N-VALUE)</th> <th>RANGE OF UNCONFINED COMPRESSIVE STRENGTH (TONS/FT²)</th> </tr> <tr> <td>GENERALLY GRANULAR MATERIAL (NON-COHESIVE)</td> <td>VERY LOOSE LOOSE MEDIUM DENSE DENSE VERY DENSE</td> <td>< 4 4 TO 10 10 TO 30 30 TO 50 > 50</td> <td>N/A</td> </tr> <tr> <td>GENERALLY SILT-CLAY MATERIAL (COHESIVE)</td> <td>VERY SOFT SOFT MEDIUM STIFF STIFF VERY STIFF HARD</td> <td>< 2 2 TO 4 4 TO 8 8 TO 15 15 TO 30 > 30</td> <td>< 0.25 0.25 TO 0.5 0.5 TO 1.0 1 TO 2 2 TO 4 > 4</td> </tr> </table>										PRIMARY SOIL TYPE	COMPACTNESS OR CONSISTENCY	RANGE OF STANDARD PENETRATION RESISTANCE (N-VALUE)	RANGE OF UNCONFINED COMPRESSIVE STRENGTH (TONS/FT ²)	GENERALLY GRANULAR MATERIAL (NON-COHESIVE)	VERY LOOSE LOOSE MEDIUM DENSE DENSE VERY DENSE	< 4 4 TO 10 10 TO 30 30 TO 50 > 50	N/A	GENERALLY SILT-CLAY MATERIAL (COHESIVE)	VERY SOFT SOFT MEDIUM STIFF STIFF VERY STIFF HARD	< 2 2 TO 4 4 TO 8 8 TO 15 15 TO 30 > 30	< 0.25 0.25 TO 0.5 0.5 TO 1.0 1 TO 2 2 TO 4 > 4	<p style="text-align: center;">GROUND WATER</p> <p>▽ WATER LEVEL IN BORE HOLE IMMEDIATELY AFTER DRILLING</p> <p>▽/24 STATIC WATER LEVEL AFTER 24 HOURS</p> <p>▽/PW PERCHED WATER, SATURATED ZONE, OR WATER BEARING STRATA</p> <p>○ SPRING OR SEEP</p>										<p style="text-align: center;">MISCELLANEOUS SYMBOLS</p> <p>ROADWAY EMBANKMENT (RE) WITH SOIL DESCRIPTION</p> <p>SOIL SYMBOL</p> <p>ARTIFICIAL FILL (AF) OTHER THAN ROADWAY EMBANKMENT</p> <p>INFERRED SOIL BOUNDARY</p> <p>INFERRED ROCK LINE</p> <p>ALLUVIAL SOIL BOUNDARY</p> <p>DIP & DIP DIRECTION OF ROCK STRUCTURES</p> <p>SPT DMT VST PMT TEST BORING</p> <p>AUGER BORING</p> <p>CORE BORING</p> <p>MONITORING WELL</p> <p>PIEZOMETER INSTALLATION</p> <p>SLOPE INDICATOR INSTALLATION</p> <p>CONE PENETROMETER TEST</p> <p>SOUNDING ROD</p> <p>TEST BORING WITH CORE</p> <p>SPT N-VALUE</p>																																																																																																																																																																															
PRIMARY SOIL TYPE	COMPACTNESS OR CONSISTENCY	RANGE OF STANDARD PENETRATION RESISTANCE (N-VALUE)	RANGE OF UNCONFINED COMPRESSIVE STRENGTH (TONS/FT ²)																																																																																																																																																																																																												
GENERALLY GRANULAR MATERIAL (NON-COHESIVE)	VERY LOOSE LOOSE MEDIUM DENSE DENSE VERY DENSE	< 4 4 TO 10 10 TO 30 30 TO 50 > 50	N/A																																																																																																																																																																																																												
GENERALLY SILT-CLAY MATERIAL (COHESIVE)	VERY SOFT SOFT MEDIUM STIFF STIFF VERY STIFF HARD	< 2 2 TO 4 4 TO 8 8 TO 15 15 TO 30 > 30	< 0.25 0.25 TO 0.5 0.5 TO 1.0 1 TO 2 2 TO 4 > 4																																																																																																																																																																																																												
<p style="text-align: center;">TEXTURE OR GRAIN SIZE</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th>U.S. STD. SIEVE SIZE OPENING (MM)</th> <th>4</th> <th>10</th> <th>40</th> <th>60</th> <th>200</th> <th>270</th> </tr> <tr> <td></td> <td>4.75</td> <td>2.00</td> <td>0.42</td> <td>0.25</td> <td>0.075</td> <td>0.053</td> </tr> <tr> <td>BOULDER (BLDR.)</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>COBBLE (COB.)</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>GRAVEL (GR.)</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>COARSE SAND (CSE. SD.)</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>FINE SAND (F SD.)</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>SILT (SL.)</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>CLAY (CL.)</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>GRAIN SIZE</td> <td>305</td> <td>75</td> <td>2.0</td> <td>0.25</td> <td>0.05</td> <td>0.005</td> </tr> <tr> <td>MM</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>IN.</td> <td>12</td> <td>3</td> <td></td> <td></td> <td></td> <td></td> </tr> </table>										U.S. STD. SIEVE SIZE OPENING (MM)	4	10	40	60	200	270		4.75	2.00	0.42	0.25	0.075	0.053	BOULDER (BLDR.)							COBBLE (COB.)							GRAVEL (GR.)							COARSE SAND (CSE. SD.)							FINE SAND (F SD.)							SILT (SL.)							CLAY (CL.)							GRAIN SIZE	305	75	2.0	0.25	0.05	0.005	MM							IN.	12	3					<p style="text-align: center;">RECOMMENDATION SYMBOLS</p> <p>UNDERCUT</p> <p>SHALLOW UNDERCUT</p> <p>UNCLASSIFIED EXCAVATION - UNSUITABLE WASTE</p> <p>UNCLASSIFIED EXCAVATION - ACCEPTABLE DEGRADABLE ROCK</p> <p>UNCLASSIFIED EXCAVATION - ACCEPTABLE, BUT NOT TO BE USED IN THE TOP 3 FEET OF EMBANKMENT OR BACKFILL</p>										<p style="text-align: center;">ABBREVIATIONS</p> <p>AR - AUGER REFUSAL BT - BORING TERMINATED CL - CLAY CPT - CONE PENETRATION TEST CSE - COARSE DMT - DILATOMETER TEST DPT - DYNAMIC PENETRATION TEST e - VOID RATIO F - FINE FOSS. - FOSSILIFEROUS FRAC. - FRACTURED, FRACTURES FRAGS. - FRAGMENTS HI. - HIGHLY</p> <p>MED. - MEDIUM MICA - MICACEOUS MOD. - MODERATELY NP - NON PLASTIC ORG. - ORGANIC PMT - PRESSUREMETER TEST SAP. - SAPROLITIC SD. - SAND, SANDY SL. - SILT, SILTY SLI. - SLIGHTLY TCR - TRICONE REFUSAL w - MOISTURE CONTENT V - VERY</p> <p>VST - VANE SHEAR TEST WEA. - WEATHERED γ_s - UNIT WEIGHT γ_d - DRY UNIT WEIGHT</p> <p>SAMPLE ABBREVIATIONS</p> <p>S - BULK SS - SPLIT SPOON ST - SHELBY TUBE RS - ROCK RT - RECOMPACTED TRIAXIAL CBR - CALIFORNIA BEARING RATIO</p>																																																																																																							
U.S. STD. SIEVE SIZE OPENING (MM)	4	10	40	60	200	270																																																																																																																																																																																																									
	4.75	2.00	0.42	0.25	0.075	0.053																																																																																																																																																																																																									
BOULDER (BLDR.)																																																																																																																																																																																																															
COBBLE (COB.)																																																																																																																																																																																																															
GRAVEL (GR.)																																																																																																																																																																																																															
COARSE SAND (CSE. SD.)																																																																																																																																																																																																															
FINE SAND (F SD.)																																																																																																																																																																																																															
SILT (SL.)																																																																																																																																																																																																															
CLAY (CL.)																																																																																																																																																																																																															
GRAIN SIZE	305	75	2.0	0.25	0.05	0.005																																																																																																																																																																																																									
MM																																																																																																																																																																																																															
IN.	12	3																																																																																																																																																																																																													
<p style="text-align: center;">SOIL MOISTURE - CORRELATION OF TERMS</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th>SOIL MOISTURE SCALE (ATTERBERG LIMITS)</th> <th>FIELD MOISTURE DESCRIPTION</th> <th>GUIDE FOR FIELD MOISTURE DESCRIPTION</th> </tr> <tr> <td>LL - LIQUID LIMIT</td> <td>- SATURATED - (SAT.)</td> <td>USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE</td> </tr> <tr> <td>PLASTIC RANGE (PI)</td> <td>- WET - (W)</td> <td>SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE</td> </tr> <tr> <td>PL - PLASTIC LIMIT</td> <td>- MOIST - (M)</td> <td>SOLID; AT OR NEAR OPTIMUM MOISTURE</td> </tr> <tr> <td>OM - OPTIMUM MOISTURE</td> <td>- DRY - (D)</td> <td>REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE</td> </tr> <tr> <td>SL - SHRINKAGE LIMIT</td> <td></td> <td></td> </tr> </table>										SOIL MOISTURE SCALE (ATTERBERG LIMITS)	FIELD MOISTURE DESCRIPTION	GUIDE FOR FIELD MOISTURE DESCRIPTION	LL - LIQUID LIMIT	- SATURATED - (SAT.)	USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE	PLASTIC RANGE (PI)	- WET - (W)	SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE	PL - PLASTIC LIMIT	- MOIST - (M)	SOLID; AT OR NEAR OPTIMUM MOISTURE	OM - OPTIMUM MOISTURE	- DRY - (D)	REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE	SL - SHRINKAGE LIMIT			<p style="text-align: center;">EQUIPMENT USED ON SUBJECT PROJECT</p> <p>DRILL UNITS:</p> <p><input type="checkbox"/> CME-45C</p> <p><input checked="" type="checkbox"/> CME-550</p> <p><input type="checkbox"/> CME-550X</p> <p><input type="checkbox"/> VANE SHEAR TEST</p> <p><input type="checkbox"/> PORTABLE HOIST</p> <p><input checked="" type="checkbox"/> DIEDRICH D50</p> <p>ADVANCING TOOLS:</p> <p><input type="checkbox"/> CLAY BITS</p> <p><input type="checkbox"/> 6" CONTINUOUS FLIGHT AUGER</p> <p><input checked="" type="checkbox"/> 8" HOLLOW AUGERS</p> <p><input type="checkbox"/> HARD FACED FINGER BITS</p> <p><input type="checkbox"/> TUNG-CARBIDE INSERTS</p> <p><input type="checkbox"/> CASING <input type="checkbox"/> W/ ADVANCER</p> <p><input type="checkbox"/> TRICONE *STEEL TEETH</p> <p><input type="checkbox"/> TRICONE *TUNG-CARB.</p> <p><input type="checkbox"/> CORE BIT</p> <p>HAMMER TYPE:</p> <p><input checked="" type="checkbox"/> AUTOMATIC <input type="checkbox"/> MANUAL</p> <p>CORE SIZE:</p> <p><input type="checkbox"/> -B <input type="checkbox"/> -H <input type="checkbox"/> -N</p> <p>HAND TOOLS:</p> <p><input type="checkbox"/> POST HOLE DIGGER</p> <p><input type="checkbox"/> HAND AUGER</p> <p><input type="checkbox"/> SOUNDING ROD</p> <p><input type="checkbox"/> VANE SHEAR TEST</p>																																																																																																																																																																																			
SOIL MOISTURE SCALE (ATTERBERG LIMITS)	FIELD MOISTURE DESCRIPTION	GUIDE FOR FIELD MOISTURE DESCRIPTION																																																																																																																																																																																																													
LL - LIQUID LIMIT	- SATURATED - (SAT.)	USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE																																																																																																																																																																																																													
PLASTIC RANGE (PI)	- WET - (W)	SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE																																																																																																																																																																																																													
PL - PLASTIC LIMIT	- MOIST - (M)	SOLID; AT OR NEAR OPTIMUM MOISTURE																																																																																																																																																																																																													
OM - OPTIMUM MOISTURE	- DRY - (D)	REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE																																																																																																																																																																																																													
SL - SHRINKAGE LIMIT																																																																																																																																																																																																															
<p style="text-align: center;">PLASTICITY</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th>NON PLASTIC</th> <th>PLASTICITY INDEX (PI)</th> <th>DRY STRENGTH</th> </tr> <tr> <td></td> <td>0-5</td> <td>VERY LOW</td> </tr> <tr> <td>SLIGHTLY PLASTIC</td> <td>6-15</td> <td>SLIGHT</td> </tr> <tr> <td>MODERATELY PLASTIC</td> <td>16-25</td> <td>MEDIUM</td> </tr> <tr> <td>HIGHLY PLASTIC</td> <td>26 OR MORE</td> <td>HIGH</td> </tr> </table>										NON PLASTIC	PLASTICITY INDEX (PI)	DRY STRENGTH		0-5	VERY LOW	SLIGHTLY PLASTIC	6-15	SLIGHT	MODERATELY PLASTIC	16-25	MEDIUM	HIGHLY PLASTIC	26 OR MORE	HIGH	<p style="text-align: center;">ROCK HARDNESS</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th>TERM</th> <th>SPACING</th> <th>TERM</th> <th>THICKNESS</th> </tr> <tr> <td>VERY WIDE</td> <td>MORE THAN 10 FEET</td> <td>VERY THICKLY BEDDED</td> <td>4 FEET</td> </tr> <tr> <td>WIDE</td> <td>3 TO 10 FEET</td> <td>THICKLY BEDDED</td> <td>1.5 - 4 FEET</td> </tr> <tr> <td>MODERATELY CLOSE</td> <td>1 TO 3 FEET</td> <td>THINLY BEDDED</td> <td>0.16 - 1.5 FEET</td> </tr> <tr> <td>CLOSE</td> <td>0.16 TO 1 FOOT</td> <td>VERY THINLY BEDDED</td> <td>0.03 - 0.16 FEET</td> </tr> <tr> <td>VERY CLOSE</td> <td>LESS THAN 0.16 FEET</td> <td>THICKLY LAMINATED</td> <td>0.008 - 0.03 FEET</td> </tr> <tr> <td></td> <td></td> <td>THINLY LAMINATED</td> <td>< 0.008 FEET</td> </tr> </table>										TERM	SPACING	TERM	THICKNESS	VERY WIDE	MORE THAN 10 FEET	VERY THICKLY BEDDED	4 FEET	WIDE	3 TO 10 FEET	THICKLY BEDDED	1.5 - 4 FEET	MODERATELY CLOSE	1 TO 3 FEET	THINLY BEDDED	0.16 - 1.5 FEET	CLOSE	0.16 TO 1 FOOT	VERY THINLY BEDDED	0.03 - 0.16 FEET	VERY CLOSE	LESS THAN 0.16 FEET	THICKLY LAMINATED	0.008 - 0.03 FEET			THINLY LAMINATED	< 0.008 FEET																																																																																																																																																	
NON PLASTIC	PLASTICITY INDEX (PI)	DRY STRENGTH																																																																																																																																																																																																													
	0-5	VERY LOW																																																																																																																																																																																																													
SLIGHTLY PLASTIC	6-15	SLIGHT																																																																																																																																																																																																													
MODERATELY PLASTIC	16-25	MEDIUM																																																																																																																																																																																																													
HIGHLY PLASTIC	26 OR MORE	HIGH																																																																																																																																																																																																													
TERM	SPACING	TERM	THICKNESS																																																																																																																																																																																																												
VERY WIDE	MORE THAN 10 FEET	VERY THICKLY BEDDED	4 FEET																																																																																																																																																																																																												
WIDE	3 TO 10 FEET	THICKLY BEDDED	1.5 - 4 FEET																																																																																																																																																																																																												
MODERATELY CLOSE	1 TO 3 FEET	THINLY BEDDED	0.16 - 1.5 FEET																																																																																																																																																																																																												
CLOSE	0.16 TO 1 FOOT	VERY THINLY BEDDED	0.03 - 0.16 FEET																																																																																																																																																																																																												
VERY CLOSE	LESS THAN 0.16 FEET	THICKLY LAMINATED	0.008 - 0.03 FEET																																																																																																																																																																																																												
		THINLY LAMINATED	< 0.008 FEET																																																																																																																																																																																																												
<p style="text-align: center;">COLOR</p> <p>DESCRIPTIONS MAY INCLUDE COLOR OR COLOR COMBINATIONS (TAN, RED, YELLOW-BROWN, BLUE-BROWN). MODIFIERS SUCH AS LIGHT, DARK, STREAKED, ETC. ARE USED TO DESCRIBE APPEARANCE.</p>										<p style="text-align: center;">INDURATION</p> <p>FOR SEDIMENTARY ROCKS, INDURATION IS THE HARDENING OF MATERIAL BY CEMENTING, HEAT, PRESSURE, ETC.</p> <p>FRIABLE: RUBBING WITH FINGER FREES NUMEROUS GRAINS; GENTLE BLOW BY HAMMER DISINTEGRATES SAMPLE.</p> <p>MODERATELY INDURATED: GRAINS CAN BE SEPARATED FROM SAMPLE WITH STEEL PROBE; BREAKS EASILY WHEN HIT WITH HAMMER.</p> <p>INDURATED: GRAINS ARE DIFFICULT TO SEPARATE WITH STEEL PROBE; DIFFICULT TO BREAK WITH HAMMER.</p> <p>EXTREMELY INDURATED: SHARP HAMMER BLOWS REQUIRED TO BREAK SAMPLE; SAMPLE BREAKS ACROSS GRAINS.</p>																																																																																																																																																																																																					
<p style="text-align: center;">FRACATURE SPACING</p>										<p style="text-align: center;">BEDDING</p>										<p style="text-align: center;">BENCH MARK: N/A</p> <p style="text-align: right;">ELEVATION: FEET</p>																																																																																																																																																																																											
<p style="text-align: center;">NOTES:</p> <p>SURVEY AND ROADWAY DESIGN FILES PROVIDED BY TGS ENGINEERS ON 04/28/2022</p>										<p style="text-align: center;">INDURATION</p>										<p>SOIL, WEATHERED ROCK, AND CRYSTALLINE ROCK LINES ARE BASED ON AN INTERPRETATION OF BORE HOLE AND SEISMIC REFRACTION DATA AND SHALL BE CONSIDERED AS APPROXIMATE.</p>																																																																																																																																																																																											

SITE PLAN






Prepared in the Office of:




CAROLINAS
GEOTECHNICAL
GROUP



PROJECT REFERENCE NO.	SHEET NO.
A-0009CC	4
RETAINING WALL #23 & #24: SEISMIC REFRACTION LINE 23.1, 23.2, & 23.3 (PART) PROJECTED ALONG WALL ENVELOPES	

NOTE:
SOIL, WEATHERED ROCK, AND CRYSTALLINE ROCK
LINES ARE BASED ON AN INTERPRETATION OF
BORE HOLE AND SEISMIC REFRACTION DATA AND
SHALL BE CONSIDERED AS APPROXIMATE.




WALL ENVELOPE TAKEN FROM ROADWAY DESIGN PLANS PROVIDED BY TGS ENGINEERS
ON 04/28/22. APPROXIMATE EXISTING GROUND LINE AND INFERRED STRATIGRAPHY IS
DRAWN ALONG SEISMIC REFRACTION LINE 23.1, 23.2, AND 23.3 (PART)



Prepared in the Office of:




CAROLINAS
GEOTECHNICAL
GROUP



PROJECT REFERENCE NO.	SHEET NO.
A-0009CC	5
RETAINING WALL #24: SEISMIC REFRACTION LINE 23.3 (PART) & 23.4 PROJECTED ALONG WALL ENVELOPE	

NOTE:
 SOIL, WEATHERED ROCK, AND CRYSTALLINE ROCK
 LINES ARE BASED ON AN INTERPRETATION OF
 BORE HOLE AND SEISMIC REFRACTION DATA AND
 SHALL BE CONSIDERED AS APPROXIMATE.




**WALL ENVELOPE TAKEN FROM ROADWAY DESIGN PLANS PROVIDED BY TGS ENGINEERS
 ON 04/28/22. APPROXIMATE EXISTING GROUND LINE AND INFERRED STRATIGRAPHY IS
 DRAWN ALONG SEISMIC REFRACTION LINE 23.3 (PART) & 23.4,**

02-JUL-2022 14:25
 C:\Users\jriver\OneDrive - Carolines Geotechnical Group, PLLC\Projects\0068 - A-0009CC - Future US 74_TGS\A-0009CC\CADD\GEO\TECH\Site\Sub\A-0009CC.GEO_RWAL23_24_XSI.dgn
 \$\$\$USERNAME\$\$\$

SOIL TEST RESULTS


SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C. SAND	F. SAND	SILT	CLAY	10	40	200		
SS-8244	40' LT	448+50 -L-	3.5' - 5.0'	A-4(0)	28	NP	13	25	49	13	92	85	65	22	-

NOTE:
 SOIL, WEATHERED ROCK, AND CRYSTALLINE ROCK LINES ARE BASED ON AN INTERPRETATION OF BORE HOLE AND SEISMIC REFRACTION DATA AND SHALL BE CONSIDERED AS APPROXIMATE.




-L- EXISTING GROUND LINE TAKEN FROM ROADWAY DESIGN PLANS PROVIDED BY TGS ENGINEERS ON 04/28/22. INFERRED STRATIGRAPHY IS DRAWN THROUGH THE BORING OR SEISMIC REFRACTION LINE WITH BOTH PROJECTED ONTO THE CROSS SECTION


448 + 50.00



02-JUL-2022 14:25
C:\Users\jbriver\OneDrive - Carolines Geotechnical Group, PLLC\Projects\0068 - A-0009CC - Future US 74_TGS\A-0009CC\CADD\GEO\TECH\Site\Sub\A-0009CC.GEO_RWAL23.24_XSI.dgn




450 + 50.00




-L- EXISTING GROUND LINE TAKEN FROM ROADWAY DESIGN PLANS PROVIDED BY TGS ENGINEERS ON 04/28/22. INFERRED STRATIGRAPHY IS DRAWN THROUGH THE BORING OR SEISMIC REFRACTION LINE WITH BOTH PROJECTED ONTO THE CROSS SECTION

6/23/16
02-JUL-2022 14:25
C:\Users\jvibrer\OneDrive - Carolines Geotechnical Group, PLLC\Projects\0068 - A-0009CC - Future US 74_TGS\A-0009CC\CADD\GEO\TECH\Site\Sub\A-0009CC.GEO_RWAL.23.24.XSL.dgn
\$\$\$\$\$USERRNAME\$\$\$\$\$




6/23/16
02-JUL-2022 14:25
C:\Users\jvibrer\OneDrive - Carolines Geotechnical Group, PLLC\Projects\0068 - A-0009CC - Future US 74_TGS\A-0009CC\CADD_GEO\TECH\Site\Sub\A-0009CC_GEO_RWAL\23_24_XSI.dgn
\$\$\$\$\$USERRNAME\$\$\$\$\$




NOTE:
SOIL, WEATHERED ROCK, AND CRYSTALLINE ROCK
LINES ARE BASED ON AN INTERPRETATION OF
BORE HOLE AND SEISMIC REFRACTION DATA AND
SHALL BE CONSIDERED AS APPROXIMATE.

-L- EXISTING GROUND LINE TAKEN FROM ROADWAY DESIGN PLANS PROVIDED BY
TGS ENGINEERS ON 04/28/22. INFERRED STRATIGRAPHY IS DRAWN THROUGH THE BORING
OR SEISMIC REFRACTION LINE WITH BOTH PROJECTED ONTO THE CROSS SECTION

02-JUL-2022 14:25
C:\Users\jvibrer\OneDrive - Carolines Geotechnical Group, PLLC\Projects\0068 - A-0009CC - Future US 74_TGS\A-0009CC\CADD\GEO\TECH\Site\Sub\A-0009CC.GEO_RWAL23_24_XSI.dgn
\$\$\$\$\$USERRNAME\$\$\$\$\$



02-JUL-2022 14:25
C:\Users\jvibrer\OneDrive - Carolines Geotechnical Group, PLLC\Projects\0068 - A-0009CC - Future US 74_TGS\A-0009CC\CADD_GEO\TECH\Site\A-0009CC_GEO_RWAL23_24_XSI.dgn
\$\$\$\$\$USERRNAME\$\$\$\$\$



NOTE:
SOIL, WEATHERED ROCK, AND CRYSTALLINE ROCK
LINES ARE BASED ON AN INTERPRETATION OF
BORE HOLE AND SEISMIC REFRACTION DATA AND
SHALL BE CONSIDERED AS APPROXIMATE.

RWAL24_B-1
453+62
74' LT

- (47)
- (27)
- (49)
- (77)
- (50)
- (32)
- (60/0.0)

BT
DRY
06/21

EXISTING GROUND

LINE
23.3

CRYSTALLINE ROCK-
(META-SILTSTONE)

WEATHERED ROCK-
(META-SILTSTONE)

HARD, MOIST, TAN-ORANGE-BROWN,
SILTY FINE TO COARSE SAND (A-4),
WITH TRACE GRAVEL

FINE TO COARSE SANDY
ROCK FRAGMENTS

MEDIUM DENSE TO VERY DENSE,
SANDY COARSE SAND (A-2-4),
WITH TRACE GRAVEL

LOOSE, WET, TAN-ORANGE-BROWN,
SILTY FINE TO COARSE SAND (A-2-4),
WITH TRACE GRAVEL

RESIDUAL -
DENSE, DRY TO MOIST, TAN-GRAY-BROWN,
SILTY FINE TO COARSE SAND (A-2-4),
WITH LITTLE GRAVEL-SIZED ROCK FRAGMENTS

ROADWAY EMBANKMENT-


2:1

453 + 50.00




-L- EXISTING GROUND LINE TAKEN FROM ROADWAY DESIGN PLANS PROVIDED BY
TGS' ENGINEERS ON 04/28/22. INFERRED STRATIGRAPHY IS DRAWN THROUGH THE BORING
OR SEISMIC REFRACTION LINE WITH BOTH PROJECTED ONTO THE CROSS SECTION

6/23/16
02-JUL-2022 14:25
C:\Users\jvibrer\OneDrive - Carolines Geotechnical Group, PLLC\Projects\0068 - A-0009CC - Future US 74_TGS\A-0009CC\CADD\GEO\TECH\Site\A-0009CC.GEO_RWAL23_24_XSI.dgn
\$\$\$\$\$USERRNAME\$\$\$\$\$



6/23/16
02-JUL-2022 14:25
C:\Users\jriver\OneDrive - Carolines Geotechnical Group, PLLC\Projects\0068 - A-0009CC - Future US 74_TGS\A-0009CC\CADD_GEOTECH\Site\Sub\A-0009CC_GEO_RWAL\23.24_XSI.dgn
\$\$\$\$\$USERRNAME\$\$\$\$\$




NOTE:
SOIL, WEATHERED ROCK, AND CRYSTALLINE ROCK
LINES ARE BASED ON AN INTERPRETATION OF
BORE HOLE AND SEISMIC REFRACTION DATA AND
SHALL BE CONSIDERED AS APPROXIMATE.

-L- EXISTING GROUND LINE TAKEN FROM ROADWAY DESIGN PLANS PROVIDED BY
TGS' ENGINEERS ON 04/28/22. INFERRED STRATIGRAPHY IS DRAWN THROUGH THE BORING
OR SEISMIC REFRACTION LINE WITH BOTH PROJECTED ONTO THE CROSS SECTION


455 + 50.00
CL
-L-

02-JUL-2022 14:25
C:\Users\jbriver\OneDrive - Carolines Geotechnical Group, PLLC\Projects\0068 - A-0009CC - Future US 74_TGS\A-0009CC\CADD_GEO\TECH\Site\Sub\A-0009CC_GEO_RWAL\23_24_XSI.dgn




-L- EXISTING GROUND LINE TAKEN FROM ROADWAY DESIGN PLANS PROVIDED BY TGS ENGINEERS ON 04/28/22. INFERRED STRATIGRAPHY IS DRAWN THROUGH THE BORING OR SEISMIC REFRACTION LINE WITH BOTH PROJECTED ONTO THE CROSS SECTION

02-JUL-2022 14:25
C:\Users\jbriver\OneDrive - Carolines Geotechnical Group, PLLC\Projects\0068 - A-0009CC - Future US 74_TGS\A-0009CC\CADD\GEO\TECH\Site\A-0009CC.GEO_RWAL23_24_XSI.dgn
6/23/16



6/23/16
02-JUL-2022 14:25
C:\Users\jriver\OneDrive - Carolines Geotechnical Group, PLLC\Projects\0068 - A-0009CC - Future US 74_TGS\A-0009CC\CADD_GEO\TECH\Site\Sub\A-0009CC_GEO_RWAL\23_24_XS1.dgn
\$\$\$\$\$USERNAME\$\$\$\$\$



NOTE:
SOIL, WEATHERED ROCK, AND CRYSTALLINE ROCK
LINES ARE BASED ON AN INTERPRETATION OF
BORE HOLE AND SEISMIC REFRACTION DATA AND
SHALL BE CONSIDERED AS APPROXIMATE.

-L- EXISTING GROUND LINE TAKEN FROM ROADWAY DESIGN PLANS PROVIDED BY
TGS' ENGINEERS ON 04/28/22. INFERRED STRATIGRAPHY IS DRAWN THROUGH THE BORING
OR SEISMIC REFRACTION LINE WITH BOTH PROJECTED ONTO THE CROSS SECTION

GEOTECHNICAL BORING REPORT

BORE LOG

WBS 32572.1.FS10		TIP A-0009CC		COUNTY GRAHAM		GEOLOGIST C. Piercey										
SITE DESCRIPTION NC 143 from 0.5 Mi. North of AT to NC 28 & NC 28 from 0.2 Mi. West of NC 143 to 0.3 Mi. East of SR 1235							GROUND WTR (ft)									
BORING NO. RWAL23_B-1		STATION 448+50		OFFSET 40 ft LT		ALIGNMENT L										
COLLAR ELEV. 2,705.6 ft		TOTAL DEPTH 18.9 ft		NORTHING 623,649		EASTING 595,944										
DRILL RIGHAMMER EFF./DATE FIVE9553 CME-550X 80% 03/12/2021				DRILL METHOD H.S. Augers		HAMMER TYPE Automatic										
DRILLER J. Phillips		START DATE 05/11/21		COMP. DATE 05/11/21		SURFACE WATER DEPTH N/A										
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100						
2710																
2705	2,704.6	1.0	4	4	3										2,705.6	0.0
	2,702.1	3.5	2	1	3											
2700	2,699.6	6.0	3	8	12										2,700.1	5.5
	2,697.1	8.5	4	10	13											
2695																
	2,692.1	13.5	6	6	11											
2690	2,687.1	18.5													2,687.1	18.5
															2,686.7	18.9

WBS 32572.1.FS10		TIP A-0009CC		COUNTY GRAHAM		GEOLOGIST M. Brewer										
SITE DESCRIPTION NC 143 from 0.5 Mi. North of AT to NC 28 & NC 28 from 0.2 Mi. West of NC 143 to 0.3 Mi. East of SR 1235							GROUND WTR (ft)									
BORING NO. RWAL23_B-2		STATION 450+39		OFFSET 22 ft LT		ALIGNMENT L										
COLLAR ELEV. 2,690.1 ft		TOTAL DEPTH 23.7 ft		NORTHING 623,832		EASTING 595,893										
DRILL RIGHAMMER EFF./DATE CG29473 CME-550 79% 03/12/2021				DRILL METHOD H.S. Augers		HAMMER TYPE Automatic										
DRILLER J. Estep		START DATE 05/11/21		COMP. DATE 05/11/21		SURFACE WATER DEPTH N/A										
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100						
2695																
2690	2,689.1	1.0	15	17	18										2,690.1	0.0
	2,686.6	3.5	22	37	53											
2685	2,684.1	6.0	30	41	27											
	2,681.6	8.5	25	31	69/0.4											
2680																
	2,676.6	13.5	6	11	18											
2675	2,671.6	18.5	91	9/0.1											2,671.6	18.5
2670	2,666.6	23.5													2,666.6	23.7

NCDOT BORE DOUBLE A-0009CC_GEO_RDY_GTM.GPJ_NC_DOT.GDT 7/2/22

GEOTECHNICAL BORING REPORT

BORE LOG

WBS 32572.1.FS10		TIP A-0009CC		COUNTY GRAHAM		GEOLOGIST M. Brewer									
SITE DESCRIPTION NC 143 from 0.5 Mi. North of AT to NC 28 & NC 28 from 0.2 Mi. West of NC 143 to 0.3 Mi. East of SR 1235							GROUND WTR (ft)								
BORING NO. RWAL23_B-3		STATION 452+12		OFFSET 65 ft LT		ALIGNMENT L									
COLLAR ELEV. 2,695.9 ft		TOTAL DEPTH 15.1 ft		NORTHING 623,978		EASTING 595,791									
DRILL RIGHAMMER EFF./DATE CG29473 CME-550 79% 03/12/2021				DRILL METHOD H.S. Augers		HAMMER TYPE Automatic									
DRILLER J. Estep		START DATE 05/11/21		COMP. DATE 05/11/21		SURFACE WATER DEPTH N/A									
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)	DEPTH (ft)
2700															
2695	2,695.9	0.0	18	20	32									2,695.9	GROUND SURFACE 0.0
	2,692.4	3.5	13	18	13										RESIDUAL Dense to Very Dense, Tan-Gray-Brown, Silty Fine to Coarse SAND (A-2-4), with trace gravel-sized rock fragments
2690	2,689.9	6.0	14	28	24										
	2,687.4	8.5	17	18	21										
2685	2,682.4	13.5	100/0.4											2,682.4	
	2,680.8	15.1	60/0.0											2,680.8	15.1
															WEATHERED ROCK Gray-Tan, (META-SILTSTONE) Boring Terminated with Standard Penetration Test Refusal at Elevation 2,680.8 ft On Crystalline Rock (META-SILTSTONE)

WBS 32572.1.FS10		TIP A-0009CC		COUNTY GRAHAM		GEOLOGIST N. McLaren									
SITE DESCRIPTION NC 143 from 0.5 Mi. North of AT to NC 28 & NC 28 from 0.2 Mi. West of NC 143 to 0.3 Mi. East of SR 1235							GROUND WTR (ft)								
BORING NO. RWAL24_B-1		STATION 453+62		OFFSET 74 ft LT		ALIGNMENT L									
COLLAR ELEV. 2,706.1 ft		TOTAL DEPTH 21.4 ft		NORTHING 624,115		EASTING 595,728									
DRILL RIGHAMMER EFF./DATE CG20446 Diedrich D50 76% 06/14/2021				DRILL METHOD H.S. Augers		HAMMER TYPE Automatic									
DRILLER C. Odom		START DATE 06/17/21		COMP. DATE 06/17/21		SURFACE WATER DEPTH N/A									
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)	DEPTH (ft)
2710															
2705	2,705.1	1.0	10	31	16									2,706.1	GROUND SURFACE 0.0
	2,702.6	3.5	11	12	15										RESIDUAL Medium Dense to Very Dense, Tan-Gray-Brown, Silty Fine to Coarse SAND (A-2-4), with little gravel-sized rock fragments
2700	2,700.1	6.0	18	21	28										
	2,697.6	8.5	17	32	45										
2695	2,692.6	13.5	20	20	30										
2690	2,687.6	18.5	18	19	13										
2685	2,684.7	21.4	60/0.0											2,684.7	21.4
															Boring Terminated with Standard Penetration Test Refusal at Elevation 2,684.7 ft On Crystalline Rock (META-SILTSTONE)

NCDOT BORE DOUBLE A-0009CC_GEO_RDY_GTM.GPJ_NC_DOT.GDT 7/2/22

GEOTECHNICAL BORING REPORT


BORE LOG

WBS 32572.1.FS10		TIP A-0009CC		COUNTY GRAHAM		GEOLOGIST C. Piercey										
SITE DESCRIPTION NC 143 from 0.5 Mi. North of AT to NC 28 & NC 28 from 0.2 Mi. West of NC 143 to 0.3 Mi. East of SR 1235							GROUND WTR (ft)									
BORING NO. RWAL24_B-2		STATION 455+00		OFFSET 30 ft LT		ALIGNMENT L										
COLLAR ELEV. 2,662.5 ft		TOTAL DEPTH 18.9 ft		NORTHING 624,265		EASTING 595,724										
DRILL RIGHAMMER EFF./DATE FIVE9553 CME-550X 80% 03/12/2021				DRILL METHOD H.S. Augers		HAMMER TYPE Automatic										
DRILLER J. Phillips		START DATE 05/11/21		COMP. DATE 05/11/21		SURFACE WATER DEPTH N/A										
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100						
2665																
2660	2,661.5	1.0	4	13	15									2,662.5	0.0	GROUND SURFACE
	2,659.0	3.5	11	20	24											RESIDUAL Medium Dense to Dense, Gray, Silty Fine to Coarse SAND (A-2-4), with trace gravel-sized rock fragments
2655	2,656.5	6.0	9	52	48/0.1											
	2,654.0	8.5	66	34/0.1										2,656.0	6.5	WEATHERED ROCK Gray-Brown, (META-SANDSTONE)
2650	2,649.0	13.5														
	2,644.0	18.5														
2645	2,644.0	18.5														Boring Terminated at Elevation 2,643.6 ft In Weathered Rock (META-SANDSTONE)

WBS 32572.1.FS10		TIP A-0009CC		COUNTY GRAHAM		GEOLOGIST C. Piercey										
SITE DESCRIPTION NC 143 from 0.5 Mi. North of AT to NC 28 & NC 28 from 0.2 Mi. West of NC 143 to 0.3 Mi. East of SR 1235							GROUND WTR (ft)									
BORING NO. RWAL24_B-3		STATION 456+25		OFFSET 40 ft LT		ALIGNMENT L										
COLLAR ELEV. 2,651.1 ft		TOTAL DEPTH 18.8 ft		NORTHING 624,395		EASTING 595,698										
DRILL RIGHAMMER EFF./DATE FIVE9553 CME-550X 80% 03/12/2021				DRILL METHOD H.S. Augers		HAMMER TYPE Automatic										
DRILLER J. Phillips		START DATE 05/11/21		COMP. DATE 05/11/21		SURFACE WATER DEPTH N/A										
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100						
2655																
2650	2,650.1	1.0	7	27	41									2,651.1	0.0	GROUND SURFACE
	2,647.6	3.5	13	12	13											RESIDUAL Medium Dense to Very Dense, Gray-Brown, Silty Fine to Coarse SAND (A-2-4), with trace gravel-sized rock fragments
2645	2,645.1	6.0	5	52	48/0.2											
	2,642.6	8.5												2,644.6	6.5	WEATHERED ROCK Gray, (META-SANDSTONE)
2640	2,637.6	13.5														
2635	2,632.6	18.5														
	2,632.6	18.5														Boring Terminated at Elevation 2,632.3 ft In Weathered Rock (META-SANDSTONE)

NCDOT BORE DOUBLE A-0009CC_GEO_RDY_GTM.GPJ_NC_DOT.GDT 7/2/22

GEOPHYSICAL TEST RESULTS – SEISMIC REFRACTION LINE 23.1




GEOPHYSICAL TESTING PERFORMED BY GEL SOLUTIONS. REFERENCE "SEISMIC REFRACTION SURVEY FOR EVALUATION OF ROCK" DATED 10/01/2021

CG2 ESTIMATED WAVE SPEED FOR WEATHERED ROCK: 4,500 FT/SEC

CG2 ESTIMATED WAVE SPEED FOR CRYSTALLINE ROCK: 7,500 FT/SEC

GEOPHYSICAL TEST RESULTS – SEISMIC REFRACTION LINE 23.2




GEOPHYSICAL TESTING PERFORMED BY GEL SOLUTIONS. REFERENCE "SEISMIC REFRACTION SURVEY FOR EVALUATION OF ROCK" DATED 10/01/2021

CG2 ESTIMATED WAVE SPEED FOR WEATHERED ROCK: 4,500 FT/SEC

CG2 ESTIMATED WAVE SPEED FOR CRYSTALLINE ROCK: 7,500 FT/SEC

GEOPHYSICAL TEST RESULTS – SEISMIC REFRACTION LINE 23.3




GEOPHYSICAL TESTING PERFORMED BY GEL SOLUTIONS. REFERENCE "SEISMIC REFRACTION SURVEY FOR EVALUATION OF ROCK" DATED 10/01/2021

CG2 ESTIMATED WAVE SPEED FOR WEATHERED ROCK: 4,500 FT/SEC

CG2 ESTIMATED WAVE SPEED FOR CRYSTALLINE ROCK: 7,500 FT/SEC

GEOPHYSICAL TEST RESULTS – SEISMIC REFRACTION LINE 23.4



GEOPHYSICAL TESTING PERFORMED BY GEL SOLUTIONS. REFERENCE "SEISMIC REFRACTION SURVEY FOR EVALUATION OF ROCK" DATED 10/01/2021

CG2 ESTIMATED WAVE SPEED FOR WEATHERED ROCK: 4,500 FT/SEC

CG2 ESTIMATED WAVE SPEED FOR CRYSTALLINE ROCK: 7,500 FT/SEC