90/6

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

PROJECT REFERENCE NO.SHEET NO.R-57683B-3

RKK

86Ò1 Six Forks Road, Forum 1,Suite 700 Raleigh, North Carolina 27615-3960 NC License No. F-0112

Responsive People | Creative Solutions

Engineers | Construction Managers | Planners | Scientists

PAVEMENT REMOVAL SUMMARY

IN SQUARE YARDS

LINE	STATION	STATION	LOCATION	AREA	WIDTH	SQUARE YARDS
-L-	12+00	19+00	RT	14,305.92		1,589.55
-L-	19+25	23+50	RT	15,671.56		1,741.28
-L-	23+80	24+70	RT	2,171.15		241.24
-L-	25+05	27+10	RT	698.07		77.56
-Y1-	11+35	13+00	RT	6,360.89		706.77
-Y1-	16+50	16+50	RT/LT	2,807.59		311.95
-Y1-	19+95	61+99	LT	6,198.61		688.73
-Y1A-	11+00	12+10	RT	1,184.70		131.63
-Y1A-	14+60	19+46	CL	16,589.64		1,843.29
					TOTAL	7,332.01
					SAY	7,340

2'6" CURB & GUTTER

IN LINEAR FEET

PROJECT NO.: R-5768 COMPUTED BY: CAM CHECKED BY: JMH REVISED BY: CAM				SHEET 1 OF 1
		8/12/2022		
		8/12/2022		SECT. 846
		10/13/2022		
	2'6"	Curb and Gu	tter	
LINE	STATION	STATION	SIDE	LENGTH
L	19+75.00	21+57.09	LT	177.3
L	22+05.32	27+30.17	LT	514.1
L	20+25.55	23+28.18	RT	310.5
L	24+02.26	24+47.72	RT	46.4
L	25+27.24	27+67.57	RT	244.4
L	Drive radii	21+80	LT	48.1
L	Drive radii	24+00	RT	145.1
L	Y1 Intersection Radii	19+65.00	RT	130.3
Y1	13+33.00	21+86.00	RT	853.3
Y1	11+48.00	18+41.40	LT	682.7
Y1	20+47.17	22+62.81	LT	218.9
Y1	Drive Radii	21+90, 22+80	RT/LT	71.7
Y1	11+48, Y2 Radii	Y2 Radii, 12+80	RT	376.1
Y1	Y1A Intersection Radii	19+75.00	LT	344.4
			TOTAL	4,163.1
			SAY	4,170

PAVEMENT BREAKING SUMMARY

IN SQUARE YARDS

LINE	STATION	STATION	LOCATION	AREA	WIDTH	SQUARE YARDS
-Y1-	10+30	11+25	CL	3669.21		407.69
<u> </u>					TOTAL	407.69
					SAY	410

SHOULDER BERM GUTTER

IN LINEAR FEET

LINE	STATION	STATION	SIDE	LENGTH
L	27+30	27+65	LT	34.8
			TOTAL	34.8
			SAY	35

|///2022 |R:\Roadway\Proj\R-5768_rdy_pshØ3B-; |defailt