PROJECT REFERENCE NO.	SHEET NO.
BR-0070	EC-3
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

SOIL STABILIZATION SUMMARY SHEET

MATTING FOR EROSION CONTROL (EXCELSIOR)

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
4	-L-	15+00	16+40	RT	210
5	-L-	21+50	22+00	RT	45
			SUBTOTAL		255

MATTING FOR EROSION CONTROL (STRAW)

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	
4/5	-L-	20+50	28+00	LT	610
5	-L-	28+00	28+70	LT	60
5	-L-	22+00	22+50	RT	45
5	-L-	35+35	37+00	LT	135
5/6	-L-	37+00	40+50	LT	285
			SUBTOTAL		1,135
MISCELLANEOUS MATTING TO BE INSTALLED AS DIRECTED BY THE ENGINEER					11,920
				TOTAL	13,310
				SAY	13,310

PERMANENT SOIL REINFORCEMENT MAT

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
6	-L-	41+50	43+00	RT	125
6	-L-	43+00	43+80	RT	65
			SUBTOTAL		190
		ADDITIONAL PSRM TO BE INSTALLED			0
				TOTAL	190
				SAY	190