
+

+



 BENT	2	

(EAST	FACE)

	-	01/2022]
DESIGN ENGINEER OF RECORD: DIEGO A. AGUIRRE_ DATE		<u>01/2022</u> <u>01/2022</u>	

	LEGEND	
BEAM A	CONCRETE REPAIR AREA (CR)	
	SHOTCRETE REPAIR AREA (SCR)	SHO
	EPOXY RESIN INJECTION (ERI)	
J.7 SF SCR		
		CON
		EPO
		V A UN T C
		N RE IN AF DF
		A١

DOCUMENT	NOT	СО
FINAL	UNL	ESS
SIGNATU	RES	CON

AS-BUILT REPAIR QUANTITY TABLE				
	QUANTITIES			
	ESTIMATE ACTU		UAL	
HOTCRETE REPAIRS	AREA SQ.FT.	VOLUME CU.FT.	AREA SQ.FT.	VOLUME CU.FT.
CAP/BACKWALL	25.1	8.5		
COLUMN/PILE	1.0	0.5		
ONCRETE REPAIRS	AREA SQ.FT.	VOLUME CU.FT.	AREA SQ.FT.	VOLUME CU.FT.
САР	_	_		
POXY RESIN INJECTION	LIN.FT.		LIN.FT.	
CAP/BACKWALL	-	-		
COLUMN/PILE				

VALUES IN CHART REPRESENT ESTIMATED REPAIR TOTALS AFTER REMOVAL OF UNSOUND CONCRETE.MINIMUM OF 1"BEHIND REBAR AND MINIMUM 2"CLEARANCE TO SAWCUT.FOR REPAIR DETAILS, SEE "CONCRETE RESTORATION DETAILS" SHEETS.

NOTES:

REPAIR LOCATIONS AND ESTIMATED QUANTITIES ARE GIVEN WITH THE BEST INFORMATION AVAILABLE. IF ADDITIONAL REPAIRS NOT SHOWN ON THE DRAWINGS ARE DEEMED NECESSARY BY THE ENGINEER, THE ENGINEER WILL NOTE ON THE DRAWINGS THE APPROXIMATE LOCATIONS AND DESCRIPTION OF THE REPAIRS AND ADJUST THE ACTUAL QUANTITIES ENTERED INTO THE TABLE ABOVE.

CRACKING LOCATIONS AND QUANTITIES FOR LOCATIONS DESCRIBED AS "SCATTERED THROUGHOUT" IN THE INSPECTION REPORT ARE BASED ON THE BEST INFORMATION AVAILABLE. THE ENGINEER AND CONTRACTOR SHALL IDENTIFY AND REPAIR ALL CRACKS >=1/16" AS DESCRIBED IN THE SPECIAL PROVISIONS AT EACH BENT.

AVERAGE CONCRETE COVER IS EXPECTED TO BE FROM 2"TO 3" ON THE CAP AND FROM $1\frac{1}{2}$ "TO 2" ON THE PILES. ACTUAL CONCRETE COVER SHALL BE DETERMINED BY THE CONTRACTOR AND PRESENTED TO THE ENGINEER PRIOR TO BEGINNING EXCAVATION/ DEMOLITION.

FOR CONCRETE AND SHOTCRETE REPAIRS, SEE "CONCRETE RESTORATION DETAILS" SHEETS.

SHOTCRETE REPAIRS MAY BE REPLACED WITH CONCRETE REPAIRS WITH THE APPROVAL OF THE ENGINEER.

REPAIRS TO THE BENT CAP MAY REQUIRE BRIDGE JACKING.FOR BRIDGE JACKING,SEE SPECIAL PROVISIONS.

	bridge no. <u>170177</u>	} JNTY
	SHEET 3 OF 4	
Docusigned by SEAL Dicao & AAAUVVC 4729/2022	STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTAT RALEIGH SUBSTRUCTURE REPAIRS	ION
KCA	BENT 2	
KISINGER CAMPO	REVISIONS	SHEET NO.
& ASSOCIATESONSIDERED301 FAYETTEVILLE ST., SUITE 1500	NO. BY: DATE: NO. BY: DATE:	S3-1Ø
S ALLRALEIGH, NC 27601 (919) 882-7839MPLETEDNC FIRM LICENSE: C-1506	1 3 2 4	total sheets 11