

# AS-BUILT REPAIR QUANTITY TABLE

	ESTIMATE	ACTUAL
INCIDENTAL MILLING	1518 SY	
ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5C	213 TON	
ASPHALT BINDER FOR PLANT MIX	12.8 TON	

## NOTES:


INCIDENTAL MILLING - EXISTING APPROACH ASPHALT PAVEMENT TO BE MILLED AS NECESSARY TO ATTAIN MINIMUM 1/2" DEPTH OF NEW ASPHALT PAVEMENT. NEW ASPHALT PAVEMENT SHALL BE OF THICKNESS NECESSARY TO PROVIDE A SMOOTH TRANSITION BETWEEN THE ROADWAY AND THE BRIDGE DECK. THE NEW ASPHALT PAVEMENT THICKNESS MAY EXCEED 1/2" DUE TO SETTLEMENT OF THE EXISTING APPROACH.

FOR NEW ASPHALT PLACEMENT, SEE STANDARD SPECIFICATIONS.


GRADE MAY BE ADJUSTED BY THE ENGINEER TO ENSURE PROPER TIE-IN AT THE END BENTS.

C1	PROPOSED VARIABLE DEPTH ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5C AT AN AVERAGE RATE OF 112 LBS. PER SQ. YD. PER 1" DEPTH. TO BE PLACED IN LAYERS NOT LESS THAN 1" OR GREATER THAN 2" IN DEPTH.
----	---


INCIDENTAL MILLING




ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5C (C1)




BEGIN APPROACH SLAB



END APPROACH SLAB




PAVEMENT KEY-IN DETAIL FOR BOTH END BENTS



ROADWAY SECTION  
BEGIN/END BRIDGE

PROJECT NO. I-5915B  
IREDELL COUNTY  
 BRIDGE NO. 480066



STATE OF NORTH CAROLINA  
 DEPARTMENT OF TRANSPORTATION  
 RALEIGH  
**APPROACH ROADWAY**  
**ASPHALT MILLING**

DRAWN BY :	FIDEL L. FLORES	DATE :	01/2022
CHECKED BY :	JACOB H. DUKE	DATE :	01/2022
DESIGN ENGINEER OF RECORD:	DIEGO A. AGUIRRE	DATE :	01/2022

4/21/2022  
 I5915B.SMU.AR01.480066.dgn  
 daquirre

DOCUMENT NOT CONSIDERED  
 FINAL UNLESS ALL  
 SIGNATURES COMPLETED

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			S10-6
2			4			TOTAL SHEETS 12