PROJ. REFERENCE NO.	SHEET NO.
BR-0094	X-1A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Approximate quantities only. Unclassified excavation, borrow excavation, fine grading, clearing and grubbing, breaking of existing pavement and removal of existing pavement will be paid for at the lump sum price for "Grading".

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Station RPC	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
15+50.00	0	0	10+14.14	0	0
16+00.00	64	19	10+25.00	0	22
16+50.00	63	16	10+50.00	0	40
17+00.00	7	5	10+75.00	0	26
17+50.00	2	22	11+00.00	0	23
18+00.00	1	109	11+25.00	0	25
18+50.00	0	260	11+50.00	2	24
19+00.00	0	587	11+75.00	3	19
19+26.70	0	448	12+00.00	4	14

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Station RPD	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
21+48.70	0	0	12+00.00	0	0
21+50.00	0	13	12+25.00	6	5
22+00.00	0	547	12+50.00	6	7
22+50.00	0	538	12+75.00	3	12
23+00.00	0	430	13+00.00	1	25
23+50.00	1	240	13+25.00	0	45
24+00.00	2	47	13+50.00	0	72
24+50.00	2	15	13+75.00	1	71
25+00.00	1	21	13+94.40	1	41
25+50.00	2	25			
26+00.00	9	28			

Station RPA	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
15+25.00	0	0
15+50.00	2	11
15+75.00	3	8
16+00.00	2	4
16+17.59	1	3

Station RPB	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+13.77	0	0
10+25.00	63	4
10+50.00	90	10
10+75.00	21	12
11+00.00	5	12
11+25.00	6	10