


BAGGED STONE AND PIPE SHALL BE PLACED IMMEDIATELY AFTER COMPLETION OF END BENT EXCAVATION. PIPE MAY BE EITHER CONCRETE, CORRUGATED STEEL, CORRUGATED ALUMINUM ALLOY, OR CORRUGATED PLASTIC. PERFORATED PIPE WILL NOT BE ALLOWED.

BAGGED STONE SHALL REMAIN IN PLACE UNTIL THE ENGINEER DIRECTS THAT IT BE REMOVED. THE CONTRACTOR SHALL REMOVE AND DISPOSE OF SILT ACCUMULATIONS AT BAGGED STONE WHEN SO DIRECTED BY THE ENGINEER. BAGS SHALL BE REMOVED AND REPLACED WHENEVER THE ENGINEER DETERMINES THAT THEY HAVE DETERIORATED AND LOST THEIR EFFECTIVENESS.

NO SEPARATE PAYMENT WILL BE MADE FOR THIS WORK AND THE ENTIRE COST OF THIS WORK SHALL BE INCLUDED IN THE UNIT CONTRACT PRICE BID FOR THE SEVERAL PAY ITEMS.


## TEMPORARY DRAINAGE AT END BENT





△ POSITION OF PILE DURING WELDING.

DETAIL B

## PILE SPLICE DETAILS







PROJECT NO. BR-0094

ROCKINGHAM COUNTY

STATION: 20+38.70 -L-

SHEET 3 OF 3

SEAL 36871 STATE OF NORTH CAROLINA

DEPARTMENT OF TRANSPORTATION

RALEIGH

SUBSTRUCTURE

END BENT 2

Francisca Lea

B79DADB65D584EF...

11/16/2022

REVISIONS

SHEET NO

DOCUMENT NOT CONSIDERED
FINAL UNLESS ALL
SIGNATURES COMPLETED

REVISIONS

SHEET NO

BY: DATE: NO. BY: DATE: S-27

TOTAL SHEETS
30

DRAWN BY: Q. T. NGUYEN DATE: 08/2022
CHECKED BY: F. LEA DATE: 09/2022
DESIGN ENGINEER OF RECORD: F. LEA DATE: 09/2022

11/10/2022 R:\Structures\Plans\401\_051\_BR0094\_SMU\_E\*2\_S27\_780069.dgn ttnguyen1