

PROJECT NO.	SHEET NO.	TOTAL NO.
I-5955	7	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	1297000000-E			1330000000-E	1503000000-E	1524200000-E	1575000000-E	1577000000-E	1662000000-E	1840000000-E	4424000000-N	4434000000-N	4600000000-N	5255000000-N	7444000000-E	
												MILLING ASPHALT PAVEMENT, 2" DEPTH	MILLING ASPHALT PAVEMENT, 1-1/2" DEPTH	MILLING ASPHALT PAVEMENT, 4" DEPTH	INCIDENTAL MILLING	ASPHALT CONC INTERMEDIATE, TYPE I19.0C	ASPHALT CONC SURFACE COURSE, TYPE S9.5D	ASPHALT BINDER FOR PLANT MIX	POLYMER MODIFIED ASPHALT BINDER FOR PLANT MIX	OPEN-GRADED ASPHALT FRICTION	MILLED RUMBLE STRIPS	WORK ZONE PRESENCE LIGHTING	SEQUENTIAL FLASHING WARNING LIGHTS	CONNECTED LANE CLOSURE DEVICE	PORTABLE LIGHTING	INDUCTIVE LOOP SAW CUT	
										MI	FT	SY	SY	SY	SY	TON	TON	TON	TON	TON	LF	EA	EA	EA	LS	LF	
45908.3.1	Guilford	1	I-40 EB	I-40 EB FROM BRIDGE OVER BUFFALO CREEK TO JOINT EAST OF EAST GATE CITY BLVD/E LEE ST	1	3		NO	NO	5.315	45	175,101		6,522		19,697		1,510	5,897	53,040							
TOTAL FOR MAP NO. 1											5.315		175,101		6,522		19,697		1,510	5,897	53,040						
45908.3.1	Guilford	2	RAMP TO BUS 85 SB	I-40 EB RAMP TO BUS 85 SB	2	1		NO	NO	0.058	22		832			72		5									
TOTAL FOR MAP NO. 2											0.058			832			72		5								
45908.3.1	Guilford	3	BUS 85 NB	BUS 85 NB TO I-40 EB	3	2		NO	NO	0.177	31	5,516		537		621		50	179	930							
TOTAL FOR MAP NO. 3											0.177		5,516		537		621		50	179	930						
45908.3.1	Guilford	4	BUS 85 NB RAMP TO RANDLEMAN RD	BUS 85 NB RAMP TO RANDLEMAN RD	2,8,13	1		NO	NO	0.08	29		1,360			115		10								450	
TOTAL FOR MAP NO. 4											0.08			1,360			115		10						450		
45908.3.1	Guilford	5	I-40 EB RAMP TO RANDLEMAN RD	I-40 EB RAMP TO RANDLEMAN RD	2,4	1		NO	NO	0.139	27		2,426			205		15								400	
TOTAL FOR MAP NO. 5											0.139			2,426			205		15						400		
45908.3.1	Guilford	6	W PREDDY BLVD/RANDLEMAN RD RAMP TO I-40 EB	W PREDDY BLVD/RANDLEMAN RD RAMP TO I-40 EB	2,4,6	1		NO	NO	0.194	19		3,890			330		20								450	
TOTAL FOR MAP NO. 6											0.194			3,890			330		20						450		
45908.3.1	Guilford	6A	I-40 EB RAMP TO S ELM-EUGENE ST	I-40 EB RAMP TO S ELM-EUGENE ST	7,8	1		NO	NO	0.077	26		1,655			140		10								650	
TOTAL FOR MAP NO. 6A											0.077			1,655			140		10						650		
45908.3.1	Guilford	7	S ELM-EUGENE ST RAMP TO I-40 EB	S ELM-EUGENE ST RAMP TO I-40 EB	8	1		NO	NO	0.092	21		1,296			110		10									
TOTAL FOR MAP NO. 7											0.092			1,296			110		10								
45908.3.1	Guilford	8	I-40 EB OFF RAMP TO MLK JR DR	I-40 EB OFF RAMP TO MLK JR DR	8,9	1		NO	NO	0.152	28		3,684			312		20								650	
TOTAL FOR MAP NO. 8											0.152			3,684			312		20						650		
45908.3.1	Guilford	9	MAP DELETED	MAP DELETED				NO	NO	0	0															650	
TOTAL FOR MAP NO. 9											0														650		
45908.3.1	Guilford	10	MLK JR DR RAMP TO I-40 EB	MLK JR DR RAMP TO I-40 EB	10	2		NO	NO	0.365	27	6,974				789		50									
TOTAL FOR MAP NO. 10											0.365		6,974				789		50								
45908.3.1	Guilford	11	MAP DELETED	MAP DELETED				NO	NO	0	0																
TOTAL FOR MAP NO. 11											0																
45908.3.1	Guilford	12	I-40 EB RAMP TO E GATE CITY BLVD/E LEE ST	I-40 EB RAMP TO E GATE CITY BLVD/E LEE ST	2	1		NO	NO	0.258	24		3,806			322		20								425	
TOTAL FOR MAP NO. 12											0.258			3,806			322		20						425		
45908.3.1	Guilford	13	E GATE CITY BLVD/E LEE ST RAMP TO I-40 EB	E GATE CITY BLVD/E LEE ST RAMP TO I-40 EB	5	1		NO	NO	0.316	33			3,054	436	258	25	15			28	24	4	1			
TOTAL FOR MAP NO. 13											0.316				3,054	436	258	25	15			28	24	4	1		
45908.3.1	Guilford	14	I-40 WB	I-40 WB FROM JOINT EAST OF GATE CITY BLVD TO BRIDGE OVER BUFFALO CREEK	1	3		NO	NO	4.9	35	176,605		4,625		19,864		1,495	5,466	53,790							
TOTAL FOR MAP NO. 14											4.9		176,605		4,625		19,864		1,495	5,466	53,790						
45908.3.1	Guilford	15	I-40 WB RAMP TO E GATE CITY BLVD	I-40 WB RAMP TO E GATE CITY BLVD	2,11	1		NO	NO	0.128	29		2,768			234		15									
TOTAL FOR MAP NO. 15											0.128			2,768			234		15								
45908.3.1	Guilford	16	E GATE CITY BLVD RAMP TO I-40 WB	E GATE CITY BLVD RAMP TO I-40 WB	2	1		NO	NO	0.068	25		1,131			96		10									
TOTAL FOR MAP NO. 16											0.068			1,131			96		10								
45908.3.1	Guilford	17	I-40 WB RAMP TO MLK JR DR	I-40 WB RAMP TO MLK JR DR	2,8,12	1		NO	NO	0.259	35		4,976			422		25		640							
TOTAL FOR MAP NO. 17											0.259			4,976			422		25		640						
45908.3.1	Guilford	18	US 29 SB TO I-40 WB	US 29 SB TO I-40 WB	10	2		NO	NO	0.12	34	3,068		675		347		25	63	760							
TOTAL FOR MAP NO. 18											0.12		3,068		675		347		25	63	760						
45908.3.1	Guilford	19	US 29 SB RAMP TO MLK JR DR	US 29 SB RAMP TO MLK JR DR	2,4	1		NO	NO	0.403	25		7,658			648		40		425							
TOTAL FOR MAP NO. 19											0.403		7,658				648		40		425						
45908.3.1	Guilford	20	MLK JR DR RAMP TO I-40 WB	MLK JR DR RAMP TO I-40 WB	2,13	1		NO	NO	0.098	20		1,266			108		10		425							
TOTAL FOR MAP NO. 20											0.098		1,266				108		10		425						
45908.3.1	Guilford	21	I-40 WB RAMP TO S ELM-EUGENE ST	I-40 WB RAMP TO S ELM-EUGENE ST	2,13	1		NO	NO	0.121	21		1,479			159		10								300	
TOTAL FOR MAP NO. 21											0.121			1,479			159		10						300		
45908.3.1	Guilford	22	S ELM-EUGENE ST RAMP TO I-40 WB	S ELM-EUGENE ST RAMP TO I-40 WB	2,13	1		NO	NO	0.108	26		1,995			169		10									
TOTAL FOR MAP NO. 22											0.108			1,995			169		10								
45908.3.1	Guilford	22A	S ELM-EUGENE ST RAMP TO I-40 WB	I-40 WB RAMP TO RANDLEMAN RD	7	1		NO	NO	0.103	20		1,273			108		10								1,000	
TOTAL FOR MAP NO. 22A											0.103			1,273			108		10						1,000		
45908.3.1	Guilford	23	RANDLEMAN RD RAMP TO I-40 WB	RANDLEMAN RD RAMP TO I-40 WB	2,14	1		NO	NO	0.286	22		4,206			357		25									
TOTAL FOR MAP NO. 23											0.286			4,206			357		25								
45908.3.1	Guilford	24	RANDLEMAN RD RAMP TO BUS 85 SB	RANDLEMAN RD RAMP TO BUS 85 SB	2,15	1		NO	NO	0.239	18		3,130			266		20									
TOTAL FOR MAP NO. 24											0.239			3,130			266		20								
45908.3.1	Guilford	25	BUS 85 SB	I-40 WB TO BUS 85 SB	3	2		NO	NO	0.066	38	1,892		493		213		20	54	525							
TOTAL FOR MAP NO. 25											0.066		1,892		493		213		20	54	525						
TOTAL FOR PROJ NO. 45908.1.1											14.122		369,156	48,831	3,054	12,852	436	45,962	25	3,450	11,659	109,685	28	24	4	1	4,750
GRAND TOTAL											14.122		369,156	48,831	3,054	12,852	436	45,962	25	3,450	11,659	109,685	28	24	4	1	4,750