

PROJECT NO.	SHEET NO.	TOTAL NO.
2023CPT.08.14.20621	9	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	1245000000-E	1260000000-E	1330000000-E	1519000000-E	1575000000-E	1704000000-E	2830000000-N	2845000000-N	
												SHOULDER RECONSTRUCTION	AGGREGATE SHOULDER BORROW	INCIDENTAL MILLING	SURFACE COURSE, \$9.5B	ASPHALT BINDER FOR PLANT MIX	PATCHING EXISTING PAVEMENT	ADJUST MANHOLES	ADJUST METER OR VALVE BOX	
												MI	FT	SMI	TON	SY	TONS	TONS	TONS	EA
2023CPT.08.14.20621	Montgomery	1	SR 1005 (PEKIN RD)	FROM SR 1565 (ONVIL RD) TO SR SR 1516 (MCCALLUM RD)	1	2	2WU	NO	NO	0.82	20	1.64	230.00	333	879	60	15			
TOTAL FOR MAP NO. 1											0.82	20	1.64	230.00	333	879	60	15		
2023CPT.08.14.20621	Montgomery	2	SR 1565 (ONVIL RD)	FROM SR 1568 (BLAKE LOOP EXT.) TO SR 1005 (PEKIN RD)	1	2	2WU	NO	NO	1.35	21	2.70	378.00	642	1,518	104	40			
TOTAL FOR MAP NO. 2											1.35	21	2.70	378.00	642	1,518	104	40		
2023CPT.08.14.20621	Montgomery	3	SR 1541 (BOWLES RD)	FROM SR 1540 (VALLEY VIEW CHURCH RD) TO NC731	1	2	2WU	NO	NO	1.48	16	2.96	414.00	178	1,271	88	50			
TOTAL FOR MAP NO. 3											1.48	16	2.96	414.00	178	1,271	88	50		
2023CPT.08.14.20621	Montgomery	4	SR 1551 (OSCAR RD)	FROM SR 1630 (COVINGTON RD) TO NC 24/NC 109	1	2	2WU	NO	NO	0.43	18	0.86	120.00	200	415	29	15		1	
TOTAL FOR MAP NO. 4											0.43	18	0.86	120.00	200	415	29	15		1
2023CPT.08.14.20621	Montgomery	5	SR 1553 (ROSLYN RD)	FROM SR 1554 (TAFT ST/TROY-CANDOR RD) TO END OF PAVEMENT	1	2	2WU	NO	NO	0.76	20	1.52	213.00	111	814	55	10	1		
TOTAL FOR MAP NO. 5											0.76	20	1.52	213.00	111	814	55	10	1	
TOTAL FOR PROJ NO. 2023CPT.08.14.20621											4.84	9.68	9.68	1,355.00	1,464	4,897	336	130	1	1
GRAND TOTAL											4.84	9.68	9.68	1,355.00	1,464	4,897	336	130	1	1