

PROJECT NO.	SHEET NO.	TOTAL NO.
2023CPT.08.17.20761	12	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANE S	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGT H	WIDT H	1245000000-E	1260000000-E	1297000000-E	1330000000-E	1519000000-E	1575000000-E	1704000000-E	1775000000-E	1838000000-E	1838500000-N	2143000000-E	
												SHOULDER RECONSTRUCTION	AGGREGATE SHOULDER BORROW	1.5" MILLING	INCIDENTAL MILLING	SURFACE COURSE, \$9.5B	ASPHALT BINDER FOR PLANT MIX	PATCHING EXISTING PAVEMENT	ASPHALT SURFACE TREATMENT, MATCOAT, #67 STONE	EMULSION FOR ASPHALT SURFACE TREATMENT	VACUUM TRUCK	BLOTTING SAND	
											MI	FT	SMI	TON	SY	SY	TONS	TONS	TONS	SY	GAL	WK	TON
2023CPT.08.17.20761	Randolph	1	SR 1332 GARREN TOWN RD.	(FROM: US HWY 64 W. TO: SR1317 GOLDEN MEADOW RD.)	2	2	2WU	NO	NO	4.29	22	8.58	1,201.00		520	5,105	352	200	60,906.00	24,362	3.00	2	
TOTAL FOR MAP NO. 1											4.29		8.58	1,201.00		520	5,105	352	200	60,906.00	24,362	3.00	2
2023CPT.08.17.20761	Randolph	2	SR 1329 JACKSON RD.	(FROM: SR1328 SAWYERSVILLE RD. TO: SR 1318 MOORE RD.)	2	2	2WU	NO	NO	0.07	18	0.14	20.00			61	6	15	739.00	296	0.10	2	
TOTAL FOR MAP NO. 2											0.07		0.14	20.00			61	6	15	739.00	296	0.10	2
2023CPT.08.17.20761	Randolph	3	SR 1318 MOORE RD.	(FROM: SR 1193 OLD NC-49 TO: US-HWY 64)	2,3	2	2WU	NO	NO	3.74	22	7.48	1,051.00	325	245	4,381	297	75	53,100.00	21,240	2.60	2	
TOTAL FOR MAP NO. 3											3.74		7.48	1,051.00	325	245	4,381	297	75	53,100.00	21,240	2.60	2
2023CPT.08.17.20761	Randolph	4	SR 1411 JARVIS MILLER RD.	(FROM: US-64 W TO: SR 1413 MOUNTAIN VIEW CHURCH RD.)	1	2	2WU	NO	NO	1.95	20	4.29	603.00		520	2,364	161	60					
TOTAL FOR MAP NO. 4											1.95		4.29	603.00		520	2,364	161	60				
2023CPT.08.17.20761	Randolph	5	SR 3156 RACE TRACK RD.	(FROM: SR 1415 OLD COUNTY FARM RD. TO: END OF MAINTENANCE)	1	2	2WU	NO	NO	0.51	18	1.02	143.00		260	529	38	50					
TOTAL FOR MAP NO. 5											0.51		1.02	143.00		260	529	38	50				
2023CPT.08.17.20761	Randolph	6	SR 1415 OLD COUNTY FARM RD.	(FROM: SR 1004 CARAWAY MOUNTAIN RD. TO: SR 1518 LAKE LUCAS RD.)	1	2	2WU	NO	NO	3.79	24	7.58	1,065.00		2,340	4,843	344	400					
TOTAL FOR MAP NO. 6											3.79		7.58	1,065.00		2,340	4,843	344	400				
2023CPT.08.17.20761	Randolph	7	SR 1416 OLD LEXINGTON RD.	(FROM: SR 1004 CARAWAY MOUNTAIN RD. TO: SR 1411 JARVIS MILLER RD.)	1	2	2WU	NO	NO	3.26	20	6.46	907.00		1,170	3,620	247	100					
TOTAL FOR MAP NO. 7											3.26		6.46	907.00		1,170	3,620	247	100				
2023CPT.08.17.20761	Randolph	8	SR 1004 TRINITY RD.	(FROM: NC-62 TO: SR 1577 ARCHDALE RD.)	2	2	2WU	NO	NO	2.03	22	4.06	570.00		1,430	2,706	184	50	30,133.00	12,053	1.50	2	
TOTAL FOR MAP NO. 8											2.03		4.06	570.00		1,430	2,706	184	50	30,133.00	12,053	1.50	2
2023CPT.08.17.20761	Randolph	9	SR 1924 TOM BALL RD.	(FROM: GUILFORD COUNTY LINE TO: SR 1921 COLTRANE MILL RD.)	1	2	2WU	NO	NO	0.81	20	1.62	227.00		260	902	63	50					
TOTAL FOR MAP NO. 9											0.81		1.62	227.00		260	902	63	50				
2023CPT.08.17.20761	Randolph	10	SR 1921 COLTRANE MILL RD.	(FROM:SR 1926 HARLOW RD. TO: SR 1928 COLTRANE MILL RD.)	1	2	2WU	NO	NO	1.19	20	2.20	309.00		520	1,252	86	40					
TOTAL FOR MAP NO. 10											1.19		2.20	309.00		520	1,252	86	40				
TOTAL FOR PROJ NO. 2023CPT.08.17.20761											21.64		43.43	6,096.00	325	7,265	25,763	1,778	1,040	144,878.00	57,951	7.20	8
GRAND TOTAL											21.64		43.43	6,096.00	325	7,265	25,763	1,778	1,040	144,878.00	57,951	7.20	8