

PROJECT NO.	SHEET NO.	TOTAL NO.
2023CPT.14.02.10871	8	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	1297000000-E		1503000000-E	1523000000-E	1575000000-E	1577000000-E	1704000000-E	1839140000-E
												1½" MILLING	4" MILLING	INTERMEDIATE COURSE, I19.0C	SURFACE COURSE, S9.5C	ASPHALT BINDER FOR PLANT MIX	POLYMER MODIFIED ASPHALT BINDER FOR PLANT MIX	PATCHING EXISTING PAVEMENT	ULTRA-THIN BONDED WEARING COURSE
												MI	FT	SY	SY	TONS	TONS	TONS	TONS
2023CPT.14.02.10871	Swain	1	US 74 WEST	SR 1190 (MP 2.38) TO US 19 ALARKA RD (MP 7.88)	1	2	MD	NO	NO	5.5	32	49,488	42,592	6,070	7,735	819	180	1,325	3,471
TOTAL FOR MAP NO. 1										5.5		49,488	42,592	6,070	7,735	819	180	1,325	3,471
2023CPT.14.02.10871	Swain	2	US 74 EAST	US 19 ALARKA RD (MP 17.01) TO SR 1190 (MP 22.5)0	1	2		NO	NO	5.49	32	49,743	43,460	6,059	7,750	820	181	1,322	3,477
TOTAL FOR MAP NO. 2										5.49		49,743	43,460	6,059	7,750	820	181	1,322	3,477
2023CPT.14.02.10871	Swain	3	ON RAMP MP 69 WB	FROM SR 1190 TO US 74 W	2	2		NO	NO	0.19	24	2,948			248	15			
TOTAL FOR MAP NO. 3										0.19		2,948			248	15			
2023CPT.14.02.10871	Swain	4	OFF RAMP MP 67 WB	FROM US 74 TO US 19	2	2	MD	NO	NO	0.235	24	2,895			336	20			
TOTAL FOR MAP NO. 4										0.235		2,895			336	20			
2023CPT.14.02.10871	Swain	5	ON RAMP MP 67 WB	FROM US 19 TO US 74	2	2	MD	NO	NO	0.192	24	3,620			304	18			
TOTAL FOR MAP NO. 5										0.192		3,620			304	18			
2023CPT.14.02.10871	Swain	6	OFF RAMP MP 64 WB	FROM US 74 TO US 19 (ALARKA RD)	2	2	MD	NO	NO	0.12	24	2,169			183	11			
TOTAL FOR MAP NO. 6										0.12		2,169			183	11			
2023CPT.14.02.10871	Swain	7	OFF RAMP MP 67 EB	FROM US 74 TO SR 188 (VETRANS BLVD)	2	2	MD	NO	NO	0.14	24	2,343			197	12			
TOTAL FOR MAP NO. 7										0.14		2,343			197	12			
2023CPT.14.02.10871	Swain	8	ON RAMP MP 67 EB	FRFROM SR 188 TO US 74	2	2	MD	NO	NO	0.1	25	1,726			146	9			
TOTAL FOR MAP NO. 8										0.1		1,726			146	9			
2023CPT.14.02.10871	Swain	9	OFF RAMP MP 69 EB	FROM US 74 TO SR 1190	2	2	MD	NO	NO	0.16	24	2,681			226	14			
TOTAL FOR MAP NO. 9										0.16		2,681			226	14			
TOTAL FOR PROJ NO. 2023CPT.14.02.10871										12.127		117,613	86,052	12,129	17,125	1,738	361	2,647	6,948
GRAND TOTAL										12.127		117,613	86,052	12,129	17,125	1,738	361	2,647	6,948