

## DECK SURFACE REPAIR QUANTITY TABLE

SPAN B

	ESTIMATE	ACTUAL
CONCRETE DECK REPAIR FOR SILANE DECK TREATMENT	0.0 CU. FT	
CONCRETE REPAIR	0.0 CU.FT.	
BRIDGE JOINT DEMOLITION	0.0 SQ.FT.	
SHOTBLASTING BRIDGE DECK	1172.0 SQ. YDS.	
SILANE DECK TREATMENT	1172.0 SQ. YDS.	
SURFACE PREPARTAION FOR CONCRETE BARRIER RAIL	790.0 SQ.FT.	
SILANE BARRIER RAIL TREATMENT	790.0 SQ.FT.	

## **NOTES**

DECK SURFACE REPAIR QUANTITIES REPRESENT ESTIMATED VALUES OF CLASS II SURFACE PREPARATION AND CONCRETE DECK REPAIR AFTER REMOVAL OF UNSOUND CONCRETE. (MIN. 2" CLEAR TO SAWCUT). SEE CONCRETE FOR DECK REPAIR SPECIAL PROVISION.

REPAIR LOCATIONS AND ESTIMATED QUANTITIES ARE BASED ON THE BEST INFORMATION AVAILABLE. IF ADDITIONAL REPAIRS NOT SHOWN ON THE DRAWINGS ARE DEEMED NECESSARY BY THE ENGINEER, THE ENGINEER WILL NOTE ON THE DRAWINGS THE APPROXIMATE LOCATIONS AND DESCRIPTION OF THE REPAIRS AND ENTER THE ACTUAL QUANTITIES INTO THE REPAIR QUANTITY TABLE.



CONCRETE REPAIR AREA

PROJECT NO. 15BPR.59

WAKE COUNTY
BRIDGE NO. 911084



DEPARTMENT OF TRANSPORTATION
RALEIGH

DECK SURFACE REPAIR

SPAN B

12/08/2022

REVISIONS SHEET NO. BY: DATE: NO. BY: DATE: S4-04

FINAL UNLESS ALL SIGNATURES COMPLETED 2 4 2 21

DRAWN BY: D.A. CANTRELL
CHECKED BY: A.Y. GODFREY
DESIGN ENGINEER OF RECORD: N.A. PIERCE

DATE: 03/2021
DATE: 10/2022
DATE: 12/2022

12/7/2022 R:\Structures\Plans\404\_007\_15BPR59\_SMU\_DSR02\_S4-04\_911084.dgn napierce SPAN B